				UTAH OIL AND	GAS CONSER	VATION CO	MMISSION			
REMARKS:	WELL LOG	ELE(	CTRIC LOGS	X wa	TER SANDS	LOÇATIO	N INSPECTED _		SUB. REPORT/abd.	
CON	ridentis	al Sha	AUS EMO	1-21	-95	160401	Oper Nm.	cha.		
						•		8		
*										
			<u> </u>				·			
DATE FILED		12-14-	93							
LAND: FEE &	PATENTED	STATE L	EASE NO.		PUBLIC	LEASE NO. T	J <b>–</b> 007978		INDIAN	
DRILLING AP	PROVED:	12-20-	93	· ,						
SPUDDED IN:	0-14	-94								
COMPLETED:	<u> 3-91-</u>	94 120		OING: 3-20-1	94					
INITIAL PROD			BOPD: 2	20 mcf:						
GRAVITY A.P.	5	Н	· · · · · · · · · · · · · · · · · · ·					<u> </u>		
GOR:	<u> </u>									
PRODUCING	ZONES:	MO3-1	4104 (	SRRV)						
TOTAL DEPT	H:	5700'								
WELL ELEVAT	TION:	5318	10 GR				-			
DATE ABAND	ONED:					<del> </del>				
FIELD:		MONUME	NT BUTTE		,			······		
UNIT:										
COUNTY:		DUCHES								81108
WELL NO.				FEDERAL 33				API	NO. 43-013	
LOCATION	1980'	FSL FI	. FROM (N) (S) LINE,	1980' FEL	FT. F	ROM (E) (W) LII	VE. NW SE		1/4 — 1/4 SEC.	8 .
				·				1,16		
TWP.	RGE.	SEC.	OPERATOR	4		TWP.	RGE. SE	C. OPERATO	OR .	
<b>9</b> S	17E	8	EQUITABLE	RESOURCES						



1601 Lewis Avenue P.O. Box 21017 Billings, MT 59104



Office: (406) 259-7860 FAX: (406) 245-1365 [] FAX: (406) 245-1361 []

DIVISION OF OIL. GAS & MINING

December 13, 1993

-- VIA FEDERAL EXPRESS --

Bureau of Land Management 170 South 500 East Vernal, UT 84078

Gentlemen:

Enclosed are Applications for Permit to Drill the following wells:

Balcron Monument Federal #33-8

Balcron Monument Federal #34-7

As operator, we hereby request that the status of this well be held TIGHT for the maximum period allowed by Federal and State regulations.

Sincerely,

Bobbie Schuman

Coordinator of Operations,

Environmental and Regulatory Affairs

/rs

Enclosures

cc: Utah Division of Oil, Gas and Mining

(3/89)

本を支持の大学のな

DIVISION OF OIL, GAS AND	HINING	5. Lenze Verignation and Serial No.
•		Federal # U-007978
APPLICATION FOR PERMIT TO DRILL, DE	EPEN, OR PLUG BACK	6. If Indian, Alinttee or Tribe Name
Type of Work		n/a 7. Unit Agreement Name
DRILL 🛛 DEEPEN 🗌	PLUG BACK	n/a
Type of Well OII XX Gas C Other	Single Multiple Zone	3. Farm or Lense Namo
		Balcron Monument Federal
Equitable Resources Energy Company, Ba	Teron UII DIVISION	9. Well No.
Address of Operator		#33-8
P.O. Box 21017; Billings, MT 59104  Location of Well (Report location clearly and in accordance with any	State requirements.*)	Monument Butte/Green River
1980' FSL, 1980' FEL	anne requirement r	11. QQ, Sec., I., R., H., or Blk. and Survey or Area
At proposed prod. zone NW SE Section	8. T9S. R17F	·
•		NW SE Sec. 8, T9S, R17E
Distance in miles and direction from neurest town or post office.	16 miles couthwest	Duchesne UTAH
From Myton, Utah, approximately	is. No. of acres in lease lie No.	of agres assigned
location to nearest property or last line, ft. (Also to nearest drig, line, if any)	to .	this well
(Also to nearest drig, line, if any)  Distance from proposed locations	ly. Proposed depth 20. Ro	tary or cable tools
. Distance from proposed locations to nearest well, drilling, completed, or applied for, on this lease, ft.	6,000'	Rotary
. Elevations (Show whether DF, RT, GR, etc.)		22. Approx. date work will start* Upon APD approval
GL 5318.6'		opon Arb approvat
PROPOSED CASING	AND CEMENTING PROGRAM	
Size of Hole Size of Casing Weight per Foot	Setting Depth	Quantity of Cement
See attached		
Operator plans to drill this well in a for Permit to Drill.	accordance with the at	cached Federal Application
•	•	
· .		DEC 4 4 4002
	•	DEC 1 4 1993 .
		700 24 64 65 2 7 7 7
	·	DIVISION OF
I ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is		THE CAC O SEIZERIA
	to deepen or plug back, give data on	present productive zone and proposed hem pro-
ective zone. If proposal is to drill or deepen directionally, give pertine	s to deepen or plug back, give data on ent data on subsurface locations and m	present productive zone and proposed hew pro- rasured and true vertical depths. Give blowout
ective zone. If proposal is to drill or deepen directionally, give pertind aventer program, if any.	hast of my knowledge.	ranged and true vertical meptile. Offe dismost
nctive zone. If proposal is to drill or deepen directionally, give pertind eventer program, if any.  I hereby cartify that this report is true and complete to the	best of my knowledge.  Coordinator of Enviro	nmental December 13, 1993
nctive zone. If proposal is to drill or deepen directionally, give pertind eventer program, if any.  I hereby cartify that this report is true and complete to the	hast of my knowledge.	nmental December 13, 1993
nctive zone. If proposal is to drill or deepen directionally, give pertind eventer program, if any.  I hereby cartify that this report is true and complete to the	best of my knowledge.  Coordinator of Enviro	nmental December 13, 1993
ective zone. If proposal is to drill or deepen directionally, give pertind aventer program, if any.  I hereby captify that this report is true and complete to the Signed Dobbie Schuman. Title	best of my knowledge.  Coordinator of Enviro	nmental December 13, 1993
ective zone. If proposal is to drill or deepen directionally, give pertind aventer program, if any.  I hereby captify that this report is true and complete to the Signed Dobbie Schuman. Title	best of my knowledge. Coordinator of Environment of Courtinator of Courtinator Affai	December 13, 1993  APPROVED BY THE STATE
eventer program, if any.  I hereby cartify that this report is true and complete to the Signed Schuman Title (This approved by 13 - 013 - 31407  Approved by Title	best of my knowledge.  Coordinator of Environment Regulatory Affai	nmental December 13, 1993
ictive zone. If proposal is to drill or deepen directionally, give pertind aventer program, if any.  I hereby cartify that this report is true and complete to the Signed Schuman Title (This appear of Federal or State office use)  API NO	best of my knowledge. Coordinator of Environment Regulatory Affai	APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING
eventer program, if any.  I hereby cartify that this report is true and complete to the Signed Schuman Title (This approved by 13 - 013 - 31407  Approved by Title	best of my knowledge. Coordinator of Environment Regulatory Affai	APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING DATE:
ictive zone. If proposal is to drill or deepen directionally, give perting avenue program, if any.  I hereby cartify that this report is true and complete to the Signed Schuman Title (This appear of the fairn of State office use)  API NO	best of my knowledge. Coordinator of Environment Regulatory Affai	APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING
ictive zone. If proposal is to drill or deepen directionally, give perting avenue program, if any.  I hereby cartify that this report is true and complete to the Signed Schuman Title (This appear of the fairn of State office use)  API NO	best of my knowledge.  Coordinator of Environment Regulatory Affairment Date  Approval Date  tions On Reverse Side	APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING DATE:

Form 3160-3 (November 1983) (formerly 9-331C)

CONDITIONS OF APPROVAL, IF ANY :

## UNITED STATES DEPARTMENT OF THE INTERIOR

SUBMIT IN TRIPLICATE
(Other instructions on reverse side)


Form approved. Budget Bureau No. 1004-0136 Expires August 31, 1985

G. LEASE DESIGNATION AND SERIAL NO.

•	BUREAU OF	LAND MANAGEMEN	T	. •	U-007978		
A DDL ICATION		O DRILL, DEEPE		ACK	G. IF INDIAN, ALLOT	EMAN AGIST SO RET	
	TON PENMIN	O DIVILL, DELL'E	, 0		n/a		
lr. TYPE OF WORK DRII	LL 🛛	DEEPEN	PLUG BAC	K 🗆	7. UNIT AGENEMBAT	HAMM	
b. Tipe of wall			NOLE TO MULTIPL		· n/a S. farm or lease	N A V B	
	SLL OTHER	20					
. HAMB OF OPERATOR				TIAL -	Balcron Mont	ument Federal	
	<u>OURCES ENERGY CO</u>	OMPANY Balcron		11 ila	#33-8		
ADDRESS OF OPERATOR				-	10. FIELD AND POOR	, OR WILDCAT	
P.O. Box 2101	7; Billings, MT	59104 in accordance with any S	tate requirements.*)		Monument But	te/Green River	
At surface NW SF	Sec 8. T9S R	17 <b>£</b> 1980' F	SL. 1980' FEL		11. BRC., T., R., M., O		
At proposed prod. zon						8, T9S,R17E	
14. DISTANCE IN MILES A	ND DIRECTION FROM NEAR	EST TOWN OR POST OFFICE	•		12. COUNTY OR PAR	•	
From Myton	, Utah, approxi	mately 16 mile	s southwest.		Duchesne	HATU	
In DISTANCE PROM PROPU	BED?	. 18. NO	. OF ACRES IN LEASE	17. NO. OF	F ACRES ASSIGNED		
LOCATION TO NEAREST PROPERTY OR LEASE L (Also to nearest drig	INE, FT. , unit line, if any)						
18. DISTANCE PROM PROP TO NEAREST WELL, D OR APPLIED FOR, ON TH	OEED LOCATION®		OPOSED DEPTH	_	Rotary		
			6,000'	<u> </u>		WORK WILL START	
21. ELEVATIONS (Show who					Upon APD a		
GL 5318.			A CHICANOLINA DECORA		1 00011 711 0	<u> </u>	
<b>20</b> ,	P	ROPOSED CASING AND	,	1			
SIZE OF ROLE	. BIZE OF CABING	WEIGHT PER FOOT	SETTING DEPTH	.	QUANTITY OF CE	HENT	
	<u></u>	See att	h chod	.			
		See all	acheu				
						A PRICIALITY	A.
EXHIBITS A	TTACHED	•				Mark Street	
"A" DDODOS	ED DRILLING PRO	ICP AM	· "H" BOPE DIA	GRAM		1111	
	SED SURFACE USE		"I" EXISTING		(Map A)	DEC 1 A 1993	Ž
	IC PROGNOSIS	1 Hours	"J" PLANNED			* 58 <b>19 36</b>	4
	NG PROGRAM/CASI	NG DESIGN	"K" EXISTING			Dillosai a	fram
	DECLARATION		"L" CUT & FI			DIVISION 6	4.0
"F" SURVEY			"M" ARCHEOLO	GY REPO	ORT	OIL, GAS & MIR	4
"G" RIG LA	YOUT		"N" PROPOSED	KODOC	TION FACILITY	I DIAGRAM	
•	• •	•	•		•		
SELF CERTIFICATION	: I hereby certify	that I am authorize	ed, by proper lease	interest	t owner, to con	duct these	
operations associa	ted with the applica	ation. Bond coverag	ge pursuant to 43 C	FR_3104 f	for lease activ	itles is	
being provided by	Equitable Resources	Energy Company as	principal and Safec	o Insurar	nce Company of	America as	
surety under BLM Bo	ond No. MT 0576 (Na	tionwide Oil & Gas I	Bond #554/188) v/no	Mill be t	responsible for	corp rance	
with all of the ter	THE BRODGER PROGRAM: If	of that portion of proposal is to deepen or	THE TEASE ASSOCIATE	O WILL U	inctive rone and bro	posed new productive	
zone. If proposal is to	drill or deepen directions	proposal is to deepen or ; ally, give pertinent data	on subsurface locations a	nd measured	d and true vertical d	lepths. Give blowout	
preventer program, if an	//		dimeter of Co.		n+a7	······································	
KOAD.	in labuma.		ordinator of En		. De	cember 13, 1993	
BONED PORDE	e Schuman	ZITLE_d	nd Regulatory A	Hall'S	DATE		
(This space for Fede	eral or State office use)				•		
	•		APPROVAL DATE				
PERMIT NO.			ALENVIRU UNAH			: · · <del></del>	
. APPROVED BY	·•	TITLE			PATM,		
. ~							


#### T9S, R17E, S.L.B. & M.

S 89°56' W' (GLO)



#### EQUITABLE RESOURCES ENERGY CO.

WELL LOCATION, BALCRON MONUMENT FEDERAL #33-8, LOCATED AS SHOWN IN THE NW 1/4 SE 1/4 OF SECTION 8, T9S, R17E, S.L.B. & M, DUCHESNE COUNTY UTAH.





X = SECTION CORNERS LOCATED

BASIS OF BEARINGS; G.L.O. PLAT 1911

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SE)

WEATHER: CLEAR & WARM

DATE: 11/6/93 SCALE: 1" = 1000'

SURVEYED BY: GS HW

FILE: 33-8

TRI — STATE
LAND SURVEYING. INC.
38 WEST 100 NORTH, VERNUL, UTAN 84078.
801—781—2801

EXHIBIT "A"
Proposed Drilling Program
Page 1

# EQUITABLE RESOURCES ENERGY COMPANY Balcron Oil Division Balcron Monument Federal #33-8 NW SE Section 8-T9S-R17E Duchesne County, Utah

In accordance with requirements outlined in 43 CFR 3162-3.1 (d):

1. ESTIMATED IMPORTANT GEOLOGICAL MARKERS:

See Geologic Prognosis (EXHIBIT "C")

2. ESTIMATED DEPTHS OF ANTICIPATED OIL, GAS OR WATER:

See Geologic Prognosis (EXHIBIT "C)

- 3. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:
  - a. EXHIBIT "H" is a schematic of the BOP equipment and choke manifold. A 2M system will be used. The BOPE will be installed after setting 8-5/8" casing at 260'. The blind rams and pipe rams will be tested to 1500 psi. Pipe rams will be operationally checked each 24-hour period and blind rams each time pipe is pulled out of the hole.
  - b. The BOPE will be tested to 1500 psi when initially installed, whenever any seal subject to test pressure is broken, and following related repairs. The pipe and blind rams will be activated at least weekly and on every trip the pipe and blind rams will be activated.
  - c. An accumulator of sufficient capacity to open the hydraulically-controlled choke valve lines (if so equipped), close all rams, and retain a minimum of 200 psi above precharge on the closing manifold without the use of the closing unit pumps will be installed during the drilling of this well.
  - d. An upper kelly cock will be used during the drilling of this well.
  - e. Visual mud monitoring equipment will be used to detect volume changes indicating loss or gain in circulating fluid volume.
  - f. Sufficient quantities of mud materials will be maintained or readily accessible for the purpose of assuring well control.

EXHIBIT "A"
Proposed Drilling Program
Page 2

#### 4. PROPOSED CASING AND CEMENTING PROGRAM:

- a. Surface casing will be set in the Uinta formation to approximately 260' and cemented to surface.
- b. All potentially productive hydrocarbon zones will be isolated.
- c. Casing designs are based on factors of burst: 1.25, collapse: 1.125, and joint strength: 1.8.
- d. All casing strings will be pressure tested to 0.22 psi/ft. of casing string length or 1500 psi whichever is greater (not to exceed 70% of yield).
- E. For details of casing, cement program, drilling fluid program, and proposed mud program, see the following two attachments:

Drilling Program/Casing Design (EXHIBIT "D")
Geologic Prognosis (EXHIBIT "C")

#### 5. HAZARDOUS PRESSURES, TEMPERATURES, FLUIDS/GASSES EXPECTED:

- a. Expected bottom hole temperature is 125 degrees F. Expected bottom hole pressure is 1500 psi.
- b. No abnormal pressures or temperatures have been noted or reported in wells drilled to the Green River formation in this area.
- c. No dangerous levels of hydrogen sulfide, hazardous fluids, or gasses have been found, reported, or known to exist at the depth to be drilled in this well, in this area.

#### 6. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:

- a. The drilling operations for this well will begin as soon after APD approval as possible.
- b. These drilling operations should be completed within 12 days after spudding the well depending on weather and hole conditions.
- c. If the well is productive, a sundry notice and plat showing exact installed facilities will be submitted.
- d. If this well is non-productive, a sundry notice will be filed with the BLM District Office within 30 days following completion of the well for abandonment.

#### Multi-Point Surface Use and Operations Plan

EQUITABLE RESOURCES ENERGY COMPANY
BALCRON OIL DIVISION
BALCRON MONUMENT FEDERAL #33-8
NW SE SECTION 8, T9S, R17E
DUCHESNE COUNTY, UTAH

#### 1. Existing Roads: Refer to Maps "A" & "B" (shown in RED)

- A. The proposed well site is staked and four reference stakes are present. 150' & 200' SE and 225' & 275' SW.
- B. The Monument Federal #33-8 is located 16 miles Southwest of Myton Utah in the NW1/4 SE1/4 Section 18, T9S, R17E, SLB&M, Duchesne County, Utah. To reach the 42-18, proceed West from Myton, Utah along U.S. Highway 40 for 1.6 miles to the junction of this highway and Sand Wash road; Proceed South along the Sand Wash road approximately 10.6 miles to a road intersection, turn right and continue 1.0 miles to road intersection. Turn right and proceed 0.3 mile proposed access road sign. Follow flags 150 feet to location.
- C. Access roads refer to Maps "A" and "B".
- D. Access roads within a one-mile radius refer to map "B".
- E. The existing roads will be maintained in the same or better condition as existed prior to the commencement of operations and said maintenance will continue until final abandonment and reclamation of the well location.

#### 2. Planned Access Roads: Refer to Map "B"

Approximately 150 feet of new road construction will be required for access to the proposed well location.

A. Width - maximum 30-foot overall right-of-way with an 18foot road running surface, crowned & ditched and/or sloped and dipped. B. Construction standard - the access road will be constructed so as to conform to the standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development. (1989)

The road will be constructed to meet the standards of the anticipated traffic flow and all-weather requirements. Construction will include ditching, draining, crowning, and capping or sloping and dipping the roadbed as necessary to provide a well constructed and safe road. Prior to construction/upgrading, the roadway shall be cleared of any snow cover and allowed to dry completely. Traveling off of the thirty (30) foot right-of-way will not be allowed.

Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossing shall be designed so they will not cause siltation or the accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts.

Upgrading shall not be allowed during muddy conditions.

Should mud holes develop, they shall be filled in and detours around them avoided.

- C. Maximum grade Less than 8%
- D. Turnouts no turnouts will be required on this access road.
- E. Drainage design the access road will be crowned and ditched or sloped and dipped, and water turnouts installed as necessary to provide for proper drainage along the access road route.
- F. Culverts, cuts and fills no culverts will be required.

  There are no major cuts and/or fills on/along the proposed access road route.
- G. Surface materials all construction materials will be native material taken from onsite.
- H. Gates, cattlequards or fence cuts none required.
- I. Road maintenance during both the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and

will be maintained in accordance with the original construction standards. All drainage ditches and culverts will be kept clear and free-flowing, and will also be maintained in accordance with the original construction standards. The access road right-of-way will be kept free of trash during operations.

- J. The proposed access road has been centerline flagged.
- K. If a right-of-way is required please consider this APD the application for said right-of-way.

#### Location of Existing Wells Within a One-Mile Radius:

Please Refer to Map "C"

- A. Water wells none known.
- B. Abandoned wells see Map "C"
- C. Temporarily abandoned wells none known.
- D. Disposal wells none known.
- E. Drilling wells none known.
- F. Producing wells see Map "C".
- G. Shut-in wells none known.
- H. Injection wells none known.
- I. Monitoring wells none known.

### 4. Location of Existing and/or Proposed Facilities Owned by Equitable Resources Energy Company Within a One-Mile Radius:

- A. Existing
  - 1. Tank batteries see Map "C".
  - 2. Production facilities see Map "C".
  - Oil gathering lines none.
  - 4. Gas gathering lines see Map "C".
- B. New Facilities Contemplated
  - 1. All production facilities will be located on the disturbed portion of the well pad and at a minimum of twenty-five (25) feet from the toe of the backslope or toe of the fill slope.

  - 3. Production facilities will be accommodated on the

existing well pad. Construction materials required for installation of the production facilities will be obtained from the site; any additional materials required will be purchased from a local supplier having a permitted (private) source of materials within the area.

A dike will be constructed completely around those production facilities which contain fluids (i.e. production tanks, produced water tanks and/or heater treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

- 4. All permanent (onsite for six months or longer) above the ground structures constructed or installed including pumping units) will be painted Desert Brown. All production facilities will be painted within six (6) months of installation. Facilities required to comply with Occupational Health and Safety Act Rules and Regulations will be excluded from this painting requirement.
- C. The production (emergency) pit will be 12'x12' and will be fenced. Said fence will be maintained in good condition.
- D. During drilling and subsequent operations, all equipment and vehicles will be confined to the access road right-of-way and any additional areas as specified in the approved Application for Permit to Drill.
- E. Reclamation of disturbed areas no longer needed for operation will accomplished by grading, leveling and seeding as recommended by the Bureau of Land Management.

#### For Pipeline:

- F. Any proposed pipelines will be submitted to the authorized officer Via Sundry Notice for approval of subsequent operations.
- G. Equitable Resources Energy Company shall be responsible for road maintenance from the beginning to completion of operations.

#### 5. Location and Type of Water Supply

A. Water to be used for the drilling of these wells will be

hauled by truck over the roads described in item #1 and item #2, from a well owned by Owen Dale Anderson of Vernal Utah or from a spring owned by Joe Shields of Myton Utah. Source will be determined by sundry notice closer to the beginning of drilling operations.

B. No water well will be drilled on this location.

#### 6. Source of Construction Materials

- A. No construction materials are needed for drilling operations. In the event of production, the small amount of gravel needed for facilities will be hauled in by truck from a local gravel pit over existing access roads to the area. No special access other than for drilling operations and pipeline construction is needed.
- B. All access roads crossing Federal land are described under item #2, and shown on Map #A.

All construction material for these location sites and access roads shall be borrowed material accumulated during the construction of the location sites and access roads. No additional construction material from other sources is anticipated at this time, if in the future it is required the appropriate actions will be taken to acquire it from private sources.

- C. All surface disturbance area is on B.L.M. lands.
- D. There are no trees on this location.

#### 7. Methods of Handling Waste Materials:

- A. Cuttings the cuttings will be deposited in the reserve pit.
- B. Drilling fluids including salts and chemicals will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within one hundred twenty (120) days after termination of drilling and completion activities.

In the event adverse weather conditions prevent removal of the fluids from the reserve pit within this time period, an extension may be granted by the Authorized Officer upon receipt of a written request from Equitable Resources Energy Company. The reserve pit will be constructed so as not to leak, break, or allow discharge. The reserve pit will be lined with a 12 mil plastic reinforced liner.

C. Produced fluids - liquid hydrocarbons produced during completion operations will be placed in test tanks on the location. Produced waste water will be confined to a lined pit (reserve pit) or storage tank for a period not to exceed ninety (90) days after initial production. During the ninety (90) day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with the required water analysis, shall be submitted for the Authorized Officer's approval. Failure to file an application within the time frame allowed will be considered an incidence of noncompliance.

Any spills of oil, gas, salt water or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

- D. Sewage self-contained, chemical toilets will be provided for human waste disposal. Upon completion of operations, or as needed, the toilet holding tanks will be pumped and the contents thereof disposed of in the nearest, approved, sewage disposal facility.
- E. Garbage and other waste material garbage, trash and other waste materials will be collected in a portable, self-contained and fully-enclosed trash cage during drilling and completion operations. Upon completion of operations (or as needed) the accumulated trash will be disposed of at an authorized sanitary landfill. No trash will be burned on location or placed in the reserve pit.
- F. Immediately after removal of the drilling rig, all debris and other waste materials not contained in the trash cage will be cleaned up and removed from the well location. No adverse materials will be left on the location. Any open pits will be fenced during the drilling operation and the fencing will be maintained until such time as the pits are backfilled.
- G. The reserve and/or production pit will be constructed on the existing location and will not be located in natural drainages where a flood hazard exists or surface runoff will destroy or damage the pit walls. All pits will be constructed so as not to leak, break, or allow the discharge of liquids therefrom.

#### 8. Ancillary Facilities:

None anticipated.

#### 9. Wellsite Layout:

- A. Plat #1 shows the drill site layout as staked. Cross sections have been drafted to visualize the planned cuts and fills across the location. An average minimum of six (6) inches of topsoil will be stripped from the location (including areas of cut, fill, and/or subsoil storage) and stockpiled for future reclamation of the well site. Refer to Figure #1 for the location of the topsoil and subsoil stockpiles. The reserve pit will be on the West side of location. The flare pit will be located downwind of the prevailing wind direction on the West near corner #4. Access will be from the Northeast near corner #8.
- B. Plat #2 is a diagram showing the rig layout. No permanent living facilities are planned. There may be as many as three (3) trailers on location during drilling operation.
- C. A diagram showing the proposed production facility layout will be submitted to the Authorized Officer via Sundry Notice (Form 3160-5) for approval of subsequent operations.
- D. The reserve pit will be constructed so as to be capable of holding 12,000 bbls. of fluid.

The reserve pit will be lined with a 12 mil plastic liner, it will be torn and perforated after the pit dries and before backfilling of the reserve pit.

- E. Prior to the commencement of drilling operations, the reserve pit will be fenced on three (3) sides using 39-inch net wire with one strand of barbed wire on top of the net wire. The net wire will be no more than two inches above the ground. the barbed wire will be three inches above the net wire. total height of the fence will be at least 42-inches.
  - Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
  - 2. Standard steel, wood, or pipe posts shall be used between the corner braces. The maximum distance between any two (2) posts shall be no greater than sixteen (16) feet.
  - 3. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The fourth side of the reserve pit will be fenced immediately upon removal of the drilling rig and the fencing will be maintained until the pit is backfilled.

F. Any hydrocarbons on the pit will be removed from the pit as soon as possible after drilling operations are completed.

#### 10. Plans for Reclamation of the Surface:

The B.L.M. will be contacted prior to commencement of any reclamation operations.

#### A. Production

- Immediately upon well completion, the well location and surrounding area(s) will be cleared of all debris, materials, trash and junk not required for production.
- Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with 43 CFR 3162.7-1.
- 3. The plastic pit liner shall be torn and perforated before backfilling of the reserve pit.
- 4. Before any dirt work to restore the location takes place, the reserve pit will be completely dry and all cans, barrels, pipe, etc. will be removed.
  - Other waste and spoil materials will be disposed of immediately upon completion of drilling and workover activities.
- 5. The reserve pit and that portion of the location and access road not needed for production facilities/operations will be reclaimed within one hundred twenty (120) days from the date of well completion, weather permitting.
- 6. If the well is a producer, Equitable Resources Energy Company will, upgrade and maintain access roads as necessary to prevent soil erosion, and accommodate year round traffic. Reshape areas unnecessary to operations, distribute topsoil, disk and seed all disturbed areas outside the work area according to the recommended seed mixture. Perennial vegetation must be established. Additional work shall be required in case of seeding failures, etc.

If the well is abandoned/dry hole, Equitable Resources

Energy Company will, restore the access road and location to approximately the original contours. During reclamation of the site, push the fill material into cuts and up over the backslope. Leave no depressions that will trap water or form ponds. Distribute topsoil evenly over the location, and seed according to the above seed mixture. The access road and location shall be ripped or dished prior to seeding. Perennial vegetation must be established. Additional work shall be required in case of seeding failures, etc.

Seedbed will be prepared by disking, then roller packing following the natural contours. Seed will be drilled on contours at a depth no greater than one-half inch (1/2"). In areas that cannot be drilled, seed will be broadcast at double the seeding rate and harrowed into soil. Certified seed will be used whenever available.

Fall seeding will be completed after September 1 and prior to prolonged ground frost. Spring seeding, to be effective, will be completed after the frost has left the ground and prior to May 15th.

7. Upon completion of backfilling, leveling and recontouring, the stockpiled topsoil will be evenly spread over the reclaimed area(s). Prior to reseeding, all disturbed surfaces will be scarified and left with a rough surface. No depressions will be left that would trap water and form ponds. All disturbed surfaces will be reseeded with the seed mixture stipulated by the B.L.M.

Seed will be drilled on the contour to a approximate depth of one-half (1/2) inch. All seeding will be conducted after September 1 and prior to ground frost. Spring seeding will be done after the frost leaves the ground and no later than May 15. If the seeding is unsuccessful, Equitable Resources may be required to make subsequent seedings.

- B. Dry Hole/Abandoned Location
  - 1. On lands administered by the Bureau of Land Management, abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include:
    - (c) ensuring revegetation of the disturbed areas to the specifications of the Bureau of Land Management at

the time of abandonment.

2. All disturbed surfaces will be recontoured to the approximate natural contours and reseeded according to BLM specifications. Reclamation of the well pad and access road will be performed as soon as practical after final abandonment and reseeding operations will be performed in the fall or spring following completion of reclamation operations.

#### 11. Surface Ownership:

The well site and proposed access road are situated on surface lands administered by

Bureau of Land Management Vernal District Office Vernal, Utah

#### 12. Other Information:

A. Topographic and geologic features of the area (reference Topographic Map #A) are:

The proposed drill site is located in the Monument Butte oil field, which lies in a large basin formed by the Uinta Mountains to the North and the Bookcliff Mountains to the South. The site is located approximately 15 miles Northwest of the Green River, which is the major drainage for this area, and approximately 13 miles Southwest of Myton Utah.

This basin floor is interlaced with numerous canyons and ridges formed by the non-perennial streams of the area. The sides of these canyons are steep and ledges formed in sandstone, conglomerate deposits and shale are common in this area.

The geologic structures that are visible in the area are of the Uinta formation (Eocene Epoch) tertiary period and the cobblestone and younger alluvial deposits from the Quaternary period.

The soils in the semi-arid area of the Williams Fork Formation (Upper Cretaceous) and Wasatch Formation (Eocene) consist of light brownish gray clay (OL) to sand soil (SM-ML) type with poorly graded gravels.

Outcrops of sandstone ledges, conglomerate deposits and shale are common in this area.

The topsoils in the area range from a sandy clay (SM-ML) type soil to a clayey (OL) soil.

The majority of the numerous washes and draws in the area are of a non-perennial nature flowing during the early spring run-off and heavy rain storms of long duration which are rare as the normal annual rainfall in the area is only 8".

The flora of the area includes sagebrush, mountain mahogany, serviceberry, rabbit brush, greasewood, fourwing saltbush, Gambel scrub oak, willow, tamarack, shadscale, Spanish bayonet, indian rice grass, cheatgrass, wheatgrass, curly grass, crested wheatgrass, sweet clover, gum weed, foxtail, mustard, Canadian thistle, Russian thistle, Kochia, sunflowers and cacti.

The fauna of the area includes cattle, horses, elk, deer, coyotes, rabbits, rodents, lizards, bull snakes, rattle snakes, water snakes and horned toads. Birds of the area are ground sparrows, bluejays, bluebirds, magpies, ravens, rapters, morning doves, swallows, nighthawks, hummingbirds, and chukar.

- B. The surface ownership is Federal. The surface use is grazing and petroleum production.
- C. 1. The closest live water is the Green River which is approximately 15 miles Southwest of the proposed site.
  - 2. There are no occupied dwellings in the immediate area

  - 4. There are no reported restrictions or reservations noted on the oil and gas lease.
  - 5. A silt catchment dam will be constructed if determined necessary as a condition of approval.

#### 13. Lessee's or Operator's Representative:

Balcron Oil
a division of Equitable Resources Energy Company
1601 Lewis Avenue
P.O. Box 21017
Billings, Montana 59104
(8:00 a.m. to 5:00 p.m.)
(406)259-7860
FAX: (406)245-1361

Dave McCoskery, Drilling Engineer Home (406)248-3864

Dale Griffin, Home (303)824-3323

#### 14. certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that any statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Balcron Oil, a division of Equitable Resources Energy Company, and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Desember 13,1993

Bobbie Schuman
Coordinator of Environmental
and Regulatory Affairs
BALCRON OIL division of

Equitable Resources Energy Co.

## Balcron Oil Well Prognosis

Well Name BALCRON N	ONUMENT FEL	DERAL #33-8	;	Exploratory		Control W	ell	PAIUTE #34-8
Location NWSE SEC 8				Development	X			DMND SHMRK
County DUCHESNE	×			-	MON BUTTE		KB	5350
State UTAH					NWSE 8			SWSE 8
Total Depth 5700					98	Townsh		9S
GL (Ung) 5318.6	- FCT KR	5327			17E			17E
Gr (Oug) 3316.6		J321	•	160	1,1		·6·	
Formation Tops	Progn		-	. •	Control Wel	•		
Formation	Depth	Datum	Depth	Datum	Datum	Prog C	ntl	Deviation
UINTA	SURFACE						-	<u> </u>
GREEN RIVER	11435	3892			3922			
HORSEBENCH SS	2159	3168			3198			
2ND GARDEN GULCH	3764	1563			1593			
Y-2 SAND (PAY)	4041	1286			1316			······································
Y-3 SAND (PAY)	4090	1237			1267 1030			
Y-5 SAND (PAY)	4327	1000			973			
YELLOW MARKER	4384	943 778			808		$\dashv$	
DOUGLAS CREEK	4549 4616	711			731			· · · · · · · · · · · · · · · · · · ·
R-2 SAND (PAY)	4746	581			611		-	· · · · · · · · · · · · · · · · · · ·
R-5 SAND (PAY) 2ND DOUGLAS CREEK	4785	542			572		_	
GREEN MARKER	4919	408			438		$\neg$	4
G-3 SAND (PAY)	4997	330			360			
CARBONATE MARKER	5391	-64			-34			
B-1 SAND (PAY)	5425"	-98			+68			
TD	5700	······································						· · · · · · · · · · · · · · · · · · ·
		· · · · · · · · · · · · · · · · · · ·						
Samples	Т	OST,s			Wellsite Ge	ologist		
50' FROM 1400' TO 3850'		DST #1	NONE					
		DST #2			From:		to:	······································
10' FROM 3850' TO TD				<u></u>	- Address:			
<u>,</u>		DST #3			- Address:			· · · · · · · · · · · · · · · · · · ·
		DST #4			<b>.</b>			
					Phone #			wk.
Logs	C	Cores						hm.
DLL FROM SURF CSG TO T	D	Core #1	NONE		Fax#			
LDT/CNL FROM 3550' TO T		Core #2			-			
					Mud Logger	/Hot Wire		
		Core #4	<del></del>		Company:			
		COIC #4				(Yes/No	) VE	is
					-			
•	* * * * * * * * * * * * * * * * * * *				• -	TWO MAN		
Comments:								
					•	<u></u>		· ,··
					. Fax#			
Report To: 1st Name	: DAVE BICKERS	STAFF	Phone #	(406) 259-7860	wk.	245-2261		hm.
•	KEVEN REINSC		Phone #			248-7026		hm.
Prepared By: KKR			Phone #					hm.
r rehaten pl. WW	12/0/70		. I MOME !!		7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7			

#### Equitable Resources Energy Company Balcron Oil Division

#### DRILLING PROGRAM

WELL NAME: Monument Butte Area

PROSPECT/FIELD: Monument Butte

LOCATION: Twn.95 Rge.16E & 17E

COUNTY: Duchesne

STATE: Utah

TOTAL DEPTH: SEE APD COVER SHEET

HOLE SIZE

\_\_\_\_\_\_

INTERVAL

12 1/4" 0 to 260'
7 7/8" 260 to T.D.

CASING	INTERVAL	CASING					
STRING TYPE	FROM TO	SIZE WEIGHT	GRADE				
Surface Casing Production Casing		8 5/8" 24 #/Ft 5 1/2" 15.50#/Ft will be new, ST&C)	J-55 J-55				
CEMENT PROGRAM							
Surface	150 sacks 75% Class "G" 25% Poz with 2% CaCl and 1/4 #/Sk Flocele. ( Cement will be circulated to surface.)						
Production	250 sacks Th	ifty Lite and 400 sack	s 50-50 Poz				

#### PRELIMINARY DRILLING FLUID PROGRAM

TYPE	FROM	TO	WEIGHT	PLAS. VIS	YIELD POINT
Air and air mist Air/Air Mist/KCl Water	0	260 T.D.	N.A. 8.7-8.9		N.A. N.A.

depending on the drilling contractor either:

- a.) Drilling will be with air from surface to as deep as hohelitions allow. 2% KCl fluid will be used for the remainder of the hole.
- b.) Drilling will be done using 2% KCl water and gel.

#### COMMENTS

1.) No cores or DST's are planned.

#### BALCRON OIL CO.

Operator: BALCRON OIL	Well Name: MONUMENT BUTTE AREA
Project ID:	Location: Monument Butte, Utah

Design Factors: Design Parameters: : 1.125 Collapse psi/ft : 0.500 Mud weight ( 9.63 ppg) : 1.00 Shut in surface pressure : 2280 Burst : 1.80 (J) 8 Round psi/ft Internal gradient (burst) : 0.100 : 1.60 **Buttress** (J) Annular gradient (burst) psi/ft : 0.000 : 1.50 (B) Body Yield Tensile load is determined using air weight 0 lbs. Overpull Service rating is "Sweet"

	Length (feet)	Size (in.)	Weight (lb/ft)	Grade	Joint		epth eet)	Drift (in.)	Cost
1	SFC ȚO TD	5-1/2"	15.50	J-55	ST&C		APD SHEET	4.825	
	Load (psi)	Collapse Strgth (psi)	S.F.		Min Int ) Strgth (psi)	lield S.F.	Load (kips)	Tension Strgth (kips)	s.F.
1	2850	4040	1.418	2850	4810	1.69	88.35	5 202	2.29 J

Prepared by : McCoskery, Billings, MT Date : 11-30-1992 (Revised 8/30/93)

Remarks

The mud gradient and bottom hole pressures (for burst) are 0.500 psi/ft and 2,850 psi, respectively.

NOTE: The design factors used in this casing string design are as shown above. As a general guideline, Lone Star Steel recommends using minimum design factors of 1.125 - Collapse (with evacuated casing), 1.0 - Burst, 1.8 - 8 Round Tension, 1.6 - Buttress Tension, and 1.5 - Body Yield. Collapse strength under axial tension was calculated based on the Westcott, Dunlop and Kemler curve. Engineering responsibility for use of this design will be that of the purchaser. Costs for this design are based on a 1990 pricing model. (Version 1.0G) A. Hazardous chemicals 10,000 pounds of which will most likely be used, produced, stored, transported, or disposed of in association with the proposed action of drilling, completing and producing this well:


We anticipate that none of the hazardous chemicals in quantities of 10,000 pounds or more will be associated with these operations.

B. Extremely hazardous substances threshold quantities (per Howard Cleavinger 11/30/93) of which will be used, produced, stored, transported, or disposed of in association with the proposed action of drilling, completing and producing this well:

We anticipate that none of the extremely hazardous substances in threshold quantities per 40 CFR 355 will be associated with these operations.

12/1/93 Revised 12/7/93 /rs


# EQUITABLE RESOURCES ENERGY CO. WELLSITE LAYOUT





TRI-STATE
LAND SURVEYING, INC.
38 WEST 100 MORTH, VERNAL, UIAH 84078
801-781-2501


ADJ... CHOKE

#3000\_STACK\_\_\_














# ARCHEOLOGICAL - ENVIRONMENTAL RESEARCH CORPORATION 23-2

P. O. Box 853 Bountiful, Utah 84011-0853 Tel: (801) 292-7061, 292-9668

November 22, 1993



Subject:

CULTURAL RESOURCE EVALUATION OF SEVEN PROPOSED WELLS IN THE MONUMENT BUTTES AND PLEASANT VALLEY LOCALITIES OF DUCHESNE AND

UINTAH COUNTIES, UTAH

Project:

Balcron Oil -- 1993-1994 Development Program

Project No.:

BLCR-93-11

Permit No.:

Dept. of Interior -- UT-93-54937

State Project No: UT-93-AF-669b

To:

Ms. Bobbie Schuman, Balcron Oil Division, P.O. Box 21017, Billings, Montana 59104

Mr. David Little, District Manager, Bureau of Land Management, 170 South 500 East, Vernal, Utah 84078

Info:

Antiquities Section, Division of State History, 300 Rio Grande, Salt Lake City, Utah 84101

# CULTURAL RESOURCE EVALUATION OF SEVEN PROPOSED WELLS IN THE MONUMENT BUTTES AND PLEASANT VALLEY LOCALITIES OF DUCHESNE AND UINTAH COUNTIES, UTAH

Report Prepared for Balcron Oil Company

Dept. of Interior Permit No.: UT-93-54937 AERC Project 1415 (BLCR-93-11)

Utah State Project No.: UT-93-AF-669b

Principal Investigator F. Richard Hauck, Ph.D.

Authors of the Report F. Richard Hauck & Glade V Hadden



## ARCHEOLOGICAL-ENVIRONMENTAL RESEARCH CORPORATION (AERC)

181 North 200 West, Suite 5 P.O. Box 853 Bountiful, Utah 84011-0853

November 22, 1993

#### **ABSTRACT**

An intensive cultural resource evaluation has been conducted for Balcron Oil Company of seven proposed wells (Monument Federal Units 33-8, 12-17, 22-17, 31-17, 42-18, 43-7 and 41-26) and associated access routes situated on BLM administered lands located in the Monument Buttes locality of Duchesne County, Utah and the Pleasant Valley locality of Uintah County, Utah. This evaluation involved a total of 78.6 acres, of which 70 acres are associated with the seven well pads and an additional 8.6 acres associated with the various access road rights of way. These evaluations were conducted by Glade Hadden and Walter Lenington of AERC on November 16, 17 and 18, 1993.

No previously recorded significant or National Register eligible cultural resources will be adversely affected by the proposed developments.

One newly identified cultural resource activity locus was discovered and recorded during the examinations. 42UN 2084 is a non-significant prehistoric activity locus associated with well location 41-26. This site is a cobble quarry area located within the proposed well development zone.

One isolated artifact was recorded during the investigations. Isolate 1415G/X1 is a non-diagnostic chert core noted on the access road between Units 12-17 and 22-17. This artifact was recorded but not collected.

AERC recommends project clearance based on adherence to the stipulations noted in the final section of this report.

#### TABLE OF CONTENTS

					٠.		page
Abstract		•	•	•		•	ii
Table of Contents		•	•	•	•		iii
List of Maps of the Project Area		•	•		•	•	iv
List of Figures		•	•	•		•	iv
General Information	•	•	•	•	•	•	1
Project Location .		. •		•		•	1
Environmental Description	•	•		•	•	•	4
Previous Research in the Locality	•	•	•	٠	•	•	4
File Search	•		•	•	•	•	4
Prehistory and History of the	he Pr	oject Ar	ea .	•	•	•	5
Site Potential in the Project	Dev	elopmen	t Zone	•	•		5
Field Evaluations	•					•	6
Methodology	•		•	•	•	,	6
Site Significance Criteria			•	•	•	•	6
Results of the Inventory	•		•	•	•		7
Conclusion and Recommendations	•		•	•	•		8
Deference							9

#### LIST OF MAPS OF THE PROJECT AREA

BAAD 1. Children Decourse Courses of				page
MAP 1: Cultural Resource Survey of Proposed Balcron Well Units in the Monument Buttes Locality of Duchesne County	•	•	•	2
MAP 2: Cultural Resource Survey of a Proposed Balcron Well Unit in the Pleasant Valley Locality of Uintah County	•			3
LIST OF FIGURES				
FIGURE 1: Isolated Artifact 1415G/X1	.*	•	•	7

#### GENERAL INFORMATION

On November 16, 17 and 18, 1993, AERC archaeologists Glade Hadden and Walter Lenington conducted an intensive cultural resource evaluation for Balcron Oil Company of Billings, Montana. This examination involved seven proposed well locations (Monument Federal Units 33-8, 12-17, 22-17, 31-17, 42-18, 43-7 and 41-26) and associated access roads located in the Monument Buttes area, and in the Pleasant Valley area, south of Myton, Utah. Some 78.6 acres were examined which includes ca. 70 acres associated with the well pads and an additional 8.6 acres associated with the various 100 foot-wide access routes. This project is situated in the Monument Buttes locality of Duchesne County, Utah. The entire project area is situated on federal lands administered by the Bureau of Land Management, Vernal District Office, Diamond Mountain Resource Area.


The purpose of the field study and this report is to identify and document cultural site presence and assess National Register potential significance relative to established criteria (cf., Title 36 CFR 60.6). The proposed developments of these seven drilling locations require archaeological evaluations in compliance with U.C.A. 9-8-404, the Federal Antiquities Act of 1906, the Reservoir Salvage Act of 1960-as amended by P.L. 93-291, Section 106 of the National Historic Preservation Act of 1966-as amended, the National Environmental Policy Act of 1969, the Federal Land Policy and Management Act of 1979, the Archaeological Resources Protection Act of 1979, the Native American Religious Freedom Act of 1978, the Historic Preservation Act of 1980, and Executive Order 11593.

In addition to documenting cultural identity and significance, mitigation recommendations relative to the preservation of cultural data and materials can be directed to the Bureau of Land Management Vernal District Office, and to the Utah State Antiquities Section. This work was done under U.S. Department of Interior Permit for Utah UT-93-54937 which expires on January 31, 1994.

#### Project Location

The project location is in the Monument Buttes locality of Duchesne County, Utah (situated on the Myton SE 7.5 minute topographic quad) and in the Pleasant Valley locality of Uintah County, Utah (situated on the Pariette Draw SW 7.5 minute topographic quad). The proposed drilling locations are situated in the following sections:

Balcron Monument Federal #33-8 is located in the NW - SE of Section 8, T. 9 So., R. 17 E. (see Map 1)



9 So. Τ.

17 E. R.

Meridian: SL Quad: Myton SE

Utah

Cultural Resource Survey of Proposed Balcron Well Units in the Monument Buttes Locality, Duchesne County

Legend:

Well Location


Access Route

Scale: 1:64,000 BLCR-93-11 Project:

Series:

Uinta Basin Date:

11/22/93



Legend: T. 8 So. MAP Cultural Resource Survey of Well R. 17 E. a Proposed Balcron Well Location Meridian: SL in the Pleasant Valley Access Quod: Pariette Draw SW Route Locality, Uintah County Cultural Utah Site Project: Scale: 1:64,000
Series: Series: Uinta Basin

Date:

11/22/93

Balcron Monument Federal #12-17 is located in the SW - NW of Section 17, T. 9 So., R. 17 E. and includes ca. 600 feet of access road (see Map 1)

Balcron Monument Federal #22-17 is located in the SE - NW of Section 17, T. 9 So., R. 17 E. and includes ca. 500 feet of access road (see Map 1)

Balcron Monument Federal #31-17 is located in the NW - NE of Section 17, T. 9 So., R. 17 E. and includes ca. 350 feet of access road (see Map 1)

Balcron Monument Federal #42-18 is located in the SE - NE of Section 18, T. 9 So., R. 17 E. (see Map 1)

Balcron Monument Federal #43-7 is located in the NE - SE of Section 7, T. 9 So., R. 17 E. and includes ca. 1000 feet of access road (see Map 1)

Balcron Monument Federal #41-26 is located in the NE - NE of Section 26, T. 8 So., R. 17 E. and includes ca. 1300 feet of access road (see Map 2)

#### Environmental Description

The project area is within the 5000 to 5500 foot elevation zone above sea level. Open rangeland terrain and eroded Eocene lakebed surfaces are associated with the project area.

The vegetation in the project area includes Chrysothamnus spp. Artemisia spp., Eriogonum spp., Sarcobatus vermiculatus, Ephedra viridis, Cercocarpus spp. Atriplex canescens, Salix spp., Typha spp., and a variety of grasses and sedges.

The geological associations within the project area consist of fluvial and lake deposits which correlate with the Uinta Formation which is of Tertiary age.

#### PREVIOUS RESEARCH IN THE LOCALITY

#### File Search

A records search of the site files and maps at the Antiquities Section of the State Historic Preservation Office in Salt Lake City was conducted on November 19, 1993. A similar search was conducted in the Vernal District Office of the BLM on November 16, 1993. The National Register of Historic Places has been consulted and no registered historic or prehistoric properties will be affected by the proposed developments.

A variety of known cultural sites are situated in the Monument Buttes / Castle Peak Draw locality. Many of these prehistoric resources were identified and recorded by AERC during the Mapco River Bend survey (Norman and Hauck 1980). Other sites have been located and

recorded by AERC and other archaeological consultants during oil and gas exploration inventories.

## Prehistory and History of the Cultural Region

Currently available information indicates that the Northern Colorado Plateau Cultural Region has been occupied by a variety of cultures beginning perhaps as early as 10,000 B.C. These cultures, as identified by their material remains, demonstrate a cultural developmental process that begins with the earliest identified Paleoindian peoples (10,000 -- 7,000 B.C.) and extends through the Archaic (ca. 7,000 B.C. -- A.D. 300), and Formative (ca. A.D. 400 -- 1100) Stages, and the Late Prehistoric-Protohistoric periods (ca. A.D. 1200 -- 1850) to conclude in the Historic-Modern period which was initiated with the incursion of the Euro-American trappers, explorers, and settlers. Basically, each cultural stage — with the exception of the Late Prehistoric hunting and gathering Shoshonean bands -- features a more complex life-way and social order than occurred during the earlier stage of development (Hauck 1991:53). For a more comprehensive treatment of the prehistory and history of this region see Archaeological Evaluations in the Northern Colorado Plateau Cultural Area (Hauck 1991).

## Site Potential in the Project Development Zone

Previous archaeological evaluations in the general project area have resulted in the identification and recording of a variety of cultural resource sites having eligibility for potential nomination to the National Register of Historic Places (NRHP). The majority of these sites are lithic scatters containing cobble reduction materials. Many of these quarry sites are of the "Tap and Test" variety, and extend for tens or hundreds of meters. Open occupations are also frequently being identified in this locality. Sites associated with the open rangeland generally appear to have been occupied during the Middle Plains Archaic Stage with occasional indications of Paleoindian activity based on the recovery of isolated Plano style projectile points. The north-south drainage canyons appear to contain the majority of Late Prehistoric (Numa) sites probably because those canyon floors were transportation corridors and convenient pastures for the Ute horse herds. Evidence of Formative Stage occupation, i.e., Fremont, is rarely observed in the rangeland environment but is common within the Green River and White River canyons and their primary tributary canyons.

Site density in certain portions of the region appears to range from one to four sites per section. These densities increase in the canyon bottoms due to Ute rock art loci. Recent evaluations indicate that the site densities may reach 8 to 12 sites per section in certain localities on the upper benches which were apparently favored for hunting, lithic resource procurement, and camping. Prehistoric sites on the rangeland benches appear to be associated with water courses and aeolian deposits.

#### FIELD EVALUATIONS

#### Methodo logy

Intensive evaluations consisted of the archaeologists walking a series of 10 to 20 meterwide transects across a 10 acre area covering each well pad. In addition, access routes were surveyed by the archaeologists walking a pair of 10 to 15 meter wide transects on each side of the flagged access route right of way. Thus, a 30 meter-wide or 100 foot-wide corridor (ca. 8.6 acres) was examined for the total ca. 3750 foot length of proposed access road, in addition to the seventy acres inventoried on the well pads for a total of 78.6 acres.

Observation of cultural materials results in intensive examinations to determine the nature of the resource (isolate or activity locus). The analysis of each specific cultural site results in its subsequently being sketched, photographed, and appropriately recorded on standard IMACS forms. Cultural sites are then evaluated for significance utilizing the standards described below and mitigation recommendations are considered as a means of preserving significant resources which may be situated within the development zone.

#### Site Significance Criteria

Prehistoric and historic cultural sites which can be considered as eligible for nomination to the National Register of Historic Places have been outlined as follows in the National Register's Criteria for Evaluation as established in Title 36 CFR 60.6:

The quality of significance in American ... archaeology ... and culture is present in ... sites ... that possess integrity of location, design, setting, materials, workmanship, feeling, and association and:

- a. That are associated with events that have made a significant contribution to the broad patterns of our history; or
- b, that are associated with the lives of persons significant in our past; or
- c. that embody the distinctive characteristics of a type, period, or method of construction ...; or
- d. that have yielded, or may be likely to yield, information important in prehistory or history.

In addition to satisfying one or more of these general conditions, a significant cultural resource site in Utah will generally be considered as being eligible for inclusion in the National Register if it should advance our current state of knowledge relating to chronology, cultural relationships, origins, and cultural life ways of prehistoric or historic groups in the area.

In a final review of any site's cultural significance, the site must possess integrity and at least one of the above criteria to be considered eligible for nomination to the National Record of Historic Places.


#### Results of the Inventory

One prehistoric cultural resource activity locus was observed and recorded during the archaeological evaluations. Site 42UN 2084 (see map 2) is a 50 x 120 meter lithic surface quarry area. Isolated flakes are located up to 500 meters from the main locus. Artifacts are composed mainly of Parachute Creek Chert cores. Two biface blanks and two utilized flakes were also found. This non-significant site is of a type commonly found in the area. Remnant lag gravel deposits with many chert and quartzite cobbles present cover extensive areas in this locality, and most such "Desert Pavement" sites are the location for "Tap and Test" quarry operations. No buried deposits are present and artifact context is questionable due to sheet wash erosion. The site does not qualify under criterion d of Title 36 CFR 60.6.

No previously identified and recorded significant or National Register sites were noted or recorded during the survey.

No paleontological loci were observed or recorded during the evaluations.

One isolated artifact was recorded during the evaluations. Isolate 1415G/X1 (see Figure one) consists of a single Parachute Creek chert core located along the access route connecting Units 12-17 and 22-17. This artifact was not collected.



Isolated Artifact 1415G/X1 (actual size)

#### CONCLUSION AND RECOMMENDATIONS

No known significant cultural or paleontological resources will be adversely impacted during the development and operation of Balcron Units 33-8, 12-17, 22-17, 31-17, 42-18, 43-7 and 41-26 as evaluated during this project.

AERC recommends that a cultural resource clearance be granted to Balcron Oil Company relative to the developments of these seven proposed drilling locations based upon adherence to the following stipulations:

- 1. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the flagged areas and corridors examined as referenced in this report, and to the existing roadways.
- 2. All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.
- 3. The authorized official should be consulted should cultural remains from subsurface deposits be exposed during construction work or if the need arises to relocate or otherwise alter the location of the exploration area.

F. Richard Hauck, Ph.D. President and Principal Investigator

Glade V Hadden Field Supervisor

#### REFERENCES

#### Hadden, Glade V and F. R. Hauck

- 1993a Cultural Resource Evaluation of Seven Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-4, Archaeological-Environmental Research Corporation, Bountiful.
- 1993b Cultural Resource Evaluation of Four Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-5, Archaeological-Environmental Research Corporation, Bountiful.
- 1993c Cultural Resource Evaluation of Eight Proposed Well Locations in the Monument Buttes Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-9, Archaeological-Environmental Research Corporation, Bountiful.
- 1993d Cultural Resource Evaluation of Four Proposed Well Locations in the Monument Buttes and Pleasant Valley Localities of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-10, Archaeological-Environmental Research Corporation, Bountiful.

#### Hauck, F. Richard


- 1981 Cultural Resource Inventory of Nine Proposed Well Locations and Access Roads in the Coyote Basin Locality of Uintah County, Utah, and in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Diamond Shamrock, DS-81-2, Archeological-Environmental Research Corporation, Bountiful.
- 1991 Archaeological Evaluations on the Northern Colorado Plateau Cultural Area, AERC Paper No. 45, Archeological-Environmental Research Corporation, Bountiful.
- 1992a Cultural Resource Evaluations of Four Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-2, Archeological-Environmental Research Corporation, Bountiful.

- 1992b Addendum to Cultural Resource Evaluations of Four Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-4, Archeological-Environmental Research Corporation, Bountiful.
- 1992c Cultural Resource Evaluations of Seven Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-5, Archeological-Environmental Research Corporation, Bountiful.
- 1992d Cultural Resource Evaluation of a Proposed Water Pipeline Corridor in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-6, Archeological-Environmental Research Corporation, Bountiful.
- 1992e Cultural Resource Evaluation of Seven Proposed Well Locations in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-92-8, Archeological-Environmental Research Corporation, Bountiful.
- 1993a Cultural Resource Evaluation of Nine Proposed Well Locations in the Castle Peak Draw Locality of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-1, Archeological-Environmental Research Corporation, Bountiful.
- 1993b Addendum to Cultural Resource Evaluation of Nine Proposed Well Locations in the Castle Peak Draw Locality of Duchesne and Uintah Counties, Utah. Report prepared for Balcron Oil Company, BLCR-93-2, Archeological-Environmental Research Corporation, Bountiful.
- 1993c Cultural Resource Evaluation of a Pipeline Corridor Situated in the Castle Peak Draw Locality of Duchesne County, Utah. Report prepared for Balcron Oil Company, BLCR-93-3, Archeological-Environmental Research Corporation, Bountiful.

Norman, V. Garth and F.R. Hauck

1980 Final Report on the Mapco River Bend Cultural Mitigation Study. AERC Paper No. 18, of the Archeological-Environmental Research Corporation, Bountiful.

EXHIBIT "N"






API NO. ASSIGNED: 43-013-31427 APD RECEIVED: 12/14/93 WELL NAME: BALCRON MONUMENT FEDERAL 33-8 OPERATOR: EQUITABLE RESOURCES (N9890) PROPOSED LOCATION: INSPECT LOCATION BY: / / NWSE 08 - T09S - R17E TECH REVIEW Initials Date SURFACE: 1980-FSL-1980-FEL BOTTOM: 1980-FSL-1980-FEL DUCHESNE COUNTY Engineering MONUMENT BUTTE FIELD (105) Geology LEASE TYPE: FED Surface LEASE NUMBER: U-007978 RECEIVED AND/OR REVIEWED: LOCATION AND SITING: y' Plat R649-2-3. Unit: Bond FEDERAL 0516 (Number <u>55 47188 MATION WI</u>) E R649-3-2. General.  $\sqrt{}$  Potash (Y/N) $\overline{\mu}$  Oil shale (Y/N)R649-3-3. Exception. ⊬ Water permit (Number BV SUMORY)

M RDCC Review (Y/N) Drilling Unit. Board Cause no: (Date: Date: COMMENTS: WELL IS NOT IN A SECONDARY REPOVERY UNIT. INFILL LOCATION. STIPULATIONS: TEA SOUNCE & PERMIT WILL BE NOTHERD BY SUNDAY PAID

PERIOD
EXPIRED
ON 4-61-95

## MONUMENT BUTTE WATER FLOOD UNITS



WATER FLOOD BOUNDARY

FIELD BOUNDARY



Michael O. Leavitt Ted Stewart Executive Director James W. Carter

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) Division Director 801-538-5319 (TDD)

December 20, 1993

Equitable Resources Energy Company P.O. Box 21017 Billings, Montana 59104

Balcron Monument Federal #33-8 Well, 1980' FSL, 1980' FEL, NW SE, Sec. 8, Re: T. 9 S., R. 17 E., Duchesne County, Utah

#### Gentlemen:

Pursuant to Utah Admin. R. 649-3-2, Location and Siting of Wells and Utah Admin. R. 649-3-4, Permitting of Wells to be Drilled, Deepened or Plugged-Back, approval to drill the referenced well is hereby granted.

In addition, the following specific actions are necessary to fully comply with this approval:

- Compliance with the requirements of Utah Admin. R. 649-1 et seq., Oil and 1. Gas Conservation General Rules.
- Notification within 24 hours after commencing drilling operations. 2.
- Submittal of Entity Action Form, Form 6, within five working days following 3. commencement of drilling operations and whenever a change in operations or interests necessitates an entity status change.
- Submittal of the Report of Water Encountered During Drilling, Form 7. 4.
- Prompt notification prior to commencing operations, if necessary, to plug 5. and abandon the well. Notify Frank R. Matthews, Petroleum Engineer, (Office) (801)538-5340, (Home) (801)476-8613, or Mike Hebertson, Oil and Gas Field Specialist, (Home) (801)269-9212.
- Compliance with the requirements of Utah Admin. R. 649-3-20, Gas Flaring 6. or Venting, if the well is completed for production.



Page 2 Equitable Resources Energy Company Balcron Monument Federal #33-8 Well December 20, 1993

This approval shall expire one year after date of issuance unless substantial and continuous operation is underway or a request for an extension is made prior to the approval expiration date. The API number assigned to this well is 43-013-31427.

Sincerely,

Associate Director, Oil and Gas

ldc

Enclosures

CC:

**Duchesne County Assessor** 

Bureau of Land Management, Vernal

WOI1

Form 3160-3 (November 1983) (formerly 9-331C)

# UNITED STATES DEPARTMENT OF THE INTERIOR

SUBMIT IN TRIPLICATE
(Other instructions on reverse side)

Form approved. Budget Bureau No. 1004-0136 Expires August 31, 1985

	DEPARTMENT	OF THE IN LAND MANAG		)R		U-DG7978	THE BESILL NO.
1 10 1 710 1	FOR PERMIT TO			OR PILIG	BACK	G. IF INDIAN, ALLOTTER	OR TRIBE HAME
APPLICATION	FOR PERMIT I	O DRILL, D	FF1 F1			n/a 7. UNIT AGREEMENT NA	MH
DRIL	L 🖾 .	DEEPEN [		PLUG BA	ACK ∐		
b. TIPE OF WELL CAS			BINGI	AULT ZONE		S. FARM OR LEASE NAME OF LEASE	(5
WELL X WELL 2. NAME OF OPERATOR	LL OTHER		20112	חחבוחם	ותודח	Balcron Monume	ent Federal
EQUITABLE RESO	URCES ENERGY CO	MPANY Balc	ron Oi	البالز الزابال	111111	9. WELL NO.	. •
3. ADDRESS OF OPERATOR						#33-8 10. FIELD AND POOL, 0	R WILDCAT
P.O. BOX 21017 4. LOCATION OF WELL (Re)	; Billings, MT	in accordance with	any Stat	e requirements.*)		Monument Butte	
At Huriace NW SE	Sec. 8, T9S, R	17 <b>E</b> 198	80' FSL	., 1980' FEL		11. SEC., T., R., M., OR I AND SURVET OR AR	ELK.
At proposed prod. zone	· .	43	2-013	-31427		NW SE Sec. 8,	
14. DISTANCE IN MILES AT			orricz*	couthwast		Duchesne	UTAH
From Myton 10. DISTANCE FROM PROPUS	, Utah, approxi	mately 16		SOUTHWEST.	17. NO.	OF ACRES ASSIGNED	1
LOCATION TO NEAREST PROPERTY OR LEADS LI	KE, FT.				1	KIS WELL	
(Also to nearest drig.  18. DISTANCE FROM TROPO TO NEAREST WELL, DR OR APPLIED FOR, ON THE	SED LOCATION*	•		OSED DEPTH	20. ROTA	Rotary	
21. ELEVATIONS (Show when					<u> </u>	22. APPROX. DATE WO	
GL 5318.6	)					Upon APD app	rovai
23.	P	ROPOSED CASII	G AND	CEMENTING PROC	GRAM		
SIZE OF HOLE	. BIZE OF CABING	WEIGHT PER F	00T	SETTING DEPTH		QUANTITY OF CEME	
	· · · · · · · · · · · · · · · · · · ·	Sec	attac	ched			WE'MANNET
	<del></del>						
EXHIBITS A	TTACHED		ı			DEC 1 - 1997.	
"B" PROPOS "C" GEOLOG "D" DRILLI		PROGRAM		"J" PLANNE "K" EXISTI "L" CUT & "M" ARCHEO	ING ROADS  TO ACCESS  ING WELLS  FILL DIA  TO OGY REF	AGRAM	JAN 27 1994 DIVISION OF OIL, GAS & MINING DIAGRAM
SELF CERTIFICATION: operations associat being provided by E surety under BLM BC with all of the ter in above space describe some. If proposal is to preventer program, if an	ed with the application and local terms and conditions and conditions are properly facility of deepen direction	ation. Bond o Energy Compar tionwide Oil & of that portio	coverage ny as pr & Gas Bo on of th	pursuant to 43 incipal and Sa ind #5547188) while lease associa	3 CFR 3104 feco Insura no vill be ated with	ance Company of Am responsible for co	nes is erica as empliance
24.	. /			dinator of			mber 13, 1993
SIGNED DOBLE	e Schumai	<u>U</u>	TLE and	<u>i Regulatory</u>	Affairs	DATE	HIDEL 13, 1333 .
(This space for Fede	Schuman- ral or State office use)						
PERMIT NO.	1 AA			APPROVAL DATE			
APPROVED BY	as/Bloa	verige 21	TLE	ASSISTANT DI	STRICT MERCLS	DATE, IT IN	<u>0 4 700 j</u>
CONDITIONS OF APPROV	AL, IFKHY:				C		TACHED (

NOTICE OF APPROVAL \*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United 14 tes any faise, fictillous or fraudulent statements or representations as to any matter within its jurisdiction.

#### **CONDITIONS OF APPROVAL** APPLICATION FOR PERMIT TO DRILL

Company/Oper	ator: <u>Equitable Resources Energy Company</u>
Well Name &	Number: Monument Federal 33-8
API Number:	43-013-31427
Lease Number:	<u>U-7978</u>
Location: NW	<u>/SE_Sec8_T9S_R17E_</u>
	NOTIFICATION REQUIREMENTS
Location Construction -	at least forty-eight (48) hours prior to construction of location and access roads.
Location Completion -	prior to moving on the drilling rig.
Spud Notice -	at least twenty-four (24) hours prior to spudding the well.
Casing String and - Cementing	at least twenty-four (24) hours prior to running casing and cementing all casing strings.
BOP and Related - Equipment Tests	at least twenty-four (24) hours prior to initiating pressure tests.
First Production -	within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90)

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

days.

Notice

#### CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

#### A. DRILLING PROGRAM

## 1. <u>Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered</u>

Report <u>ALL</u> water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

#### 2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 2M system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

The Vernal District Office shall be notified, at least 24 hours prior to initiating the pressure tests, in order to have a BLM representative on location during pressure testing.

### 3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the top of the Mahogany Oil shale zone, identified at  $\pm$  2,720 ft. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

The Vernal District Office shall be notified at least 24 hours prior to the running and cementing of all casing strings, in order to have a BLM representative on location while running and cementing all casing strings.

#### 4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

#### 5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to  $\pm$  2,520 ft. and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

#### 6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The Vernal District Office shall be notified, during regular work hours (7:45 a.m.-4:30 p.m., Monday through Friday except holidays), at least 24 hours **prior** to spudding the well.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

<u>Immediate Report</u>: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the appropriate District Office within thirty (30) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

#### 7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and within 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Gerald E. Kenczka

(801) 781-1190

Petroleum Engineer

Ed Forsman

(801) 789-7077

Petroleum Engineer

**BLM FAX Machine** 

(801) 781-4410

### EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

- Unused fracturing fluids or acids
- Gas plant cooling tower cleaning wastes
- Painting wastes
- Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spend solvents, spilled chemicals, and waste acids
- Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste
- Refinery wastes
- Liquid and solid wastes generated by crude oil and tank bottom reclaimers
- Used equipment lubrication oils
- Waste compressor oil, filters, and blowdown
- Used hydraulic fluids
- Waste solvents
- Waste in transportation pipeline-related pits
- Caustic or acid cleaners
- Boiler cleaning wastes
- Boiler refractory bricks
- Incinerator ash
- Laboratory wastes
- Sanitary wastes
- Pesticide wastes
- Radioactive tracer wastes
- Drums, insulation and miscellaneous solids.

## SURFACE USE PLAN OF OPERATION Conditions of Approval (COAs)

## Methods for <u>Handling Waste Disposal</u>

The reserve pit liner will have sufficient bedding (straw or dirt) to cover rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc..., that could puncture the liner will be deposed of in the pit.

The requested emergency pit is hereby approved under Onshore Order No. 7, subject to the following Conditions of Approval:

- 1. The emergency pit shall be fenced and the fence maintained for safety, and to prevent livestock and wildlife entry. The pit shall be fenced according to the same minimum standards listed for drilling the reserve pit under Point 9E of the Multi-point Surface Use and Operation Plan. The fence shall be maintained in a taut condition. Fences shall not be built on berms.
- Turn downs shall be put on the ends of pipes to direct fluids downward instead of against the wall of the pit.

## Additional Surface Conditions of Approval

If paleontologic resources are found or uncovered during ground disturbing activities, Balcron will suspend all operations that would further disturb such materials and immediately contact the BLM Authorized Officer.

A complete copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The operator or his/her contractor shall contact the BLM Office at (801) 789-1362 forty-eight (48) hours prior to construction activities.

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.

Due to potential mountain plover nesting habitat, surface disturbing activities will not be allowed between March 15 and August 15, unless a BLM approved wildlife field inspection show no mountain plover activity near the proposed site.

The flare pit location will be changed to be downwind of the prevailing wind direction on the northwest side of the location near the #6 corner.

### Waiver of Fencing Around Containment Tanks.

Well No. 33-8 Lease No. U-7978 Date. 1-10-94

Balcron Oil Division's operation supervisor has requested to modify fencing around small containment tanks for the above well location. The purpose of the BLM fencing standards are to prevent injury to livestock or wildlife by entering pits which may contain fluids. Balcron's present method of placing 100 barrel tanks covered with metal cross supports and wire mesh within earthen depressions accomplishes this purpose. This method of containment does not need fencing. Balcron will need to maintain at least one side of the earthen depression the tank rests in at less than a 1:1 slope to allow escape if needed and any hydrocarbons that enter the depression must be considered a spill and removed within 48 hours.

Natural Resource Protection Spec

#### BALCRON OIL

Balcron Monument Federal #33-8

NW SE Section 8, T9S, R17E, SLB&M

Duchesne County, Utah

PALEONTOLOGY REPORT
WELLPAD LOCATION AND ACCESS ROAD

BY

ALDEN H. HAMBLIN PALEONTOLOGIST 235 EAST MAIN VERNAL, UTAH 84078

DECEMBER 8, 1993

#### RESULTS OF PALEONTOLOGY SURVEY AT BALCRON MONUMENT BUTTE FEDERAL #33-8

Description of Geology and Topography-

This well is located 10 miles south and 1 mile east of Myton, Utah. It sits on the north side of Pariette Bench. The immediate area is flat and covered with sandy alluvium and small rock fragments.

All rock outcrops in the general area are of the Upper Eocene Uinta Formation, known for its fossil vertebrate fauna of mammals, turtles, crocodilians, and occasional fish remains and plant impressions.

There are no exposures of bed rock (Uinta Formation) on the wellpad or proposed access road.

Paleontological material found -

No fossils were found on the wellpad location or access road.

Recommendations-

No other recommendations are made for this location.

Alch 18. Hamblin Date December 9, 1993



DIVISION OF OIL, GAS AND MINING

#### SPUDDING INFORMATION

NAME OF COMPANY: EQUITABLE RESOURCES	
WELL NAME: BALCRON MONUMENT FEDERAL 33-8	
API NO. 43-013-31427	
Section 8 Township 9S Range 17E County DUCH	ESNE
Drilling Contractor UNION	<u>_</u>
Rig #	
SPUDDED: Date <u>\$2/14/94</u>	
Time 12:00 NOON	
How DRY HOLE	
Drilling will commence	
Reported by AL PLUNKETT-DENNIS INGRAM-DOGM	
Telephone #	
Date 2/15/94 SIGNED JLT	_

	TED STATES	FORM APPROVED Budget Bureau No. 1004-0135
	NT OF THE INTERIOR LAND MANAGEMENT	Expires: March 31, 1993  5. Lease Designation and Serial No.
. BUREAU OF	CAMD MUMORIMENT	U-7978
SUNDRY NOTICES	AND REPORTS ON WELLS	6. If Indian, Allottee or Tribe Name
Do not use this form for proposals to d Use "APPLICATION FO	rill or to deepen or reentry to a different reservoir. PR PERMIT—" for such proposals	
SIIBMI.	T IN TRIPLICATE	7. If Unit or CA, Agreement Designation
	THE THE LIGHTE	⊣n/a
i. Type of Well  Oil Gas Well Well Other		8. Well Name and No.
2 Name of Operator	COMPANY, BALCRON OIL DIVISION	Balcron Monument Fed. #33-8  9. API Well No.
3. Address and Telephone No.		43-013-31427 10. Field and Pool, or Exploratory Area
P.O. BOX 21017; Billings, MT  4. Location of Well (Footage, Sec., T., R., M., or Survey I	0020	Monument Butte/Green River
NW SE Section 8, T9S,		11. County or Parish, State
1980' FSL, 1980' FEL		Duchesne County, UTAH
12. CHECK APPROPRIATE BOX	(s) TO INDICATE NATURE OF NOTICE, REPO	ORT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	<u> </u>
Notice of Intent	Abandonment	Change of Plans
	Recompletion	New Construction Non-Routine Fracturing
X Subsequent Report	Plugging Back Casing Repair	Water Shut-Off
· Trind Abandanasa Nation	Altering Casing	Conversion to Injection
☐ Final Abandonment Notice	X Other 'Water source	Dispose Water
•		(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)
Operator intends to use the Jo	all pertinent details, and give pertinent dates, including estimated date of starticical depths for all markers and zones pertinent to this work.)  De Shields water source for drilling of that permit is on file at the Vern	this well as noted
		·
		•
		- 1004
	FE	B 1 6 1994
:	•	
14. I hereby certify that the foregoing is true and correct Signed Dull Chuma	Coordinator of Environmen  Tide and Regulatory Affairs	tal February 14, 1994
(This speech recent of State of fice use)		
Approved by	Title	Date
Conditions of approval, if any:		
	on knowingly and willfully to make to any department or agency of the Unit	ed States any false, fictitious or fraudulent statement
Title 18 U.S.C. Section 1001, makes it a crime for any person representations as to any matter within its jurisdiction.	on thowingly and wanterly to make to any observation of agoney of the own	

Form	3160-5
(lune	1000)

1. Type of Well

Well Gas Well

#### UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM	APPR	OVED	
Budget Bure	cau No.	1004-013	15
Fxnires:	March	31, 1993	

	Expues	IVI MIC		
Lease	Designat	ion an	d Seria	No.

6. If Indian, Allottce or Tribe Name

U-7978

n/a

SUNDRY	NOTICES	AND	REPORTS	MO	WELLS
--------	---------	-----	---------	----	-------

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. Use "APPLICATION FOR PERMIT-" for such proposals

7. If Unit or CA, Agreement Designation

SUBMIT IN TRIPLICATE	n/a
•	8. Well Name and No.

2. Name of Operator EQUITABLE RESOURCES ENERGY COMPANY, BALCRON OIL DIVISION

3. Address and Telephone No.

(406) 259-7860

P.O. Box 21017; Billings, MT 59104 4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NW SE Section 8, T9S, R17E 1980' FSL, 1980' FEL

Other

43-013-31427 10. Field and Pool, or Exploratory Area

Balcron Monument Fed.

9. API Well No.

Monument Butte/Green River 11. County or Parish, State

Duchesne County, UTAH

			BERGET OF OTHER DATA
	CHECK APPROPRIATE BOX(s) TO	LINDICATE MATURE OF NOTICE.	REPORT OR OTHER DATA
12	CHECK APPROPRIATE BUXISH TO	INDICATE NATURE OF ROMOE,	The officer
12.	CHECK ALL HOLLING BOX (4)	•	

TYPE OF SUBMISSION	• •	TYPE OF ACTION	
Notice of Intent	Abandonment		Change of Plans  New Construction
Subsequent Report	Recompletion Plugging Back Casing Repair		Non-Routine Fracturing Water Shut-Off
Final Abandonment Notice	Altering Casing  XX Other Report of		Conversion to Injection  Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.) 13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled

give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\* This well was spurl on 2-14-94 at 12 noon by Leon Ross Air Drilling.

Coordinator of Environmental and Regulatory Affairs Date Date 

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statement or representations as to any matter within its jurisdiction.

STATE OF UTAH DIVISION OF OIL, GAS AND MINING

(3/89)

Figure Resources Finergy Company Balcron Oil Division

OPERATOR ACCT. NO. N9890

ENTITY ACTION FORM - FORM 6

FEB | 7 1994


ADDRESS P.O. Box 21017

Billings, MI 59104

(406) 259-7860

	•	•	2000	(406) 259	<del>-</del> /00U				<del></del>		
ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	QQ	sc	HELL I TP	LOCATIO RG	COUNTY	SPUD DATE	EFFECTIVE DATE
A	99999	11613	43-013-31427	Balcron Monument Federal #33-8	NW SE	8	9S	17E	Duchesne	2-14-94	2-14-94
WELL 1 C	омментs: of a new w	Nത ell.	n unit well 19	donah). Entity added 2-22-94. I							
										·	
WELL 2 C	OMMENTS:						<u></u>				
WELL 3 C	OMMENTS:										
HELL 4 C	OMMENTS:				1		<u> </u>	<u> </u>	<u> </u>		<u> </u>
A · B · C ·	ODES (See i - Establish - Add new w - Re-assign - Re-assign	new entity ell to exist well from o well from o	on back of form) for new well (si ing entity (grout nne existing enti une existing enti unents section)	ngle well only) p or unit well) ty to another existing entity ty to a new entity					Boblice Signature Coordinator of Regulatory Af Title	of Environment	Man- tal and

## CORE REPORT NO.



## BALCRON OIL COMPANY

BALCRON MONUMENT FEDERAL #33-8

NW SE SECTION 8, T9S, R17E
DUCHESNE COUNTY, UTAH

43-013-31427

CONFIDENTIAL

## Clement Consulting

Roy L. Clement Wellsite Geologist

1907 Sligo Lane Billings, MT 59106 406-656-9514

Northern Rockies Williston Basin Horizontal Experience

Aprilia de la companya de la company



# DIVISION OF OIL, GAS & MINING

#### BALCRON OIL COMPANY

#### BALCRON MONUMENT FEDERAL #33-8

#### NW SE SECTION 8, T9S, R17E

#### DUCHESNE COUNTY, UTAH

#### Prepared by:

Roy L. Clement c/o Clement Consulting 1907 Sligo Lane Billings, Montana 59106 (406) 656-9514

#### Prepared for:

Dave Bickerstaff & Keven Reinschmidt c/o Balcron Oil Company Post Office Box 21017 Billings, MT 59104 (406) 259-7860

#### **WELL DATA SUMMARY**

**OPERATOR:** 

BALCRON OIL COMPANY

ADDRESS:

Post Office Box 21017 Billings, Montana 59104

WELL NAME:

Balcron Monument Federal #33-8

FIELD:

Monument Butte

LOCATION:

1980' FSL & 1980' FEL

NW SE SECTION 8, T9S, R17E

LEASE#:

U-7978

API#:

43-013-31427

COUNTY:

Duchesne

STATE:

Utah

BASIN:

Uinta

WELL TYPE:

Developmental Well

BASIS OF PROSPECT:

Oil Production @ Monument Butte Field

**ELEVATION:** 

GL: 5318'

SUB: 10'

**KB:** 5328'

SPUD DATE:

February 18, 1994

TOTAL DEPTH/DATE:

5700' on February 26, 1994

TOTAL DRILLING DAYS: 8

TOTAL ROTATING HOURS: 137.00

STATUS OF WELL:

Cased for Completion on February 28, 1994

CONTRACTOR:

Union Drilling Company, Rig #17

TOOLPUSHER:

Dave Gray

FIELD SUPERVISOR:

Al Plunkett

MUD ENGINEER:

Al Plunkett

MUD TYPE:

Air/Foam from surface to 3853'; KCL/Fresh Water from 3853' to TD.

WELLSITE GEOLOGIST:

Roy L. Clement

PROSPECT GEOLOGISTS: Dave Bickerstaff and Keven K. Reinschmidt

of Balcron Oil Company

**MUDLOGGERS**:

Larry Vodall and Bob Drogitis of NW Well Logging

SAMPLING PROGRAM: 50' samples from 1400' to 3853'; 20' samples from

3853' to 5700' (TD). All samples lagged and caught by mud loggers. One dry set of samples sent to the state

of Utah.

HOLE SIZE: 12 1/4" to 272'

7 7/8" to TD

CASING: 8 5/8" surface casing pre-set at 262'

5 1/2" production casing to Total Depth

**DRILL STEM TEST:** None

**CORE PROGRAM:** 2 planned, 2 undertaken

CORE NO. 1: 4632'-4662' Driller; 4632'-4662' Logger

Formation: R-2; Cut 30' & Recovered 28.5'

CORE NO: 2: 5440'-5470' Driller; 5440'-5470' Logger

Formation: B-1; Cut 30' & Recovered 30'

Core Company: DBS; Core Engineer: Billy Brogdin

ELECTRIC LOGGING PROGRAM: 1.) IPLT Log from 5698' - 2500'

2.) ARI from 5685' - 50'

3.) DSI from 5672' - 4000'

4.) RFT/GR @ 5446'; 5077'; 4901'; 4659'; 4110' 5.) Sidewall Cores @ 5462'; 5455'; 5446'; 5275'; 5171'; 5077'; 5041'; 5013'; 4902'; 4659'; 4655'; 4646'; 4536'; 4401'; 4350'; 4315'; 4142';

4141.5'; 4114'; 4109'; 3059'

LOG TOPS: Green River @ 1438'; Horsebench Ss @ 2171'; Second

Garden Gulch @ 3779'; Y-3 @ 4102'; Y-5 @ 4348'; Yellow Marker @ 4398'; Douglas Creek @ 4566'; R-2 @ 4644'; Second Douglas Creek @ 4798'; Green Marker @ 4936'; G-3 @5008'; Carbonate Marker @ 5404'; B-1 @ 5442'; TD @

5700'.

LOGGING COMPANY:

Schlumberger

LOGGING ENGINEER: Chris Presmyk

CORRELATION WELL: 1

1.) Diamond Shamrock

Pauite = 34-8

Sw Se Section 8, T9S, R17E

DISTRIBUTION LIST:

Balcron Oil Company

Attn: Dave Bickerstaff & Keven K. Reinschmidt

Post Office Box 21017 Billings, MT 59104

Balcron Oil Company Attn: Dale Griffin 275-CO.RD-120 Craig, CO 81625



Bureau of Land Management Vernal District Office Attn: Ed Forsman 170 South 500 East Vernal, UT 84078

State of Utah Division of Oil, Gas, and Mining 355 W. North Temple 3 Triad Center, Suite 350 Salt Lake City, UT 84180

#### GEOLOGIC EVALUATION

Balcron Oil Company drilled the Balcron Monument Federal #33-8 as a development well in the south portion of Monument Butte Field. The field, situated in the Uinta Basin of Utah, is currently being developed by Balcron with both a water flood project and a forty acre in fill drilling program. Monument Butte produces oil and gas from sandstone reservoirs in the Tertiary aged Green River Formation.

The Monument Federal #33-8 drill site was located in the Nw Se of Section 8, T9S, R17E, in Duchesne County, Utah. Balcron spudded the well on February 18, 1994 and a total depth of 5700' was reached eight days later. The well bore was extensively evaluated by a two man mud logging crew, a well site geologist, two cores and a full suite of E-logs which included sidewall coring and repeat formation testing tools. On February 28, 1994 the #33-8 was cased for completion operations.

Zones of Interest: (Note: all depths are based on E-Logs)

The first significant gas show occurred at 3535'. A net increase of 590 total units was recorded, consisting primarily of Methane with minor heavier gas components. Drill cuttings from this interval were comprised of unconsolidated, very fine to fine grained sands with traces of asphaltic staining. E-Logs indicate 11 to 15% porosity through this interval.

The Y-3 Sands were topped at 4102' with a 448 unit gas increase, C1 through NC4 components, and oil on the pits. Samples and logs indicate two sand benches from 4102' to 4144' with 21 total feet of pay ranging from 14-18% porosity.

An 8' thick sand section averaging 11% porosity was present from 4313' to 4321'. This interval was penetrated with a 120 unit gas show from poorly to unconsolidated sandstones with light brown oil staining.

The Yellow Marker proved to be a 5' thick interval at 4398' to 4403' with porosity ranging from 17 to 21%. A 78 unit net gas increase was noted from this zone along with very fine to medium grained sandstone and brown oil staining.

Core #1 was undertaken from 4632' to 4662', topping the R-2 Sand at 4644'. The R-2 was a 19' thick section of very fine to medium grained Sandstone with good oil shows, saturations and occasional vertical fractures. E-Logs indicate 10 to 16% porosity through the R-2 Sands.

The B-1 Sand was topped with Core #2 at 5442'. 19' of very fine to medium grained sandstone with good oil saturations and porosity ranging from 10 to 13 % were present in the B-1. Both yelloworange and dark brown oil staining were note in the core along with a single open vertical fracture at 5440' to 5441'.


Respectfully submitted,

Roy L. Clement Wellsite Geologist

### DAILY ACTIVITY

DAY	DATE	DEPTH	PROG	BIT	WOB	<u>RPM</u>	$\mathbf{PP}$	<u>₩</u> T*	VIS	WL	<u>ACTIVITY</u>	<b>FORMATION</b>
0	2/18	272'	0,	1	A11	5 <b>5</b>	100	8 3	26	n/c	Rig up, drill	cement
1	2/19	645'	3 <b>73</b> '	1	45	55		8.3	26	n/c	Drill ahead	Green R.
2	2/20	2019'	1374'	1	45	55	220		26	n/c	Drill ahead	Green R.
3	2/21	3090'	1071'	1	45	5 <b>5</b>	200	8.4	26	n/c	Drill ahead	Green R.
4	2/22	3853'	763'	2	43	70	750	8.4	26	n/c	Mud up	Garden G.
5	2/23	4476'	623'	2	43	60	800	8.4	26	n/c	Drill ahead	Y-Sands
6	2/24	4690'	214'	4	45	6 <b>5</b>	775	8.4	26	n/c	Core #1	R-2
7	2/25	5236'	54 <b>6</b> '	5	45	60	800	8.4	26	n/c	Core #2	B-1
8	2/26	5 <b>490'</b>	254'	6	43	<b>60</b>	825	8.4	26	n/c	Drill to TD	B Zone
9	2/27	5700'	210'	6	43	60	825	8.4	26	n/c	Run E-Logs	B Zone

\*Note: drilled with air and foam from under surface casing to 3853', switched to KCL and Fresh water from 3853' to TD.



## BIT RECORD

CONTRACTOR: UNION DRILLING, RIG #17

SPUD: 2/18/94 TOTAL DEPTH: 2/26/94 TOTAL ROTATING HOURS: 137.00

BIT		TYPE/			DEPTH		warma	ACCUM	on	DDM	DELL	DD.	100	n	_
NO.	SIZE	<u>MAKE</u>	JETS SIZE	SERIAL #	OUT	<u>FEET</u>	HOURS	HOURS !	<u>MOR</u>	RPM	<u>DEV</u>	<u>PP</u>	T	B	<u>G</u>
1	7 7/8	SEC M84CF	24 24 24	634848	3 <b>853</b> '	3581'	66.25	66.25	45	55 1	l 1/4 <sup>0</sup>	220	3	6	I
2	7 7/8	SEC MAF	13 13 13	632768	4632'	779'	27.25	93.75	43	60	-	800	1	7	I
3	7 7/8	DBS CMPZI	open	5920515	4662'	30'	2.00	95.75	18	60	-	500	_	_	
4	7 7/8	HTC ATJ-35C	13 13 13	G60WS	5440'	778'	30.50	126.25	45	65	-	800	1	1	Ι
5	7 7/8	DBS CMPZI7	open	Rerun #3	5470'	3 <b>0'</b>	1.75	128.00	18	60	-	550	-	_	_
6	7 7/8	HTC ATJ-35C	13 13 13	Rerun #4	5700 <b>'</b>	230,	9.00	137.00	43	60 2	2 1/4 <sup>3</sup>	800	2	2	I

## **DEVIATION SURVEYS**

<u>DEPTH</u>	<b>DEVIATION</b>
288'	$1 1/4^{0}$
800'	$1 1/4^{0}$
1300'	$1 \ 1/4^{0}$
1800'	3/4 <sup>0</sup>
2300'	$2^{0}$
2798'	$1 1/4^{0}$
3300'	10
3 <b>85</b> 3'	$1 1/4^{0}$
4476'	$2^0$
5161'	1/20
5700'	2 1/40

#### FORMATION TOPS AND STRUCTURAL RELATIONSHIPS

SUBJECT WELL: Monument Federal #33-8; NW SE Sec 8, T9S, R17E KB: 5328'
OFFSET #1: Paiute #34-8; SW SE Sec 8, T9S, R17E KB: 5313'

AGE and FORMATION	PROG	SAMPLE	E-LOG	DATUM	THI CK	DIP TO OFFSET #1
TERTIARY						
Uinta	Surface	e				
Green River	1435'	1440'	1438'	3 <b>890'</b>	733'	+ 5'
Horsebench Ss	2159'	2170'	2171'	3157'	1608'	- 4'
2nd Garden Gulch	3764'	3765'	3779'	1549'	323'	- 7'
Y-2	4041'	Absent				
Y-3	4090'	4102'	4102'	1226'	15'	- 4'
Y-5	4327'	4352'	4348'	980'	7,	-13'
Yellow Marker	4384'	4394'	4398'	930'	5 <b>'</b>	- 6'
Douglas Creek	4549'	4560'	4566'	762'	78 <b>'</b>	- 9'
R-2	4616'	4641'	4644'	684'	19'	-10'
R-5	4746'	Absent		-~	~-	
2nd Douglas Ck	4785'	4804'	4798'	530'	138'	- 5'
Green Marker	4919'	4932'	4936'	3 <b>92</b> '	72'	- 9'
G-3	4997'	5008'	5008'	3 <b>20</b> '	3 <b>4</b> '	- 3'
Carbonate Mkr.	5391'	5410'	5404'	- 76'	<b>6</b> '	- 5'
B-1	5425'	5440'	5442'	-114'	19'	- 9,

## REFERENCE WELL

# DIAMOND SHAMROCK PAUITE #34-8 SW SE SEC 8, T9S, R17E KB: 5313'

AGE and FORMATION	<u>DEPTH</u>	DATUM	<u>THICK</u>
TERTI ARY			
Uinta	Surface		
Green River	1428'	3885'	724'
Horsebench Ss	2152'	3161'	1605'
2nd Garden Gulch	3757'	1556'	272'
Y-2	4034'	1279'	49'
Y-3	4083'	1230'	237'
Y-5	4320'	993'	5 <b>7</b> '
Yellow Marker	4377'	936'	165'
Douglas Creek	4542'	771'	77 <b>'</b>
R-2	4619'	694'	120'
R-5	4739'	574'	39,
2nd Douglas Creek	4778'	535'	134'
Green Marker	4912'	401'	78'
G-3	4990'	323'	394'
Carbonate Marker	5 <b>384</b> '	-71'	34'
B-1	5418'	-105'	

#### LITHOLOGY

Sami	nle	Program:
Jam	$\nu_{1}$	LIUELGH

All samples were lagged and caught by a two man mud logging crew. 50' samples were taken from 1400' to 3853' with 20' samples caught from 3853' to total depth. Additional timely samples were caught through potential zones of interest. sample quality was fair to good except as noted. Descriptions begin at 1400' in the Uinta Formation.

1400' - 1440'

Sandstone:

light gray to clear, very fine to fine grained, sub angular to sub rounded, poorly consolidated to unconsolidated, fair sorting, calcareous cement in part, trace Pyrite

#### Sample Top: Green River Formation @ 1440'

light brown to orangebrown, graybrown, 1440' - 1600' Shale:

soft to firm, platy to sub blocky,

calcareous to dolomitic, trace Pyrite and

Dolomite

1600' - 1750' Shale: light to medium brown, graybrown, light orange to orangebrown, soft to firm, platy to blocky, calcareous to dolomitic, trace Pyrite and Dolomite: tan to cream,

microcrystalline, soft, chalky, argillaceous

to shaly, calcareous

1750' - 1800' Sandstone: light gray to graybrown, very fine grained, sub angular, poor consolidation, fair sorting, trace Gilsonite, tar, moderate to bright vellow fluorescence, immediate bright bluewhite streaming cut, interbeds

of Shale: as above

1800' - 1900' Shale: light brown to graybrown, orangebrown, soft to firm, platy to sub blocky,

calcareous to dolomitic, trace Pyrite and occasional interbeds of Dolomite: white to cream, microcrystalline, firm, chalky to

earthy, argillaceous to shaly

1900' - 2000' Shale: light orange to orangebrown, brown to gray, soft to firm, platy to blocky,

dolomitic to marly, trace Pyrite and white

Calcite crystals

2000' - 2170' Shale: orange to orangebrown, graybrown, soft to firm, platy to blocky, dolomitic to marly, trace Pyrite and Dolomite

# Sample Top: Horsebench Sandstone @ 2170'

Sample 10p.	norsebench bandsu	<u>me e 2170</u>
2170' - 2300'	<u>Sandstone</u> :	light gray to clear, very fine to fine grained, sub angular to angular, poorly consolidated to unconsolidated, fair sorting, Bituminous in part, interbeds of Shale: gray to graybrown, soft to firm, platy to blocky, very calcareous
2300' - 2400'	<u>Shale</u> :	light to medium brown, graybrown, soft to firm, platy to sub blocky, calcareous to dolomitic
2400' - 2500'	<u>Shale</u> :	brown to graybrown, orangebrown, soft to firm, platy to blocky, calcareous, trace Dolomite
2500' - 2600'	<u>Shale</u> :	light to medium brown, light orangebrown, soft to firm, platy to blocky, calcareous to dolomitic, grading to Dolomite: tan to cream, microcrystalline, soft, chalky to earthy, shaly
2600' - 2705' to fine	<u>Sandstone</u> :	light brown to light gray, clear, very fine grained, occasional medium grained, sub angular, poor sorting, poorly consolidated to unconsolidated, Pyritic to Micaceous, trace brown asphaltic stain, scattered dull yellow fluorescence, slow bluewhite streaming to diffuse cut, interbeds of Shale: as above
2705' - 2800'	<u>Shale</u> :	light graybrown to gray, brown, soft to firm, platy to blocky, calcareous to dolomitic, abundant Pyrite, grading to Dolomite: cream to buff, microcrystalline, soft, chalky to earthy, shaly
2800' - 2925'	Sandstone:	gray to brown, clear in part, very fine to medium grained, sub angular, poor sorting, poorly consolidated to unconsolidated, Pyritic to Micaceous, trace brown asphaltic residue, dull gold fluorescence, slow bluewhite streaming cut, interbeds of Shale: as above
2925' - 3000'	<u>Shale</u> :	brown to orangebrown soft, platy to sub blocky, Pyritic, dolomitic and grading to Dolomite: cream to tan, microcrystalline, soft, chalky to earthy, argillaceous to shaly
3000' - 3150'	Sandstone:	light gray, salt and peppered, very fine to fine grained, sub angular to sub

		rounded, fair sorting, poorly consolidated, Micaceous to Bituminous, trace brown spotty asphaltic staining, dull yellow scattered fluorescence, slow weak bluewhite diffuse cut, grading to Siltstone
3150' - 3250'	<u>Dolomite</u> :	cream to buff, tan to light graybrown, microcrystalline, soft to firm, chalky to earthy, slightly argillaceous to argillaceous, interbedded with Shale: light gray to graybrown, light brown, firm, platy, calcareous to dolomitic, trace Pyrite
3250' - 3355'	Sandstone:	light gray, clear, very fine to fine grained, sub angular, poor to fair sorting, predominantly unconsolidated, <u>dull gold fluorescence</u> , very slow weak yellowwhite <u>diffuse cut</u> , interbedded with Shale: as above
3355' - 3465'	Siltstone:	light to medium gray, firm, calcareous, grading to very fine grained Sandstone
3465' - 3525'	<u>Shale</u> :	light gray to graygreen, soft to firm, blocky to platy, silty, calcareous to dolomitic, grading to Dolomite: tan to cream, microcrystalline, soft to firm, chalky to fragmental, slightly argillaceous, calcareous in part
3 <b>525' -</b> 3600'	Sandstone:	light gray, salt and peppered, clear, very fine to fine grained, sub angular to sub rounded, predominantly unconsolidated, Micaceous to Pyritic, trace asphaltic staining, no fluorescence, slow weak yellowwhite diffuse cut
3600' - 3650'	Shale:	light to medium brown, orangebrown, gray, firm, platy to blocky, silty, calcareous to dolomitic
3650' - 3765'	Siltstone:	light gray, firm, calcareous, Pyritic, grading to very fine grained Sandstone in part, interbeds of Shale: as above
Sample Top: Se	cond Garden Gulch	n
3 <b>765' -</b> 3 <b>795'</b>	<u>Limestone</u> :	tan to cream, white in part, cryptocrystalline, soft, chalky
3795' - 3853'	Siltstone:	light to medium gray, firm, calcareous,

grading to Sandstone: light gray, clear, very fine grained, sub angular to sub rounded, fair sorting, predominantly

## unconsolidated

<u>Note</u> :		and switched from Air/Foam to KCL/Water mud ples from 3853' to total depth.
3853' - 3942	' <u>Siltstone</u> :	light to medium gray, firm, calcareous, grading to Sandstone: light gray, clear, very fine grained, sub angular to sub rounded, poor sorting, unconsolidated, poor samples after trip, abundant cavings
3942' - 3992	Sandstone:	gray, clear, very fine to fine grained, sub angular, poor to fair sorting, poorly consolidated to unconsolidated, silty
3992' - 4048	' <u>Shale</u> :	light graybrown to light brown, graygreen in part, firm, blocky, calcareous, interbedded with Siltstone: light to medium gray, firm, calcareous, grading to very fine grained Sandstone
Sample Top:	Y-2 @ 4048'	
4048' - 4074	' <u>Sandstone</u>	clear, light gray, very fine to fine grained, occasional medium grains, sub rounded, poorly sorted, poorly consolidated to unconsolidated, grading to Siltstone
4074' - 4102	' <u>Siltstone</u> :	light gray, firm, calcareous
Sample Top:	Y-3 @ 4102'	
4102' - 4114	' <u>Sandstone</u>	light brown, clear, very fine to fine grained, sub angular, fair sorting, poorly consolidated to unconsolidated, light brown oil stain and oil on reserve pit, dull gold fluorescence, immediate bluewhite streaming cut
4114' - 4134	' <u>Siltstone</u> :	light gray to graywhite, firm, calcareous, grading to very fine grained Sandstone
4134' - 4138	' <u>Sandstone</u>	light brown, very fine to fine grained, angular, fair sorting, unconsolidated, light brown oil stain, dull gold fluorescence, immediate bluewhite streaming cut
4138' - 4178	' <u>Shale</u> :	graybrown to brown, soft, platy to sub blocky, calcareous, trace Pyrite, trace Limestone: cream to tan, microcrystalline, soft, chalky
4178' - 4220	' <u>Siltstone</u> :	light gray to graywhite, firm, calcareous,

grading	to	VANV	fine	grained	Sandstone
grading	LO	very	HHE	gramed	Sanusione

		grading to very fine grained Sandstone
4220' - 4284'	<u>Shale</u> :	light to dark brown, soft to firm, platy, calcareous, silty to Pyritic, trace Limestone: tan to buff, microcrystalline, soft, chalky, argillaceous
4284' - 4306'	<u>Siltstone</u> :	light gray to graywhite, firm, slightly calcareous, grading to very fine grained Sandstone
4306' - 4334'	Sandstone:	light gray, clear, light brown in part, fine to medium grained, sub angular, poorly sorted, poorly consolidated to unconsolidated, trace light brown oil stain, dull gold fluorescence, slow yellowwhite diffuse to streaming cut, grading to Siltstone
4334' - 4352'	<u>Siltstone</u> :	gray to graybrown, firm, slightly calcareous, grading to Shale
Sample Top:	Y-5 <b>@</b> 4352'	
4352' - 4372'	Sandstone:	light graybrown, clear, fine to medium grained, sub angular, poor sorting, poor to fair consolidation, calcareous cemented in part, silty in part
4372' - 4394'	<u>Shale</u> :	light brown to graybrown, firm, platy to blocky, calcareous to silty
Sample Top:	Yellow Marker @ 4394	<u>,                                      </u>
4394' - 4434'	<u>Sandstone</u> :	light brown to gray, clear, very fine to medium grained, poor sorting, poorly consolidated, calcareous cemented in part, brown oil stain and black asphaltic stain, dull gold to yellow fluorescence, moderate bluewhite streaming to diffuse cut, grading to Siltstone in part
4434' - 4500'	<u>Siltstone</u> :	light to medium gray, firm to slightly hard, calcareous, grading to very fine grained Sandstone in part, trace Pyrite
4500' - 4560'	<u>Siltstone</u> :	light gray to graywhite, firm, calcareous, grading to Sandstone: light brown to gray, very fine to fine grained, sub angular, fair sorting, poorly consolidated to unconsolidated, brown spotty oil stain, dull gold fluorescence, slow to moderate bluewhite diffuse cut

Sample Top: Douglas Creek @ 4560'

4560' - 4574' Shale: medium to dark brown, soft, platy,

calcareous to marly, grading to Limestone:

tan to cream, microcrystalline, soft,

chalky, shaly

4574' - 4632' Siltstone: light gray to graywhite, firm, calcareous,

grading to Shale in part

Note: Core #1 4632' - 4662'. See Core Report for complete description.

4662' - 4694' Shale: light to medium gray, firm, platy to sub

blocky, slightly calcareous, silty in part

4694' - 4758' Siltstone: light to medium gray, firm, calcareous,

trace Pyrite, grading to Shale: as above

Sample Top: R-5 @ 4758'

4758' - 4788' Siltstone: light gray to graybrown, firm, calcareous,

grading to very fine grained Sandstone

4788' - 4804' Shale: brown to graybrown, soft to firm, platy to

blocky, calcareous to silty, trace

Limestone: tan to cream, microcrystalline,

firm, chalky to earthy, shaly

Sample Top: Second Douglas Creek @ 4804'

4804' - 4844' Siltstone: light gray to graywhite, firm, calcareous,

grading to Sandstone: clear to light brown

in part, fine to medium grained, sub

angular, poorly consolidated to

unconsolidated, poor sorting, slight trace dark brown spotty oil stain, trace dull yellow fluorescence, slow weak yellowwhite

diffuse cut

4844' - 4894' Siltstone: gray to graybrown, firm to slightly hard,

calcareous to Pyritic, interbeds of Shale: graybrown to brown, soft to firm, platy,

calcareous to marly

4894' - 4932' Siltstone: light gray to graywhite, firm, calcareous,

grading to very fine grained Sandstone in

part

Sample Top: Green Marker @ 4932'

4932' - 4980' Shale: gray to graybrown, medium brown, soft to

firm, platy to blocky, calcareous, silty,

trace Limestone: tan to cream,

microcrystalline, firm, dense to chalky,

# argillaceous

4980' - 5008'	Siltstone:	light to medium gray, graywhite, firm, calcareous
Sample Top: G-3	<b>€</b> 5008'	
5008' - 5042'	Sandstone:	light brown to gray brown, clear, very fine to medium grained, sub angular, poor sorting, poorly consolidated to unconsolidated, calcareous cemented in part, brown oil stain and abundant black asphalt, dull gold fluorescence, immediate bright bluewhite streaming cut, grading to Siltstone
5042' - 5072'	Shale:	gray to graybrown, firm, platy, slightly calcareous, silty in part
5072' - 5080'	Sandstone:	light brown, clear, very fine to fine grained, sub angular, fair sorting, poorly consolidated to unconsolidated, brown oil stain, dull gold fluorescence, immediate bright bluewhite streaming cut
5080' - 5126'	Shale:	light to medium gray, graybrown, firm, platy to blocky, calcareous to silty
5126' - 5150'	<u>Shale</u> :	dark brown to graybrown, soft to firm, blocky to platy, calcareous to carbonaceous, trace Pyrite
5150' - 5166'	Shale:	light to medium gray, graybrown, firm, platy to blocky, calcareous to silty
5166' - 5206'	<u>Siltstone</u> :	light gray to graywhite, firm, calcareous, grading to Sandstone: light brown, clear, very fine to fine grained, sub angular, poorly consolidated to consolidated, fair sorting, calcareous cemented in part, brown oil stain, dull gold fluorescence, slow yellowwhite diffuse to streaming cut
5206' - 5220'	Shale:	light gray to graybrown, firm, platy to blocky, slightly calcareous
5220' - 5234'	Shale:	dark brown to dark graybrown, soft, blocky, slightly calcareous, carbonaceous
5234' - 5262'	Shale:	light to medium gray, graybrown, soft to firm, blocky to platy, calcareous to marly, silty in part
5262' - 5298'	Shale:	dark gray to dark graybrown, firm to

brittle,	blocky,	very	slightly	calcareous
carbona	ceous			

5298' - 5320'	Shale:	gray to graybrown, soft to firm, blocky to platy, calcareous, silty in part
5320' - 5390'	<u>Shale</u> :	dark brown to dark graybrown, firm to brittle, blocky to fissile in part, slightly calcareous, carbonaceous in part, trace finely disseminated Pyrite
5390' - 5410'	Shale:	light brown to graybrown, soft, blocky, very calcareous to marly

### Sample Top: Carbonate Marker @ 5410'

5410' - 5420'	<u>Limestone</u> :	tan to cream, microcrystalline, firm, chalky to fragmental in part, dolomitic, slight argillaceous
5420' - 5440'	Shale:	light to medium gray, soft to firm, calcareous to silty
Note: Core	#2 5440' - 54 <b>7</b> 0'.	See Core Report for complete description.
5470 <b>'</b> - 5502 <b>'</b>	Siltstone:	light to medium gray, firm to slightly hard, calcareous, grading to very fine grained Sandstone in part
5502' - 5542'	Sandstone:	clear, light gravbrown to brown, salt and

5502' - 5542' <u>Sandstone</u> :	clear, light graybrown to brown, salt and peppered, fine to medium grained, angular to sub angular, poor sorting, poorly consolidated to unconsolidated, slight trace brown spotty oil stain, dull gold scattered fluorescence, slow weak bluewhite streaming to diffuse cut, grading to Siltstone
----------------------------------	--

		grading to Siltstone
5542' - 5608'	<u>Siltstone</u> :	light gray to graywhite, firm to slightly hard, calcareous, grading to very fine grained Sandstone in part, interbeds of Shale: brown to graybrown, firm, blocky to platy, slightly calcareous, silty
5608' - 5630'	Sandstone:	clear, salt and peppered, fine to medium

98' - 5630'	Sandstone:	clear, salt and peppered, fine to medium grained, sub angular to sub rounded, poor sorting, poorly consolidated to unconsolidated, trace brown spotty oil stain, dull gold fluorescence, slow weak diffuse to streaming bluewhite cut, silty in part
		in part


5630' - 5700' <u>Siltstone</u>: gray to graywhite, firm to slightly hard, calcareous grading to Sandstone: as

above, interbeds of Shale: gray to graybrown, dark brown in part, soft to firm, calcareous, silty, carbonaceous in part

Note:

Driller's Total Depth @ 5700'. Circulate and condition hole for logging.


ATTN: Keven Reinschmidt / P





# CORE REPORT NO. 1

FORMATION: R-2	Sand		INTERVAL:	4632' - 46	62'	CUT:	30'
CORE COMPANY: DBS	·		DATE:	23 Feb 94	***************************************	RECOVER: _	28.5'
WELLSITE ANALYSIS: _	Roy L. Cl	ement	LA	B ANALYSIS:	Terra Tek,	Salt Lake Cit	v. UT
min /ft						· .	
2557510	Core Bit Cl	MPZI		MICRO	DESCRIPTION	S	
			4632'-4641'	Shale: medium part, abundan	gray, firm, t black carb	calcareous, s onaceous plant	ilty in remains
	4632'	1 - 1	4641'-4647'	sub angular, p & calcareous (	poorly sorted cemented, mid	ine to medium of the constant	olidated poor
	40' WOE	3 18	ACATI ACEO	moderate to be immediate brice	in and bleed cight yellow ght bluewhit	ing oil throug green fluoresc e streaming cu	h out, ence, t
	RPM PP 50'	500	4647'-4652'	calcareous, ir brown, very fi fair sorting, cemented, mica spotty brown of	nterbedded wanterbedded wanterbedded was well consologies, very poil stain and	brown, firm, s ith Sandstone: grained, sub a idated and calc poor visual po d slightly ble	light ngular, careous rosity, eding
	4662 <b>'</b>			Sandstone: lic medium grained well consolidat	t, fluorescent yht to medium to angulated and calca	m brown, very : ar, poor sorting areous cemented	above fine to
	WT Vis WI		4660.5'-4662'	oil and good of moderate to br	oil saturationistic	s, dark brown lon through out green fluoresce e streaming cut	<u>.</u> ence,








# CORE REPORT NO. 2

FORMATION:	B-1 Sand	INTERVAL: _	5440' - 5470'	CUT:	30'
CORE COMPANY:	DBS	DATE:	25 Feb 94	RECOVER:	30'
WELLSITE ANALYSIS:	Roy L. Clement	LAB	ANALYSIS: Terra Tek	, Salt Lake City	, UT









# CORE REPORT NO. 2

FORMATION:	INTERVAL:		CUT:
CORE COMPANY:			RECOVER:
	D\t	J ANALISIS	
WELLSITE ANALYSIS:	54666'-5467'  5467'-5470'	Shale: black, firm, abundant finely disapetroliferous, spott moderate bluewhite siltstone: light to	slightly calcareous, seminated Pyrite, by yellowgreen fluorescence, streaming cut medium gray, very ed in part, grading to

#### LOGGING REPORT

Logging Company: Schlumberger Engineer: Chris Presmyk Date: 2/27/94

Witnessed by: Roy Clement and Al Plunkett

Driller's TD Depth: 5700' Logger's TD Depth: 5700'

<u>Driller's Casing Depth</u>: 262' <u>Logger's Casing Depth</u>: 262'

Elevation: GL: 5318' Sub: 10' KB: 5328'

Mud Conditions: Wt: 8.4 Vis: 26 WL: n/c

**BHT**: 143° F

Hole Conditions: Good

Logging Time: Time Arrived: 1800 hrs First Tool in Hole: 2030 hrs

Last Tool Out: 1700 hrs Time of Departure: 1900 hrs

Electric Logging Program:

1.) Integrated Porosity Lithology Log with Gamma

Ray and Caliper from 5698' to 2500'.

2.) Azimuthal Laterlog with Gamma Ray from 5685' to

50'.

3.) Dipole Shear Sonic STC P & S Mode Gamma Ray

from 5672' to 4000'.

4.) RFT-GR at 5446'; 5077'; 4901'; 4659'; 4110'.

5.) Mechanical Sidewall Cores at 5462'; 5455';

5446'; 5275'; 5171'; 5077'; 5041'; 5013'; 4902';

4659'; 4655'; 4646'; 4536'; 4401'; 4350'; 4315';

4142'; 4141.5'; 4114'; 4109'; 3059'.

Log Tops: Green River Formation @ 1438'; Horsebench Ss @ 2171'; Second Garden

Gulch @ 3779'; Y-3 @ 4102'; Y-5 @ 4348'; Yellow Marker @ 4398'; Douglas Creek @ 4566'; R-2 @ 4644'; Second Douglas Creek @ 4798'; Green Marker @ 4936'; G-3 @ 5008'; Carbonate Marker @ 5404'; B-1 @ 5442'; Total Depth @

5700'.

Zones of Interest: 3055' to 3064': 9' with 14-17% porosity

Y-3 @ 4102' to 4144': 21' with 14-18% porosity

4313' to 4321': 8' with 11-12% porosity

Y-5 @ 4344' to 4354': 10' with 8% porosity

Yellow Marker @ 4398' to 4403': 5' with 17-21% porosity

4524' to 4538': 14' with 10-18% porosity

R-2 @ 4634' to 4663': 19' with 10-16% porosity

4900' to 4904': 4' averaging 11% porosity

G-3 @ 5008' to 5042': 34' with 8-10% porosity

5075' to 5079': 4' with 10-13% porosity

5169' to 5172': 3' with 12-13% porosity

B-1 @ 5442'-5463': 19' with 10-13% porosity

Note: The following pages contain log excerpts over zones of interest.

# COMPANY: BALCRON OIL COMPANY

**MONUMENT FEDERAL 33-8** WELL:

MONUMENT BUTTE FIELD:

Logger On Bottom

Unit Number Recorded By

Witnessed By

Time

FEB-26-1994


2009 CASPER


CHRIS PRESMYK


**ROY CLEMENT, AL PLUNKETT** 


SEE LOG


COUNTY: DUCHE	SNE	STAT	TE:	UTAH	
MONUMENT BUTTE MONUMENT BUTTE NW/SE MONUMENT FEDERAL 33-8 BALCRON OIL COMPANY LOCATION LOCATION LOCATION Set 18861 S	berger			TED POR	OSITY
MONUMENT BUTTE NW/SE MONUMENT FEDERAL 33	O' FEL			Elev.: K.B. G.L. D.F.	5328 F 5318 F 5327 F
- : Drilling Measured	From: KB	UND LE	VEL	Elev.: <u>5318</u> 10.0 F abov	F e Perm. Datum
Company:  API Set	ial No.	SECT 8		TOWNSHIP 9S	RANGE 17E
Logging Date	FEB-26-1994				
Run Number	1				
Depth Driller	5700 F				
Schlumberger Depth	5700 F				
Bottom Log Interval	5698 F				<del></del>
Top Log Interval	2500 F				
Casing Driller Size @ Depth	8.625 IN	@	262 F		@
Casing Schlumberger	262 F				<del> </del>
Bit Size	7.875 IN KCL WATER				
Type Fluid In Hole Density Viscosity	8.4 LB/G				
Fluid Loss PH	6.4 CD/G				<del> </del>
Source Of Sample	MUD TANK				<u> </u>
RM @ Measured Temperature	0.290 OHMM	@ 6	DEGF		@
RMF @ Measured Temperature	0.290 OHMM		0 DEGF		@
RMC @ Measured Temperature		@			@
Source RMF RMC	MEAS	NO SAM	APLE		
RM @ BHT RMF @ BHT	0.132 @ 140	0.132	@ 140	@	@
Maximum Recorded BHT	140 DEGF				
Circulation Stopped Time	FEB-26-1994		1800		
















COMPANY: BALCRON OIL COMPANY WELL: BALCRON MONUMENT FEDERAL NO. 33-8 COATION: NW SE 1980 FSL 81 1980 FEL) SEC. 8 - T9S - R17E DUCHESNE COUNTY, UTAH DEPTH LOGGED 1400 - 5700 DATE: 19 FEB 94 - 27 FEB 94 KB: 5328 GL: 5318 GEOLOGIST: ROY L. CLEMENT CONTRACTOR: UNION DRILLING RIG 17 DRILLING FLUID: AIR/FOAM 272' - 3853' KCL/WATER 3853' - TD Peresity DIL Show		1	1	T	1	1		1	1			Γ			T	1							T-	1	<b></b>	1		Т	Т—		····	
1907 SLIGO LANE   BALCLINGS, MONTAWA 59106   (406) 656-95/4   CONTIDENTAL	<u> </u>	<del>                                     </del>	_			-	-			-	<u> </u>														_	<del> </del>						
1907 SLIGO LANE   BALCLINGS, MONTAWA 59106   (406) 656-95/4   CONTIDENTAL		1	-	1	ļ	ļ				-																						
1907 SLIGO LANE   BALCLINGS, MONTAWA 59106   (406) 656-95/4   CONTIDENTAL																								<u> </u>						<del>                                     </del>		
1907 SLIGO LANE   BALCLINGS, MONTAWA 59106   (406) 656-95/4   CONTIDENTAL		├	├	-			<del> </del>	<del> </del> -							├	<del> </del>	<del> </del>						<u> </u>	<del> </del>		<del> </del>						
1907 SLIGO LANE   BALCLINGS, MONTAWA 59106   (406) 656-95/4   CONTIDENTAL		1		-	<del>-</del>	-	-				ļ	G/	F	M	A	17		CC	) <i>/</i> /	5/	II TI	NG		<b> </b>	-	<u> </u>						
### BILLINGS , MONTANA 59106  (406) 656-95/4  COMPANY: BALCRON OIL COMPANY  WELL: BALCRON MONUMENT FEDERAL NO. 33-8  COCATION: NW SE (1980' FSL & 1980' FEL) SEC. 8-T9S-RITE  DUCHESNE COUNTY , UTAH  DEPTH LOGGED: 1400' - 5700' DATE: 19 FEB 94-27 FEB 94  KB: 5328' GL: 5318'  GEOLOGIST: ROY L. CLEMENT  CONTRACTOR: UNION DRILLING RIG 17  DRILLING FLUID: AIR/FOAM 272'-3853'  KCL/WATER 3853'-TD		1		1	<b> </b>		1	-		1				ŀ	1		1	•		1												
BILLING S, MONTANA 59106				1_									1	90	1	5		GC		-A	NE											
COMPANY: BALCRON OIL COMPANY  WELL: BALCRON MONUMENT FEDERAL NO. 33-8  COCATION: NW SE (1980' FSL & 1980' FEL) SEC. 8-T9S-R17E  DUCHESNE COUNTY, UTAH  DEPTH LOGGED: 1400' - 5700' DATE: 19  KB: 5328 GI: 5318'  GEOLOGIST: ROY L. CLEMENT  CONTRACTOR: UNION DRILLING RIG 17  DRILLING FLUID: AIR/FOAM 272' - 3853'  KCL/WATER 3853' - TD							<u> </u>				D	11 1			} .	1 3	i	, ,		1			40	├	<del> </del>	├			-		-	
COMPANY: BALCRON OIL COMPANY WELL: BALCRON MONUMENT FEDERAL NO. 33-8 COCATION: NW SE (1980' FSL & 1980' FEL) SEC. 8 - T9S - R17F DUCHESNE COUNTY, UTAH DEPTH LOGGED: 1400' - 5700' DATE: 19 FEB 94 - 27 FEB 94 KB: 5328 GL: 5318' GEOLOGIST: ROY L. CLEMENT CONTRACTOR: UNION DRILLING RIG 17 DRILLING FLUID: AIR/FOAM 272' - 3853' KCL/WATER 3853' - TD		}		-			-				DI	$L_L$	II	70	ν,		70	7V 7	H	VZ		9/0	10	OKA E	3 %	3 2003 E	gazana.	N	\ T	1	<b>A</b>	2
COMPANY: BALCRON OIL COMPANY WELL: BALCRON MONUMENT FEDERAL NO. 33-8 COCATION: NW SE (1980' FSL & 1980' FEL) SEC. 8 - T9S - R17E DUCHESNE COUNTY, UTAH DEPTH LOGGED: 1400' - 5700' DATE: 19 FEB 94 KB: 5328 GL: 5318' GEOLOGIST: ROY L. CLEMENT CONTRACTOR: UNION DRILLING RIG 17 DRILLING FLUID: A1R/FOAM 272' - 3853' KC-/ WATER 3853' - TD		1		1-	<u> </u>	-	1	<b> </b>					7	41	6	6	5	6-	Q/	5/2	2			N				-				
WELL: BALCRON MONUMENT FEDERAL NO. 33-8  LOCATION: NW SE (1980' FSL & 1980' FEL) SEC. 8-795-R17E  DUCHESNE COUNTY, UTAH  DEPTH LOGGED: 1400' - 5700' DATE: 19 FEB 94 - 27 FEB 94  KB: 5328 GL: 5318'  GEOLOGIST: ROY L. CLEMENT  CONTRACTOR: UNION DRILLING RIG. 17  DRILLING FLUID: AIR/FOAM 272' - 3853'  KCL/WATER 3853' - TD		1												7.0	<u> </u>				<u> </u>			*			V				1 4	1	-	
WELL: BALCRON MONUMENT FEDERAL NO. 33-8  LOCATION: NW SE (1980' FSL & 1980' FEL) SEC. 8-795-R17E  DUCHESNE COUNTY, UTAH  DEPTH LOGGED: 1400' - 5700' DATE: 19 FEB 94 - 27 FEB 94  KB: 5328 GL: 5318'  GEOLOGIST: ROY L. CLEMENT  CONTRACTOR: UNION DRILLING RIG. 17  DRILLING FLUID: AIR/FOAM 272' - 3853'  KCL/WATER 3853' - TD					<del>                                     </del>		<del> </del>	<del> </del>		<del> </del>		<del> </del> -						-					$\vdash$	F-	<del> </del>		<u> </u>					
WELL: BALCRON MONUMENT FEDERAL NO. 33-8  LOCATION: NW SE (1980' FSL & 1980' FEL) SEC. 8-795- RITE  DUCHESNE COUNTY, UTAH  DEPTH LOGGED 1400' - 5700' DATE: 19 FEB 94 - 27 FEB 94  KB: 5328 GL: 5318'  GEOLOGIST: ROY L. CLEMENT  CONTRACTOR: UNION DRILLING RIG. 17  DRILLING FLUID: AIR/FOAM 272' - 3853'  KCL/WATER 3853' - TD			<u> </u>	-	-	-	-	-							-														-			
WELL: BALCRON MONUMENT FEDERAL NO. 33-8  LOCATION: NW SE (1980' FSL & 1980' FEL) SEC. 8-795-R17E  DUCHESNE COUNTY, UTAH  DEPTH LOGGED: 1400' - 5700' DATE: 19 FEB 94 - 27 FEB 94  KB: 5328 GL: 5318'  GEOLOGIST: ROY L. CLEMENT  CONTRACTOR: UNION DRILLING RIG. 17  DRILLING FLUID: AIR/FOAM 272' - 3853'  KCL/WATER 3853' - TD		1	_	-		1	1	<del>                                     </del>		1	<u> </u>															1						
WELL: BALCRON MONUMENT FEDERAL NO. 33-8  LOCATION: NW SE (1980' FSL & 1980' FEL) SEC. 8 - T95 - R17E  DUCHESNE COUNTY, UTAH  DEPTH LOGGED: 1400' - 5700' DATE: 19 FEB 94 - 27 FEB 94  KB: 5328 GL: 5318'  GEOLOGIST: ROY L. CLEMENT  CONTRACTOR: UNION DRILLING RIG 17  DRILLING FLUID: A1R/FOAM 272' - 3853'  KCL/WATER 3853' - TD		1		<u> </u>	1_		上																									
WELL: BALCRON MONUMENT FEDERAL NO. 33-8  LOCATION: NW SE (1980' FSL & 1980' FEL) SEC. 8 - T95 - R17E  DUCHESNE COUNTY, UTAH  DEPTH LOGGED: 1400' - 5700' DATE: 19 FEB 94 - 27 FEB 94  KB: 5328 GL: 5318'  GEOLOGIST: ROY L. CLEMENT  CONTRACTOR: UNION DRILLING RIG 17  DRILLING FLUID: A1R/FOAM 272' - 3853'  KCL/WATER 3853' - TD		上	00	TA A	$\overline{D^{A}}$	VI	<b>.</b>	<del> </del>	<del> </del>	D 4		50	<u> </u>	<u> </u>				50	<u> </u>	NI.			-	├					├			
OCATION   NW SE (1980' FSL & 1980' FEL) SEC. 8 - T95 - R17E		1	V	ועוק		IA	<u> </u>	I		DE					VI.		U			XIX	ľ			-		-			ļ			
OCATION   NW SE (1980' FSL & 1980' FEL) SEC. 8 - T95 - R17E		1	W	F I	-	•	1_	1	-	RA	11-6	P	AF	_	NA	INC	IA	AF.	VIT.		FED	FR	AT.	A	in	=	17	_ 5	<b>_</b>			
DEPTH LOGGED   1400' - 5700' DATE : 19   FEB 94 - 27 FEB 94   KB : 5328   GL : 5318'   CONTRACTOR: UNION DRILLING RIG 17   DRILLING FLUID: AIR/FOAM 272' - 3853'   KCL/WATER 3853' - TD							1			UF	<u> </u>				1			1		L	i .		L		1	1	1	<u> </u>				
DEPTH LOGGED   1400' - 5700' DATE : 19   FEB 94 - 27 FEB 94   KB : 5328   GL : 5318'   CONTRACTOR: UNION DRILL ING RIG 17   DRILLING FLUID: AIR/FOAM 272' - 3853'   KCL/WATER 3853' - TD		<del> </del>	LC	XCA	TI	NC	<del> </del>	-	-	NW	<del>  S</del>	E-	<del>119</del>	80	F	SL	8	15	86	<del>}'</del> F	FL)	SI	ic.	8	<del>-</del> 7	99	-	R	7F			-
DEPTH LOGGED   1400   - 5700   DATE   19 FEB 94   - 27 FEB 94			_	-	_		-	_		<del> </del>	<u> </u>	<del> </del>			<del> </del>		<b></b>	ļ				•	<u> </u>	<b> </b>								
KB : 5328		Ϊ_	_	-		1	-			DU	CH	ES	ΝE		Ot	M	Y	,	力力	AH						1			<b> </b>			
KB : 5328		_	he	<b>b</b> =		-	<b>5</b>	En		101				70			_		_	10					-		_					
GEOLOGIST: ROY L. CLEMENT  CONTRACTOR: UNION DRILLING RIG 17  DRILLING FLUID: AIR/FOAM 272' - 3853'  KCL/WATER 3853' - TD		_	LE				כוכא	FU	<u> </u>	141	μU				V.	<del> </del>	PΑ	TE.	•	13		3 94	<del>1 -</del>	<del>-</del>	~ (	<u> </u>	LD.	3	<del>†</del>	├		-
GEOLOGIST: ROY L. CLEMENT  CONTRACTOR: UNION DRILLING RIG 17  DRILLING FLUID: AIR/FOAM 272' - 3853'  KCL/WATER 3853' - TD			KE	3 :	53	28	3	<del> </del>		GI	<del> </del>	53	18 <sup>1</sup>		-	<del> </del>		-						-		-			<u> </u>			
CONTRACTOR: UNION DRILLING RIG 17  DRILLING FLUID: AIR/FOAM 272' - 3853'  KCL/WATER 3853' - TD					L				ļ	1						-								1						1		
DRILLING FLUID: AIR/FOAM 272' - 3853'		#	GE	OL	OC	15	T			RO	Y	<b>上</b> .		LE	M	ĮŲ,																
DRILLING FLUID: AIR/FOAM 272' - 3853'		士	<b>_</b>	حبد		_	<del>_</del>								-	_		<del>                                     </del>					-	┼─	<del> </del>	<del> </del>	<del>                                     </del>		-	-		
KCL/WATER 3853 - TD		┼─	بال	ДΥТ	LZ E	لتلا	UR	-	<del>                                     </del>	UN	וטון		DK.		III	φ	ZIC.						F-	-	_			<del>                                     </del>		-		<u> </u>
KCL/WATER 3853 - TD		<b>—</b>	DR	11-1	IN	6	FI	HIP		ΔIF	1	FA	2 114		97	<b>b</b> '		821	:=!					$\vdash$	<u> </u>		二	<u> </u>	_	_		
					111	上		711	Ψ.	-								70	<u> </u>							1						
		1						<u> </u>	<u> </u>	KC	L	W	TE	R	38	53	<u>'</u> -	+ T	D				-		-	-	-	-	<del> </del>			
Phrogity - Oil Show		+	-	+	+-	-		-																<del>                                     </del>	Ţ.	-	-					
				1	1	1			1	1						1	P	bro	ait.		l			hil	SI				1	<u> </u>		
































Form 3160-5 (June 1990)

#### UNITED STATES \* \* \* DEPARTMENT OF THE INTERIOR

FORM APPROVED

Duoget Dui	cau ivo.		/UI	•
Expires:	March	31,	1993	
				_

Lease	Designation	and	Serial	No

5. BUREAU OF LAND MANAGEMENT U-7978 SUNDRY NOTICES AND REPORTS ON WELLS 6. If Indian, Allottee or Tribe Name Do not use this form for proposals to drill or to deepen or reentry to a different reservoir. n/a Use "APPLICATION FOR PERMIT-" for such proposals 7. If Unit or CA, Agreement Designation SUBMIT IN TRIPLICATE n/a 1. Type of Well 8. Well Name and No. Oil Well Balcron Monument Federal #33 2. Name of Operator 9. API Well No. Equitable Resources Energy Company, Balcron Oil Division 43-013-31427 3. Address and Telephone No. 10. Field and Pool, or Exploratory Area P.O. Box 21017, Billings, Mr 59104

4. Location of Well (Footage, Sec., T., R., M., or Survey Description) (259-7860 Monument Butte /Green River
11. County or Parish, State NW SE Section 8, T9S, R17E Duchesne County, Utah 1980' FSL, 1980' FEL CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA 12. TYPE OF ACTION TYPE OF SUBMISSION Change of Plans Abandonment Notice of Intent **New Construction** Recompletion Non-Routine Fracturing Plugging Back Subsequent Report Water Shut-Off Casing Repair Conversion to Injection Altering Casing Final Abandonment Notice Other Report of First Production Dispose Water (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.) 13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\* First production on this well was on 3-21-94 at 11:30 a.m.

4. I hereby certify that the foregoing is true and correct  Signed Dobbeil Schuman	Coordinator of Environmental and Time Regulatory Affairs	Date3-21-94
(This space for Federal or State office use)		D
Approved by	Tide	Date


Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

# UTAH DIVISION OF OIL, GAS AND MINING EQUIPMENT INVENTORY


			Lease: State: Federal:_Y
Indian	: Fee:_	<del></del>	
Well N	lame: MONUM	ENT FEDERAL #33-8	API Number: 43-013-31427
Section	n: 8 To	nship: <u>95                                    </u>	17E County: DUCHESNE Field:
MONUM	ENT BUTTES		
Well S	Status: POW	Well Ty	oe: Oil: Y Gas:
PRODUC	TION LEASE	EQUIPMENT: Y C	ENTRAL BATTERY:
Y	Well head	Boiler(s)	CompressorSeparator(s)
	_ Dehydrator	(s) Shed(s)	Line Heater(s) Heated
Separa			
	_ VRU	Heater Treate	er(s)
PUMPS:	:		
	_Triplex	Chemic	Y Centrifugal
ITET M	ETHOD:		
Y	Pumpjack	Hydraulic	Submersible Flowing
GAS EG	WIPMENT:		
N	_ Gas Meters	N Purchase Nete	er <u>N</u> Sales Meter
MANUC.	MIMDED		SIZE
I ANNS:	NUMBER		5126
	Y	Oil Storage Tank(s)	
			BBLS
		Water Tank(s)	1-150 BARREL PIT TANK BBLS
		Power Water Tank	
			BBLS
		Condensate Tank(s)	
	••		BBLS
		Propane Tank	
REMARK	S: PUMP JA	CK POWER BY GAS MOTOR	AND RUN OFF CASING HEAD GAS. CENTRIFUGAL
PUMP	IS A TRACE	PUMP FOR GLYCOL; GAS	IS VENTED (NO METERS OR SALES LINE.
Locati	on central	battery: @tr/@tr:	Section: Township:
	?:	-	
Ingaca	tar.	DENNIS L. INGRA	M Date: 3/23/94
rusbec		DENNIS C. INGKA	

## CORE REPORT NO.

CUT: INTERVAL: \_ 4632' - 4662' R-2 Sand FORMATION: **RECOVER:** 23 Feb 94 DATE: Roy L. Clement








Compagnition of Long 1017	and a	************		
-1	D	ate of Treatn	nent : <u> </u>	3-94
Well Name <u>Monument</u> Fleld <u>Monument Ald</u>	Leb. 33-8 S	EC. <u>8</u> 1	WN. 25	RNG.172
			to there	,
Formation/Perforations:	reen Biner 154	44-63		
			THE STATE OF THE S	
			THE TOPPERSON FOR	40 (10 44) (\$1,159)
Treatment type: SAND F	RAC.	Total Numbe	r of Holes:	6
Treatment Company : <u>WE</u>	STERN		and Characte	
Volume Fluid	Conc.		rashin daling his	
Gal.				1 1 1
Gal	BPM	PS'		1
6000 Gal. 270 KC.				
		14.10		
500 Gal. //	2# 25,0		140	1000 #
500 Gal. //	3# 24,8		140	1500 #
1000 Gal, 11	47 24,0		140	4000 #
1800 Gal. 11	5# 24.1		140	! <i>/</i> 7)
1000 Gal. 11	6# 261	40	140	\$ 000 #
2000 Gal. //	6# 2614 1		30	12000 #
1900 Gal. 11	フ井 25.7 /	7/0 16/	30	13300 #
5441 Gal. 11 FL4	15/7 2715	150 -1		#
TOTAL FLUID PUMPED:	gal	%	AcId	,. , , ,
***************************************	gal		fluid	
TOTAL SAND VOL.:Z	24500 lbs. 201	40 s	and	
		<i>30</i> s	and :	;
	ibs/		and	
Flushed well with 544/	1	Ch WA	auxite	
ball sealers we	gal. of 2/3/5 re pumped. Was ball acti	on seen?	EA	
Avg. Treating Pressure =	$\frac{200}{100}$ psl, max = $\frac{21}{100}$		min = 1/2	psl,
Avg. Treating Rate = $26.6$ ISIP = $1650$ psi, 5 min. = $26.6$		140 000	mln = 24.	
Well will be shut in for 19	hrs, before bringing i		15 mln. = <u>/2</u>	y D psl.
PEMARKS: BUN TRACE		- a distributor ;	er en	*
1100			24. <b>建</b> 克鲁克 (15. 24 15. 14 15	<u>andrija</u> Agada <del>jagara</del> a
			e Night Hallon (A. C.	
			TO TO A STATE OF THE STATE OF T	2
	Mall alta Sun	andolor (m)	000	





Well Name	MANUAL BU	Le County Duc,	SEC	TWI	nt: <u>3-3</u> N.9.5, 1	RNG 174
F. 11	1	County NAC	redoll-	State	WAR	Andrew State
Formation/P	Perforations: $\underline{\mathscr{L}}$	treen ainey 1 5	444-65			
				15.3		
	(1 . 1 . 8)	7		:		
	Po: HCL Br		Total N	Number of	Holes:	6
	ompany: We	dienx	<del></del>	• , '	Characterl	10
Volume	Fluid	Conc.			E Carponal Constitution	
	Gal					
	al					
	al.			:		
			M			ar ida digigaria da Tanàng Salatan
G	al					#
	•		<del>~~~</del>	/	A A STATE STORY	#
			·		PONTO POR PARA PARA PARA PARA PARA PARA PARA	#
						#
						#
G						#
G	al			- / F. A.C.		#
					A Carrent Service	#
OTAL FLUID F		500 gal.	15 %	17CL	Acld	•
		192 gal. 2%	KCL W	IMER.	fluld	
OTAL SAND V	/OL.:	lbs		sand	and the second of the	
		lbs lbs		sand		. 21
		lbs	<del>- /-</del>	sand baux		1
lushed well v	vlth	gal, of		· · · · · · · · · · · · · · · · · · ·		
150 Parrels of Loa	_ball sealers we	re pumbea, was bo	III action see	n? HIH	HM HHT I	HT HHT H
		00 psl, max =		4174 7.7	CONT.	
wg. Treating	Rate = $Z_{i}$	bpm, max =	7,0	psi, mir bom mir	1 = 1000	psi. bpm.
SIP = 17.600	psi, 5 min, =_	psl, 10 mi	n. =	psl. 15 n	nin.	psl.
Vell will be sh	ut in for	hrs. before brin	iglng back fl	luid.		31 10
EMARKS: _5/			4 BALLS	PER BL	<i>52</i> ×	11
INTITAL BI SUBGE 13D	LL OFF. Pu	T 4.68PM, BACK	TO 2350	MT TB	PM	
Julio - (//)	- Pu	MP FOR BATE	13.0 BPM	H1 50	00 PS/	40
			o Cumondala	A	The second secon	






THE OF OIL GAS & MINING OF Transferrent: 3-7-94

Well site Supervision: Lace &


Well Name <u>Monun</u> Fleld <u>Monument</u>	rent feel 3:	3 - 8	.,_ SEC	te of Tred C. <u>-«"</u>	TWN 95	RNG_17E
Elald mondument	Count	y 12 14	Kerre		State	
Formation/Perforation	ns: <u>Green Riv</u>	27/	4656-	62		
Mari 1		T0001	·	A-1 Ni ma	har of Holos	24
Treatment type: 597 Treatment Company	ND FRAC WI : WESTERN	1 KACE	<u>-</u>	otal Inum	Sand Charac	eteristics
Volume Flu		Conc.		S	lze	Volume
Gal		•			`	•
Gal						
3000 Gal. 2%	HOLL WALFR PA	977 0	20.2	2940	,	
		2	20,2	2910	16/30	800
400 Gal. 1		<del>3</del>	20,3	2900	16130	1200
1100 Gal.		<u> </u>	2013	2880	16130	2000
500 Gal//			20,4	2730		3000
600 Gal. 1			20.4	2570	16130	4800
Gal,		7	20,4	2520		6300
Gal		0	2013	3330	-1-	
3086 Gal. 11	PL4311		. 6011		1.3.000	
Gal			<del></del>	ω	Δ	cld
TOTAL FLUID PUMPED				%		uld
	gal.		111	~ ^		-
TOTAL SAND VOL. :	<del></del>		161.	50	sand sand	,
		bs os			sand	
		os			bauxite	•
Flushed well with	gal.	of			e Si May 1	
Barrels of Load to Re	alers were pumper	d. Was l	ball action	on seen? BUR.		
Avg. Treating Pressure		asl may	( = 35		psl, min =	2450 p
Avg. Treating Rate =	20,2 bp				pm, mln =	
ISIP = 2/50 psl, 5	min. = 1580	psl, 10	mln. =_∠	1400	osl, 15 min. =_	
Well will be shut in for			oringing b	oack fluid		
PEMARKS: TAG FR	BC W/IR-192	150To1	PE,	··	1. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0.	+ , .
		<del></del>			A CONTRACTOR	
					1. 14 ma gradus 1	and the second second
						, <del></del>






BALCRON ( 1001 Lowb Ave PO Box 2101) Billion, MI 59	OIL DIVISION		nw OF OIL.	GAS & MINING			
Billi∧gis, MT 59	104-1017		DIV. O. C.L.	Date of	Treatment : _	3-7-9	4
Well Name ./.	Brown ex many	- Red.	33-8	SEC.	TWN_2	2.5 RNC	17E
Well Name	12 RICE BL	itte co	unty Duc	Respe	_ State ut	il	
Formation/Pe	6	Claren &	1.04/4	1656-62	·		
Formation/Pe	ertorations: "A	7/12110 21	((()))		· ·		
					<del>`</del>		
	pe: HCL BA	REAK I	POWN	_ Total N	lumber of Ho	ies: <u>24</u>	
Treatment (9)	ompany: 10	ection			•	naracterIstle	S
	Fluid		Conc.	:	Slze	Vol	ume
Volume	ridio						
, G							
G	;al					•	
G	Gal						: 4
G	Sal						#_
	Gal				/		<del></del>
G	•						# #
; G	Sal						#
.)** G	al	<del></del>					#_ #
	Sal						#_
	Sal						<u>#</u>
	9al				Hel	A 1-1	<u> </u>
TOTAL FLUID	PUMPED:	500	gal.	15%	MCN	Acid fluid	
			gal				
TOTAL SAND	VOL.:		lbs		sand sand		
			lbs lbs		sand		
			IDs	1	bauxl		
	Lauth		gal. of		- 1 (AP-7)		IFF.
Hushed Wei	ball sealer	s were pur	nped. Was	s ball action se	90n? <i>]}[]}_</i> 3UR.	7/ 117/ 11	11.
Barrels of Lo	ad to kecov	2200	nd m	TV 1 5000	nlm <sup>2</sup> lag	1600	
							bpm
////	47 mai 5 1001	<b>^</b> =	Dat. I	O 11111 b =		าไท. ๒	psi
14/-11/-11/	about in for		TIS. DEIDI <del>O</del>		11 11010		
			Eal	4 0/11	ren un	5% 173,9	BPM.
NITIAL	BREAMAI	330073	7 1000	<i></i>	OBPM AT	5440 PS/	* '1
SUBGE	DIIAN OF		Administration of the second				
	1		18/6	ell site Superv	Islor: 2 7cl	3. Grille	<u> </u>
			446	3113110 00POI4	· · · · ·	T NOW #6.	사용R= 3-





		1		UIL, UIL	Date of	Treatment	:3-9	-94
Well Nam	no Monume	nt les.	33-8 untv 8	uched	SEC{	ブロー TWN	95 utak	RNG
	n/Perforations:	aronn	Dines	14139	3-44			
Formation	n/Perroralions: _	MICE TO Y	receip of					
			<del> </del>	<del></del>				
Treatmen	nt type: HCL	BREAK DO	ou's	sTG. 1	Total N	lumber of	Holes:	24
	of Company: _/				_	Sand	• •	
Volume	Fluid		Cond	٥	:	Size		Volume
	 _ Gal							
	_ Gal							
	_ Gal					,		
	_ Gal							
	_ Gal							<del> </del>
	_ Gal							
	_ Gal							
	_ Gal	<del> </del>				<del></del>		
	_ Gal		<del></del>	•••		/ <u>.</u>	Section 1	
	_ Gal			······································		<del></del>		
	_ Gal					<del>/</del>		
TOTAL FLU	JID PUMPED:	500	jal <u>.</u>	13	7 %	HCL	Acid	
							fluid	
TOTAL SAI	ND VOL. :		_ lbs		1	sand	1	
			lbs			sanc	i	
			_lbs _lbs.		1,	sanc		
,							XII O	
Flushed w		s were pum 9	al. of oed. Wa	s ball a	ction se	en? 441	Hed	
Barrels of	Load to Recovi	er	4/		Br	1R. <i>NO</i>	BALL O.	
Avg. Treat	ting Pressure =	1500	psl, m	ax ≔_£	600	psl, ml	n = <u>/2</u> .	30 ps
Avg. Treat	ting Rate =3	,0	ppm, m	ax =	3,4	_ ppm, m	In ≃ <u>~~/</u> min =	<u> </u>
	psi, 5 mlr be shut in for	). =	psi, i s. before	brinain	a back	psi, 151 fluid.	· · · · · · · · · · · · · · · · · · ·	p/8/
	SPOT ACID				•		15 PE	R BBL.
ENIMICAS:	BREAK AT 2	830 PS;	BT 2,2	BPM.	BACK	TO 235	1 P53 H	7 4.0 BPP
	BALLS OFF,			E 8.0	BPM	AT 260	D. P51	
		<u> </u>			<del> </del>			, ,
			We	ell site Si	upervisi	or: Da	le Shrix	lin
					•		- //	






DIV. OF OIL, GAS	& MINI	NG	eatment :	<b>♂</b> -	9-	94
	Date	Of Ite		<u></u>		
77. <b>4</b>			T) A (A (			

Treatment typ		BEAK DOW	oN 516-	, 2 Total			
Volume	Fluid	2012/11	Conc.		Slze	Characte	Volume
					. <b></b>		
					_		
G	al						
							# #
					// /	,	#
					1 :		#
					1		#
				*			#.
	al			····			<u> </u>
TOTAL FLUID F	PUMPED:	<i>500</i> gal.		15 %	HCL	Açid	
		gal.				fluld	
TOTAL SAND	VOL.:						
	_,		os	<del></del>	sanc		
	<del> </del>		DS, DS,		sanc baux		•
Flushed well v	with	gal.	of	***			
96	ball sealers	were pumped	d, Was bo	all action s	een? BLTR.		LOFF
Ava Treating	Pressure =	2600 p	sl. max	= 4950	psl, ml	n = 12	80 psl.
Ava. Ireatina	Kaie =2	<u>,                                    </u>	III, IIIOX 1	- · · · · · ·	bpm, m	In = 4,0	•
ISIP = 430	psi, 5 mln	, <del>=</del>	psl, 10 m	nin. =	psl, 15 į	nIn. =	psl.
Well will be st	nut in for	hrs. b					لمديد ومضر
PEMARKS: 51	POT ACID		To SEI	PKR.		BALL PA	ER BBL.
WITH BRE	AK AT 1280 BLLS OFF	PSI 195 4.2	BPM, BA B. RATE	ACK TO 1	1960 PSI D	91.912	BPM





DIV. OF OIL, GAS & MINING Date of Treatment: 3 - 9 - 94nonument fed. 33-8 Led. 33-8 SEC. 8 TWN. 95 County Duckerne State With Formation/Perforations: Green River / 4104-16, 4138-44 Treatment type: SAND JERAC. Treatment Company: WESTERN Sand Characteristics Volume Slze Conc. Volume 台广 KPM Gal. Gal. 2% KCL WATER 2# 16130 500 Gal // 16130 24,7 4.500 1500 Gal. 24,7 16130 1800 Gal. 11 2000 Gal. 11 2000 Gal. 11 6# 24,7 2500 Gal.\_ 25,0 27.30 Gal. 11 FLUGH Gal. \_\_\_ \_\_\_\_\_ gal.\_ Acld TOTAL FLUID PUMPED: fluld gal.\_\_\_ lbs. 16130 5220 sand ... TOTAL SAND VOL. : lbs. sand sand lbs. bauxite Flushed well with \_\_\_\_\_ gal. of \_\_\_\_\_ ball sealers were pumped. Was ball action seen?

Barrels of Load to Recover \_\_\_\_\_ 462 BLTR. Avg. Treating Pressure = 2500 psl, max = 2950 psl, min = 2050 Avg. Treating Rate = 24.7 bpm, max = 25.1 bpm, mln = 17.0 bom. ISIP = 1750 psl, 5 mln. = 1400 psl, 10 mln. = 1350 psl, 15 mln. = 1320 psl, Well will be shut in for 16 hrs. before bringing back fluid. ?EMARKS:

Well site Supervision: 12

#### DAILY OPERATING REPORT

BALCRON MONUMENT FEDERAL #33-8

Location: NW SE Section 8, T9S, R17E

Duchesne County, Utah 1980' FSL, 1980' FEL

PTD: 6,000' Formation: Green River

Monument Butte Field Elevations: 5,318.6' GL

Contractor: Union Drilling #17

Operator: Batcron/EREC

Spud: 2-14-94 @ 12 noon

Casing: 8-5/8" 24# J-55 @ 262' KB

5-1/2" 15.5# K-55 @ 5681.25'

Tubing:

2-14-94 Well spud @ 12 noon by Leon Ross Drilling.

2-9-94 Present Operation: Start location.

2-10-94 Present Operation: Work on location.

2-11-94 Present Operation: Finish location.

2-14-94 Present Operation: Move Leon Ross Drilling on and spud @ 12:00

Noon. Drill to 260'.

2-15-94 Present Operation: Surface pipe and cement.

Run 6 joints 8-5/8" casing and cement by Western Company with 150 sxs Class "G" cement and 2% CCL, 1/4# per sx Celeflake. 5 BBLS good cement back to pit. Plug down @ 1:30PM. Four BLM people

witnessed the running of casing and cement.

Guide shoe .60'
1 jt. - 8 5/8" 24# shoe joint 42.22'
Baffle plate --5 jts. - 8 5/8", 24#, J-55 211.21'
254.03'

Set @ G.L. 252' Union Drilling KB @ 262'

2-16-94 Present Operation: Install pit liner.


2-19-94 TD: 670' (408') Day 1

MW 8.3 Vis 26 Formation: Uintah

Present Operation: Drilling

Move & rig up. Nipple up BOP. Test BOP and manifold to 2000#. Had to run packer to test casing to 1500# - O.K. Drill cement,

drill, survey, change air head rubber. Drill. DC: \$10,803 CC: \$26,778



--TIGHT HOLE--

BALCRON MONUMENT FEDERAL #33-8 Location: NW SE Section 8, T9S, R17E Duchesne County, Utah


--TIGHT HOLE--

2-20-94 TD: 2,035' (1,365') Day 2
MW 8.3 Vis 26
Formation: Green River
Present Operation: Drilling
Drill, survey, clean on rig.
DC: \$18,025

CC: \$44,803

2-21-94 TD: 3,125' (1,090') Day 3
MW 8.4 Vis 26
Formation: Green River
Present Operation: Drilling
Drill, survey, clean on rig.
DC: \$14,767

CC: \$59,570



2-22-94 TD: 3,853' (728') Day 4

MW 8.4 Vis 26

Formation: Green River

Present Operation: Wash to bottom

Drill, survey, load hole with fluid & circulate. Trip out for bit; trip in hole; wash to bottom 30'.

DC: \$15,742 CC: \$75,312

2-23-94 TD: 4,493' (640') Day 5
Formation: Yellow Zone
MW 8.4 VIS 26 pH 9.5
Present Operation: Drilling
Drill, survey, & clean on rig.
DC: \$9,385 CC: \$84,697

2-24-94 TD: 4,710' (217') Day 6
Formation: Red Zone
MW 8.4 VIS 26 pH 9.5
Present Operation: Drilling
Drill, circ, TOH for core bbl. PU core bbl & survey tools. TIH,
cut 30' of core, TOH & LD core. TIH & drill ahead. Recover 281/2' of core.
DC: \$7,502 CC: \$92,199

2-25-94 TD: 5,252' (542') Day 7
Formation: Green Zone
MW 8.4 VIS 26 pH 9.4
Present Operation: Drilling
Drill, survey, & clean on rig.
DC: \$8,023 CC: \$100,222



BALCRON MONUMENT FEDERAL #33-8 Location: NW SE Section 8, T98, R17E Duchesne County, Utah

--TIGHT HOLE--

5,500' (248') Day 8 2-26-94 TD: Formation: Green River Vis 26 pH 9.5 MW 8.4 Present Operation: Drilling Drill, circulate, trip out, pick up core barrel and trip in hole. Cut 30' core and trip out. Lay down core and core barrel, trip in and drill. CC: \$126,706 DC: \$26,484

2-27-94 TD: 5,700' (200') Day 9
Formation: Green River
MW (could not read) Vis 26 pH 9.5
Present Operation: Logging
Drill, clean on rig, weld on rig, circulate, trip out for logs.
Log well.
DC: \$6,570 CC: \$133,276

2-28-93 TD: 5,700' (0') Day 10
Formation: Green River
Present Operation: Running 5-1/2" Casing
Log well. Trip in hole, lay down drill pipe and drill collars.
Test BOP. Run 5-1/2" casing.
DC: \$23,790 CC: \$167,066

3-1-94 TD: 5,700' (0') Day 11 Present Operation: RDMO. Run 5-1/2" csg & cmt as follows: .80' Guide Shoe 45.61' 1 jt 5-1/2" 15.5# shoe jt 1.10' Float Collar 5624.74' 128 jts 5-1/2" 15.5# K-55 5672.251 9.00' Landing Jt 5681.25' Csg set at 5633.74' PBTD

PBTD 5633.74' 20 centralizers Cmt by Western w/132 sxs Thrifty-Lite & tail w/257 sxs 50-50 POZ. Plug down @ 9 a.m., release rig @ 1:00 p.m. 2-28-94. Set slips, ND BOP, clean mud tanks. RU on Balcron Monument Federal

#43-7. DC: \$54,770

BALCRON MONUMENT FEDERAL #33-8

Location: NW SE Section 8, T98, R17E

Duchesne County, Utah

--TIGHT HOLE--

3-2-94 Completion
Level location. Set rig anchors. Set tanks & rig pump. MIRU
Cannon Well Service Rig #2. Spot tbg trailer at well. NU BOP.

SDFN. DC: \$18,696 CC: \$240,532

Completion
TIH w/csg scraper & bit, tag PBTD @ 5640' KB. Circ hole clean w/125 bbls 2% KCL wtr. TOOH w/scraper & bit. RU Schlumberger to bond log & perf 5444'-63' (4 SPF). RD Schlumberger, cmt top 2390' KB. TIH w/RBP, retrieving tool, one 2-7/8" x 4' sub, 1 seat nipple, 173 jts 2-7/8" tbg. Set BP @ 5477' KB, pull 3 jts. EDT @ 5379' KB. SWIFN.

DC: \$7,220 CC: \$247,752

DC: \$7,220 CC: \$247,75

Completion
RU Western to do HCL breakdown 5444'-63', 76 holes refer to
treatment report. RU Western to frac 5444'-63' refer to treatment
report. Start frac. SWIFD.
CC: \$25,438
CC: \$273,190

DC: \$25,438 CC: \$273,190

Completion
CP - 740 psi. TIH w/retrieving tool, 2-7/8" x 4' sub, 5-1/2" HD
packer, SN & 171 jts 2-7/8" tbg. Tag sand @ 5416' KB, circ down to
5477'KB, set packer @ 5379' KB. Made 21 swab runs, recovered 126
BW, trace oil. Release packer, tag sand @ 5468' KB. Circ down to
BP, release BP, try to reset BP @ 4699' KB, would not hold. TOOH
w/tbg & tools. SWIFN.
DC: \$1,850

CC: \$275,040

Completion
TIH w/RBP, retrieving tool, 2-7/8" x 4' sub, SN & 148 jts 2-7/8"
tbg, set BP @ 4687' KB. TOOH w/tbg & retrieving tool. SWIFN.
DC: \$659

CC: \$275,699

Completion
RU Schlumberger to perf 4656'-62' (4 SPF). RD Schlumberger. TIH
W/144 jts 2-7/8" tbg & one 2-7/8" x 10' blast jt. EOT @ 4564' KB.
RU Western to do HCL breakdown refer to treatment report. Could
not surge balls off perfs, run EOT down past perfs, reset EOT @
4654' KB. Pump acid into perfs, reset EOT @ 4564' KB. Frac well
refer to treatment report. SWIFN.
DC: \$25,158

CC: \$300,857

BALCRON MONUMENT FEDERAL #33-8
Location: NW SE Section 8, T9S, R17E
Duchesne County, Utah

--TIGHT HOLE--

3-8-94 Completion

CP & TP - vac. Tag sand @ 4607' KB, circ down to 4692'KB. TOOH w/2-7/8" tbg. TIH w/retrieving tool, 2-7/8" x 4' sub, HD packer, SN, & 146 jts 2-7/8" tbg. Set packer @ 4637'KB. Made 21 swab runs, recovered 126 bbls of fluid (2 oil, 124 BW, good gas). Last 4 runs fluid level stable @ 3100', no sand on last 3 runs. Release packer, tag sand @ 4665' KB, circ down to BP @ 4692' KB (BP). Release BP, reset BP @ 4168' KB. TOOH w/131 jts 2-7/8" tbg, SN, HD packer, 2-7/8" x 4' sub & retrieving tool. SWIFN. Load to recover 638 BW.

DC: \$1,665 CC: \$302,522

3-9-94 Completion

CP - 0 psi. BP set @ 4168'KB. RU Schlumberger to perf 4104'-16' & 4138'-44'. RD Schlumberger. RIH w/retrieving head, one 2-7/8" x 4' sub, HD packer, SN, & 130 jts 2-7/8" tbg. Set packer @ 4125'KB. EOT @ 4133'KB. RU Western to do HCL break down on perfs 4104'-16'KB refer to treatment report. Had communication between 4638'-44' & 4104'-16'. Reset BP @ 4133'KB & set packer @ 4070'KB. RU Western to do HCL break down on 4138'-44'KB refer to treatment report. TOOH w/2-7/8" tbg, SN, HD packer, 2-7/8" x 4' sub & retrieving head. TIH w/126 jts 2-7/8" tbg, one 2-7/8" x 10' blast jt, EOT @ 4001'KB. RU Western to sand frac 4104'-16' & 4138'-44'. Tag frac w/single isotope trace refer to treatment report. SWIFN. Load to recover 1210 BW.

DC: \$6,827 CC: \$309,349

3-10-94 Completion

CP - 0, TP - 0. Tag sand @ 4063'KB, circ down to 4168'KB (BP), TOOH w/2-7/8" tbg. TIH w/retrieving tool, 2-7/8" x 4' sub, 5-1/2" HD packer, SN, & 128 jts 2-7/8" tbg, set packer @ 4070'KB, EOT @ 4075'KB. Made 30 swab runs, recovered 180 bbls of fluid - 3 oil, 177 wtr, good gas. Fluid stable last 5 runs. SWIFN. Load to recover 1033 BW.

DC: \$1,825 CC: \$311,174

3-11-94 Completion

CP - 0, TP - 5 psi. Made 15 swb runs, recovered 90 bbls of fluid; 2 oil & 88 wtr, good gas, no sand last 5 runs. Fluid level stable @ 2900' last 5 runs. Release packer, tag sand @ 4118' KB. Circ down to 4167'KB. Release BP & TOOH w/tbg & tools. SWIFN. Load to recover 941 BW.

DC: \$1,300 CC: \$312,474

BALCRON MONUMENT FEDERAL #33-8 Location: NW SE Section 8, T9S, R17E Duchesne County, Utah

--TIGHT HOLE--

Completion 3-14-94

RU Schlumberger to run dipole sonic imager, lower mode log & GR single trace log. RD Schlumberger. ND BOP. TIH w/tbg production stering: T---th Donth KR

	<u>Length</u>	<u>Depth KB</u>
1 jt 2-7/8" EUE J-55 8RD 6.5#	30.52'	5506.83'
1 Perf Sub 2-7/8" x 3'	3.20′	5476.31'
1 Seat Nipple	1.10'	5473.11'
45 jts 2-7/8" EUE J-55 8RD 6.5#	1410.45'	5472.01'
1 Tbg Anchor 2-1/2" x 5-1/2" (Trico)		4061.56′
128 jts 2-7/8" EUE J-55 8RD 6.5#	4049.21'	4059.21'
KB	10.00'	
NU well head. SWIFN.		

CC: \$319,019 DC: \$6,545

3-15-94 Completion

TIH w/rod production string:

1 BHP, 2-1/2" x 1-1/2" x 16' RWAC w/PA plunger, Pump #1041 (Trico)

218 3/4" x 25' D-61 (Trico)

One 3/4" x 4' pony

One 1-1/4" x 22' polish rod SM (Trico)
Clamp rods off. Pressure test well to 1000# - OK. RDMO.

DC: \$8,627 CC: \$327,646

3-21-94 Completion

Start well pumping @ 11:30 a.m. 4.5 SPM, 87" stroke. Lufkin model LM-228D-86T S/N B129532A - 525673. Engine: Ajax CMA 8-1/2"x10", S/N 62760. Tanks: 12'x20' 400bbl S/N 03850-23118. Contract pumper

Jody Mecham.


DC: \$33,969 CC: \$361,615

June 1990) DEPARTMEN	TED STATES IT OF THE INTERIOR LAND MANAGEMENT	FORM APPROVED Budget Bureau No. 1004-0135 Expires: March 31, 1993  5. Lease Designation and Serial No.
Do not use this form for proposals to dr	AND REPORTS ON WELLS  III or to deepen or reentry to a different reservoir.  R PERMIT—" for such proposals	U-7978  6. If Indian, Allottee or Tribe Name n/a
SUBMIT	IN TRIPLICATE	7. If Unit or CA, Agreement Designation  n/a
1. Type of Well  Oil  Well  Well  Other  2. Name of Operator  Equitable Resources Frency Company,  3. Address and Telephone No.	Balcron Oil Division (259-7860	8. Well Name and No.  Balcron Morament, Federal #33- 9. API Well No. 43-013-31427 10. Field and Pool, or Exploratory Area
P.O. Box 21017, Billings, Mr 59104  4. Location of Well (Footage, Sec., T., R., M., or Survey D  NW SE Section 8, T9S, R17E  1980' FSL, 1980' FEL	Nonument Butte / Green Rive 11. County or Parish, State Duchesne County, Utah	
12. CHECK APPROPRIATE BOX(	s) TO INDICATE NATURE OF NOTICE, REPO	RT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	
Notice of Intent  Subsequent Report	Abandonment Recompletion Plugging Back Casing Repair	Change of Plans  New Construction  Non-Routine Fracturing  Water Shut-Off
Final Abandonment Notice  13. Describe Proposed or Completed Operations (Clearly state a	Altering Casing  X Other Site Security Diagram	Conversion to Injection  Dispose Water (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

Attached is the Site Security Diagram for this well.

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

#### Equable Resources Energy Ampany Balcron Monument Federal 33-8 Production Facility Diagram



FOUTABLE RESOURCES CO MONUMENT BUTTE FED #33-8 U-007978 43-013-314-27 RITE Sec 8 T95 SURFACE SOIL PILE POW 1-150 BARREC SUBSULFACE SOUTH Pit Tank W/LEOK Detection 2-400 OIL W/ BURNER) 42.381 50 SHEETS 5 SQUARE 42.382 100 SHEETS 5 SQUARE MATTOWAL MASSING & Residue on Casing Head GAS LIVE Flouline WELLHRAD Rod Pump PropenE JACK A FNTRANCE

#### REPORT OF WATER ENCOUNTERED DURING DRILLING - FORM 7 (1/89)

1. Well name and number: <u>Belcron Monument Federal #33-8</u> API number: 43-013-31427							
2. Well location: QQ <u>NW SE</u> section <u>8</u> township <u>9S</u> range <u>17E</u> county <u>Duchesne</u>							
3. Well operator: Equitable Resources Energy Company, Balcron Oil Division  Address: P.O. Box 21017 phone: (406) 259-7860  Billings, MT 59104							
4. Drilling contractor: Union Drilling  Address: Drawer 40 phone: (304) 472-4610  Buckhannon, W 26201							
5. Water encountered (continue on reverse side if necessary)							
Depth Volume Quality from to (flow rate or head) (fresh or salty)							
No measurable water encountered during drilling operations.							
6. Formation tops: Geologic Report submitted separately.							
If an analysis has been made of the water encountered, please attach a copy of the report to this form.							
I certify that this report is true and complete to the best of my knowledge.							
Name Bobbie Schuman. Signature Bobbie Schuman  Title Regulatory & Frivironmental Specialist. Date 4-20-94							

Comments:

Form 3160-5 (June 1990)

# UNITED STATES DEPARTMENT OF THE INTERIOR TO TH

Accepted by the State of Utah Division of

Federal Approval of this

FORM APPROVED Budget Bureau No. 1004-0135

		Exhites:				
5.	Lease	Designat	ion	and	Serial	No.
	TT 7	070				

BUREAU OF L	AND MANAGEMENT	5. Lease Designation and Serial No.
SUNDRY NOTICES A	AND REPORTS ON WELLS II or to deepen or reentry to a different reservoir. R PERMIT—" for such proposals	U-7978 6. If Indian, Allottee or Tribe Name n/a
	IN TRIPLICATE '	7. If Unit or CA, Agreement Designation  n/a
1. Type of Well    X   Oil	· · · · · · · · · · · · · · · · · · ·	8. Well Name and No. Balcron Morument Federal #33-8
Equitable Resources Energy Conpany,  3. Address and Telephone No.	Balcron Oil Division	9. API Well No. 43-013-31427
P.O. Box 21017, Billings, MI 59104  4. Location of Well (Fuotage, Sec., T., R., M., or Survey De  NW SE Section 8, T9S, R17E	(406) 259–7860 scription)	10. Field and Pool, or Exploratory Area  Monument Butte/Green River  11. County or Parish, State
1980' FSL, 1980' FEL	s) TO INDICATE NATURE OF NOTICE, REPO	Duchesne County, Utah RT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	
Notice of Intent	Abandonment Recompletion	Change of Plans New Construction
Subsequent Report	Plugging Back Casing Repair	☐ Non-Routine Fracturing ☐ Water Shut-Off ☐ Conversion to Injection
Final Abandonment Notice	X Other Onshore Order #7	Dispose Water (Note: Report results of multiple completion on Well Cumpletion or Recompletion Report and Log form.)
give subsurface locations and measured and true vertice	pertinent details, and give pertinent dates, including estimated date of starting all depths for all markers and zones pertinent to this work.)*	

Any water produced by this well will be held in a produced water tank and trucked to a commercial disposal facility. The primary facility to be used is the R.N. Industries produced water disposal facility located in Section 9, T2S, R2W in Duchesne County, Utah. A copy of the State-issued permit for that facility is on file at the Vernal Bureau of Land Management. If for some reason the operator is unable to use this primary disposal facility, the produced water will be trucked to another State-approved disposal facility. If applicable, Operator has received approved Right-of-Way access to this well location for the Vernal Bureau of Land Management.

Oil, Gas (1) Date: 4-26-74 By:	9 	A	
I hereby certify hat the foregoing is frue and correct Signed Bobbie Schuman	Regula Tille Frviro	ntory and nmental Specialist	Date 4-20-94
(This space for Federal or State office use)			

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(November 1983)			IITED	STA	ΓES	SUBMI	T IN	DIEFTCV			Budget Expires	Hures Augi	au No. 1004-0137
((lormerly 9-330)		RT	NT OI	F THI	E IN	TERIOF	₹	ALCI	ither in iona on se side)		834 BEA	IGNATI	UN AND BERIAL NO.
	E	BUREAU	OF LAN	D MANA	GEME	NT ·			<u></u>		-7978	-:::::	THE OR TRIBE NAME
WELL CO	MPLETIO	N-OR	RECON	<b>APLETI</b>	ON F	REPORT .	AN	D LO	3 *	_ 0. 'F		ALLOT	TERE OR TRIBE NAME
In. TYPE OF WEL	L: (	WELL X	WELL		<del></del>	Other					IT AGRE	EMENT	NAME
b. TYPE OF COMP	PLETION:	DEEL-	pres [			Other		FIDE	TIF	<u>.</u> ! Pao	RM Est 1		NAME
2. NAME OF OFERAT					·1 D: -					Ba1	rus ja Kulton	men	t Federal
Equitable Res		ergy Com	oany, Ba	Laran O	II DIVI	<b>邢</b> 宣(	9			33	<del>-</del> 8		
P.O. Box 2101	17. Billing	s.MC	59104			IU/							, OR WILDCAT
4. LOCATION OF WELL				gcardunce	with an	TATT A	R		.	<u>M</u>	rument		te/Green River
At top prod. Into	980' FSL, 1		_					<b>→ €</b>					8, T9S, R17
At total depth					•	DIV. OF	DIL	GAS & M			,		
m total diplo				14. PE	RMIT NO.		DATE	1880-0	Higher	Y	O TTN'JO IEELDA		13. STARE
•					)13-314			2-20-93		l D	chesne	-	Utah
15. DATE SPUDDED	16. DATE T.D		1	COMPL. (	Really to	prod.) 18		VATIONS (D 318.6' G		RT, GR, 1	crc.)*		
2-14-94 20. TOTAL DEPTH, MD	2-27-		3-21		. IF MI'I.	TIPLE COMPL.		1 23, INT			NY TOOL	.8	CABLE TOOLS
57001	.	5633.74	' KB	.	HOM. M	n/a			->	Sfc -	- TD		n/a
24, PRODUCING INTER	YAL(S), OF TE	IIS COMPLE	TIUN-TOP,	BOTTOM,	A) BIANK	AD AND TVD)*						25	WAR DIRECTIONAL SURVEY MADE
5463'-4104'	' (	ireen Riv	ær	•							.•	.	NO
26. TYPE BLECTAIC A		NUR BE								<u> </u>			AS WELL CORED
IPIT, AIT,	NSC m	UD L	06,0		e/ccl,	2001			<u> </u>	クエ			Yes
28. CABING BIZE	WEIGHT, I	n./ft.	CASI			ort all strings	**************************************	r well)	ENTING	necond			AMOUNT PULLED
8-5/8"	2/4/		262'I		12-	1/4"	150	) sxs ''G'	" + ax	ditive	s		n/a
5-1/2"	15.		5681.2			7/8"		2 sxs Th			nd		n/a
		-			<del></del> -		2	257 sxs :	50-50	POZ.			
29.		LINER	RECORD				1	30.		TUBING	RECO	RD	
BIZE	TOP (MD)		M (MD)	SACKS CE	MENT*	SCREEN (M	D)	SIZE		DEPTH	BET (MI	9)	PACKER SET (MD)
n/a								2-7/8	3''	5506.	83'KB		_n/a
31. PERFORATION REC	oen (Interval	else and	number)			1 32.	A.C	ID SHOT	FRAC	TURE. C	EMENT	SQU	EEZE, ETC.
5 <del>444</del> !-63! (			4144': 52	2.200# 1	6/30	DEPTH INT							ATERIAL USED
4656'-62' (	(		in 19,8			54441-63	'		24,50	00# 20/	40 san	rd & :	25,300#16/30
4104'-16'		2% K	L wtr &										2% KCL water &
4138'-44' (	(4 SPF)	15% I	ICL.	•	•	76501 60				pallons			5700 gallons 2
				·	PROI	4652'-62							ns 15% HCL.
33.º DATE FIRST PRODUCTI	ION PA	ODUCTION	METHOD (F	lowing, go		umping—size	and t	ype of pun		water C	WELL	BTATUE	(Producing or
3-30-94		1-1/2"	insert P	mp									Producing
DATE OF TEST	HOURS TEST		OKE SIZE	PROD'N	I. FOR PERIOD	OIL-BBL.		I AM	r.	1 -	CN-BBL.	·	3
4-1-94	24		1/a	011,1	>	65 GAS-	M C.F.	200	WATER	<u> </u>	<del></del> 1	OIL GI	RAVITY-API (CORR.)
rlow. Tubing Press.	casino pres n/a	24	HOUR RATE			200		1	0			34	
34. DISPOSITION OF GA		for fuel, ve	nled, elc.)	1 0-							WITHES		
Used for fu	1.										ale Gr	iffi	<u>n</u>
35. LIST OF ATTACHA	IENTS												
36. I bereby certify	that the fores	oing and a	ttached in	formation	is comp	lete and corre	ct as	determine	d from	all ava	ilable re	cords	
						ılatory & I							20-94
SIGNED DA	one y	$\mathcal{U}\mathcal{U}$	11th//	_ TIT	TEWER	Laury & E			- 2pc		DATE		

\*(See Instructions and Spaces for Additional Data on Reverse Side)

FORMATION	TOP	воттом	description, contents, etc.		TOP		
	٠.		•	NAME	MEAS. DEPTH	TRUE VERT. DEPTH	
			•		and the second s		
	::		Core submitted separately.	Geologic Report s		tely.	
			•				
.*· •		·					
		· .	•	,,			
					#10 #10 #10 #10 #10 #10 #10 #10		

#### ROUTINE CORE ANALYSIS

#### **BALCRON OIL COMPANY**

43-013-31427 Sec 8 TS, RITE Balcron Monument Federal 33-8 Well Duchesne County, Utah

# CONFIDENTIAL

Prepared for:

BALCRON OIL COMPANY 1601 Lewis Avenue Billings, Montana 59104

**TR95-5646 September 1994** 

# **TerraTek**

TerraTek, Inc.

University Research Park 400 Wakara Way Salt Lake City, Utah 84108 U.S.A.

#### **ROUTINE CORE ANALYSIS**

#### **BALCRON OIL COMPANY**

# Balcron Monument Federal 33-8 Well Duchesne County, Utah

#### Prepared for:

BALCRON OIL COMPANY 1601 Lewis Avenue Billings, Montana 59104

Prepared by:

TerraTek, Inc.
University Research Park
420 Wakara Way
Salt Lake City, Utah 84108

**TR95-5646 September 1994** 

#### 1 INTRODUCTION

03 - 3

#### 1.1 Well Summary

Company:

BALCRON OIL COMPANY

County:

Duchesne

Well Name:

Balcron Monument Federal 33-8

State:

Utah

Field:

Monument Butte

Location:

Sec.8, T9S, R17E

Drilling Fluid:

Water Base

Elevation:

5350' KB

#### 1.2 Core Summary

Diamond coring equipment and water base drilling mud were used in the Balcron Monument Federal 33-8 well, located in Duchesne County, Utah, to obtain four-inch diameter conventional cores. The intervals and formation cored are listed below in Table 1-1. In addition, rotary sidewall coring equipment was used to obtain sidewall cores from the same well. Table 1-2 below lists the sidewall cores received.

Table 1-1 Core Interval Summary Conventional Core

Core Number	Depth Interval	Formation
1	4632' - 4662'	Green River
-	4662' - 5440'	Drilled Interval
2	5440' - 5470'	Green River

Table 1-2 Core Interval Summary Rotary Sidewall Cores

Core Number	Core Depth	Formation
1	3059.0	Green River
2	4109.0	Green River
3	4114.0	Green River
4	4141.5	Green River
5	4142.0	Green River
6	4315.0	Green River
7	4350.0	Green River
8	4401.0	Green River
9	4536.0	Green River
10	4646.0	Green River
11	4655.0	Green River
12	4659.0	Green River
13	4902.0	Green River
14	5013.0	Green River
15	5041.0	Green River
16	5077.0	Green River
17	5171.0	Green River
18	5275.0	Green River
19	5446.0	Green River
20	5455.0	Green River
21	5462.0	Green River

#### **TerraTek**

A representative of TerraTek, Inc. was at well site to retrieve the conventional cores and prepare them for transport to the TerraTek laboratory in Salt Lake City, Utah for analysis. Residual core fluids were preserved by wrapping the cores with plastic film. The sidewall cores were sealed inside glass jars at well site and delivered to the TerraTek laboratory by Balcron Oil personnel.

The following routine core analysis tests were performed as requested: component core gamma log on the conventional core; and fluid saturations, porosity, grain density, and permeability on both the sidewall cores and on the conventional cores. Conventional core tests were performed on full diameter samples obtained from intervals specified by Balcron Oil personnel.

#### 1.3 Distribution of Final Reports

Routine core analysis reports for the Balcron Monument Federal 33-8 well were distributed as follows:

Table 1-3
Distribution of Final Reports

Number of Reports	Recipient	Company Contact
4	Balcron Oil P.O. Box 21017 Billings, MT 59104	Keven Reinschmidt
1	Balcron Oil 275 County Road 120 Craig, CO 81625	Dale Griffin
2	Bureau of Land Management Vernal District Office 170 South 500 East Vernal, UT 84078	Ed Forsman

Number of Reports	Recipient	Company Contact
1	Utah Geological Survey 2363 South Foothill Boulevard Salt Lake City, Utah 84109	
2	State of Utah Division of Oil, Gas, & Mining 355 West North Temple Street 3 Triad Center, Suite 350 Salt Lake City, UT 84180	

#### 2 PROCEDURES

Upon arrival in the laboratory, the conventional cores were laid out on a core rack, the pieces were properly fitted together, and a component core gamma log was recorded. Full diameter samples for analysis were prepared from each foot of core within the intervals designated by Balcron Oil Company geologists. The samples were cut from the core using a diamond impregnated saw blade and fresh water as blade coolant. The sidewall cores were removed from the jars and drilling mud was cleaned from each surface using a damp rag. The ends were not trimmed until after fluid saturation and porosity testing was complete.

Also, 12 samples from the conventional cores were selected for retort analysis. These samples were obtained from full diameter core sample trimmed end pieces. The retort analysis performed on these samples provided preliminary fluid saturation and porosity results. Water and oil saturations were determined on 100 grams of crushed sample material, which was poured into individual bombs and placed in a retort furnace. The furnace was heated to 375°F to measure water volumes and to 1200°F to measure oil volumes. Gas volumes were measured on 25-gram chunks by mercury injection.

#### **TerraTek**

Fluid saturations of the full diameter samples and the sidewall cores were determined by means of the solvent distillation extraction (Dean-Stark) technique using toluene as the extracting solvent. Oil remaining in the full diameter samples following the initial extraction phase was removed by cleaning with toluene and  $CO_2$  in a pressurized core cleaner. Oil remaining in the sidewall cores was removed by cleaning with toluene in a reflux soxhlet. The clean core samples were dried in a convection oven at 110°C prior to performing porosity and permeability tests.

Porosity values were determined by measuring grain volumes and bulk volumes. Grain volumes were measured in helium expansion porosimeters using Boyle's law. Bulk volumes were measured by submerged weight in an appropriate liquid of known density using Archimedes' principle of buoyancy. Full diameter sample bulk volumes were measured in water and sidewall core sample bulk volumes were measured in mercury. Grain volume and dry weight values were utilized to determine grain density for each sample.

Horizontal and vertical permeability to nitrogen gas was measured in pressurized Hassler sleeve core holders. Nominal sleeve pressure of 400 psig was applied to prevent gas from leaking around the outside of the sample being tested. Steady-state downstream flow rate, monitored with a calibrated orifice-equipped pressure transducer, was kept as close as possible to 1 cm<sup>3</sup>/sec. A form of Darcy's equation was employed to calculate apparent gas permeability values.

Additional vertical permeability tests were performed on the following five full diameter samples: #9, #10, #11, #12, and #15. Following the completion of standard testing, these samples were cut in half (from 8 inches to 4 inches) and the vertical permeability tests were repeated. They were cut in half again (from 4 inches to 2 inches) and the vertical permeability tests were performed a third time.

#### 3 RESULTS

Results of the tests described above are presented in graphical and tabular form on the following pages. Test results are presented in three tables: Table 3-1 contains results of the retort analysis data, Table 3-2 contains results of full diameter Dean-Stark analysis, including results of the additional vertical permeability tests performed on five samples as described above, and Table 3-3 contains results of Dean-Stark analysis performed on the sidewall cores. The activities of potassium, uranium, and thorium are plotted separately, in addition to a plot of the total gamma ray activity, on the Compnonent Gamma Log, included following the data tables. A plot of the total gamma ray activity also appears on the enclosed Teklog, along with plots of grain density, horizontal and vertical permeability, porosity, and fluid saturations for the conventional cores. At the end of this report are four crossplots. The first plot shows 90-degree horizontal permeability versus porosity for the full diameter samples, the second plot shows permeability versus porosity for the sidewall cores, and the third and fourth plots are for the five samples which were tested repeatedly for vertical permeability. One shows original vertical permeability versus permeability after cutting the samples down to 4 inches in length and the other shows original vertical permeability versus permeability after cutting the samples down to two inches in length.

Table 3-1
Retort Analysis - Summation of Fluids Porosity
Test Results

Sample Number	Depth (feet)	Porosity %	Oil Saturation %	Water Saturation %
1	4643 - 44	6.7	61.4	28.4
2	4646 - 47	4.5	43.7	28.0
3	4655 - 56	16.5	53.7	4.9
4	4660 - 61	10.1	49.2	7.3
5	5440 - 41	8.4	36.9	29.8
6	5443 - 44	12.6	49.1	6.6
7	5444 - 45	11.2	53.9	10.8
8	5446 - 47	7.8	31.9	6.1
9	5447 - 48	12.6	48.9	9.5
10	5450 - 51	13.0	50.7	2.7
11	5454 - 55	12.9	46.5	6.5
12	5459 - 60	12.5	47.7	12.6

Table 3-2
Full Diameter Dean-Stark Analysis
Test Results

	Permeability			Oil	Water	Grain	Kh-max		
Sample Number	Depth (feet)	Kh-max	Kh-90°	Kv	Porosity %	Saturation %	Saturation %	Density (gm/cc)	Direction CW fr/North
1	4642 - 43	1.8	0.02	<0.01	5.2	37.8	42.5	2.65	164
2+	4643 - 44	87.	0.10	24.	5.3	42.5	64.3	2.67	168
3+	4644 - 45	172.	0.02	79.	6.7	28.1	56.0	2.67	167
4+	4645 - 46	99.	0.04	1186.	6.4	43.0	38.2	2.65	162
5	4648 - 49	0.47	0.07	<0.01	4.8	5.9	68.7	2.66	108
6	4650 - 51	1.6	1.1	0.10	3.7	39.6	31.9	2.66	61
7	4653 - 54	0.44	0.40	0.02	9.9	43.9	19.0	2.65	154
8	4654 - 55	3.4	2.8	0.72	12.7	48.8	9.7	2.64	97
9	4655 - 56	9.0	8.7	3.8	13.9	59.6	6.2	2.64	18
				6.8 <sup>1</sup>					
-				6.5 <sup>2</sup>					
10	4656 - 57	8.0	7.8	3.0	14.7	49.3	13.4	2.65	18
				1.9 <sup>1</sup>					
			-	1.3 <sup>2</sup>					
11	4657 - 58	19.	19.	19.	14.9	52.1	12.7	2.66	21
				19.1					
				19.²					
12	4658 - 59	12.	11.	7.4	14.0	59.6	6.9	2.66	7
		_		6.8 <sup>1</sup>					
				6.1 <sup>2</sup>		_			
13	4659 - 60	7.0	7.0	2.2	12.2	45.1	12.6	2.65	132
14+	5440 - 41	352.	0.52	.96	9.0	45.8	22.4	2.65	149
15	5441 - 42	1.4	1.4	2.4	11.0	49.4	14.9	2.63	*
				1.31					
				1.42					
16	5442 - 43	1.4	1.3	1.0	11.3	50.5	10.6	2.64	*

## **TerraTek**

			Permeability			Oil	Water	Grain	Kh-max
Sample Number	Depth (feet)	Kh-max	Kh-90°	Kv	Porosity %	Saturation %	Saturation %	Density (gm/cc)	Direction CW fr/North
17	5443 - 44	2.5	2.1	1.6	11.5	51.9	10.1	2.63	*
18	5444 - 45	0.68	0.59	0.49	10.2	49.1	15.5	2.64	*
19	5445 - 46	0.28	0.27	0.08	7.6	55.5	16.8	2.65	*
20	5446 - 47	0.64	0.56	0.08	8.9	49.8	21.0	2.64	*
21	5447 - 48	0.52	0.46	0.29	9.8	52.2	15.3	2.64	*
22	5448 - 49	0.18	0.16	<0.01	6.5	45.6	33.5	2.66	*
23	5451 - 52	0.53	0.53	0.46	10.4	50.6	13.3	2.65	*
24	5452 - 53	0.32	0.28	0.17	9.8	51.2	14.5	2.68	*
25	5453 - 54	0.42	0.17	<0.01	6.9	45.7	27.2	2.71	*
26	5454 - 55	0.53	0.51	0.19	10.2	49.0	16.5	2.67	*
27	5455 - 56	0.30	0.25	0.17	8.8	47.8	18.3	2.68	*
28	5456 - 57	0.16	0.12	<0.01	7.8	47.8	19.8	2.69	146
29	5457 - 58	0.20	0.20	0.11	8.4	46.8	20.1	2.66	180
30	5458 - 59	0.52	0.51	0.38	10.4	53.6	12.8	2.65	97
31	5459 - 60	0.42	0.39	0.33	10.0	52.1	14.0	2.67	195
32	5461 - 62	0.12	0.10	<0.01	4.9	44.1	30.6	2.67	75

<sup>+ -</sup> Open or partially open vertical fracture affecting permeability

<sup>\* -</sup> No orientation scribe marks present

<sup>&</sup>lt;sup>1</sup> - Vertical permeability value for 4-inch sample

<sup>&</sup>lt;sup>2</sup> - Vertical permeability value for 2-inch sample

Table 3-3
Plug Dean-Stark Analysis (Rotary Sidewall Cores)
Test Results

Sample Number	Depth (feet)	Permeability (md)	Porosity %	Oil Saturation %	Water Saturation %	Grain Density (gm/cc)
1	3059.0	21.	15.8	35.5	62.9	2.66
2	4109.0	16.	16.9	45.0	52.8	2.66
3	4114.0	8.9	15.1	46.5	50.6	2.66
4	4141.5	2.5	13.2	49.6	43.8	2.66
5	4142.0	0.43	10.8	42.2	27.6	2.67
6	4315.0	3.4	13.3	51.6	42.7	2.66
7	4350.0	0.03	6.6	26.9	41.9	2.67
8	4401.0	122.	24.6	30.0	63.1	2.77
9	4536.0	0.31	11.5	67.6	10.3	2.67
10	4646.0	0.02	6.1	57.4	26.5	2.68
11	4655.0	0.02	4.4	54.3	34.2	2.66
12	4659.0	569.+	15.3	36.0	57.3	2.66
13	4902.0	NA	9.6	65.0	13.9	2.69
14	5013.0	0.02	5.7	59.8	34.3	2.65
15	5041.0	0.03	6.9	61.4	26.4	2.67
16	5077.0	0.28	10.1	52.5	12.4	2.68
17	5171.0	0.25	9.5	56.1	15.7	2.67
18	5275.0	787.+	10.5	54.5	11.7	2.47
19	5446.0	0.77	6.9	46.1	31.1	2.64
20	5455.0	0.67	11.5	43.4	19.1	2.66
21	5462.0	0.17	8.3	54.0	19.6	2.68


<sup>+ -</sup> Fracture affecting permeability

NA - Not suitable for permeability testing

## **TerraTek**

## TERRA TEK GEOSCIENCE SERVICES

360 Wakara Way, SLC Utah 84108 (801) 584-2480




### TERRA TEK GEOSCIENCE SERVICES

360 Wakara Way, SLC Utah 84108 (801) 584-2480

BALCRON OIL COMPANY Monument Federal 33-8 Well

September 30, 1994 TerraTek File# 5646

## COMPONENT GAMMA LOG



Copyright @ Terra Tek Geoscience Services.

## Terra Tek Geoscience Services ®


University Research Park - 360 Wakara Way - Salt Lake City, Utah 84108 - (801) 584-2480 - FAX 801-584-2408

HORIZONTAL PERMEABILITY VSPOROSITY

#### BALCRON OIL COMPANY

Monument Federal 33-8 Well Monument Butte Field Duchesne County, Utah September 30, 1994

Depth Interval: 4642 to 5461 Feet TerraTek File# 5646 Porosity (phi), % Min Max Average 3.666 14.933 9.302 Permeability (K90), md Min Max Geo. Ave 0.020 0.504 18.644 Equation of the Line  $\log K90 = \alpha \, phi + \beta$ log K90 = 0.2160 ph! -2.3073Correlation Coefficient: 0.854 Green River Formation Conventional Cores



## Terra Tek Geoscience Services ®


University Research Park - 360 Wakara Way - Sait Lake City, Utah 84108 - (801) 584-2480 - FAX 801-584-2408

# HORIZONTAL PERMEABILITY VS POROSITY

#### BALCRON OIL COMPANY

Monument Federal 33—8 Well Monument Butte Field Duchesne County, Utah September 30, 1994

Depth Inte	erval: 3059 to	5462 Feet
Te	rraTek File# 5	646
1	Peresity (phi),	7
Min	Max	Average
4.386	24.593	11.282
Per	meability (Kh)	, md
Min	Max	Geo. Ave
0.016	787.493	1.100
Eg	uation of the	Line
log	Kh = a phi	+ B
log Kh	= 0.2403 phi	-2.6698
Correlat	tion Coefficien	t: 0.787
Gre	en River Form	ation
Rot	ary Sidewall C	ores



Copyright © Terra Tek Geoscience Services All Rights Reserved

# Terra Tek Geoscience Services®


University Research Park - 360 Wakara Way - Sait Lake City, Utah 84108 - (801) 584-2480 - FAX 801-584-2408

# VERTICAL PERMEABILITY VS VERTICAL PERMEABILITY

#### BALCRON OIL COMPANY

Monument Federal 33—8 Well Monument Butte Field Duchesne County, Utah September 30, 1994

TerraTek File# 5646 Permeability (Kv-8"), md Geo. Ave 2.400 19.000 5.212 Permeability (Kv-4"), md Max Geo. Ave 19.000 4.648 Equation of the Line  $\log Kv-4" = \alpha \log Kv-8" + \beta$  $\log Kv-4" = 1.1835 \log Kv-8" -0.1813$ Correlation Coefficient: 0.914 Vertical Permeability for 8" samples Vertical Permeability for 4" samples



## Terra Tek Geoscience Services ®


University Research Park - 360 Wakara Way - Sait Lake City, Utah 84108 - (801) 584-2480 - FAX 801-584-2408

# VERTICAL PERMEABILITY VS VERTICAL PERMEABILITY

#### BALCRON OIL COMPANY

Monument Federal 33—8 Well Monument Butte Field Duchesne County, Utah September 30, 1994

TerraTek File# 5646 Permeability (Kv-8"), md Geo. Ave 2.400 19.000 5.212 Permeability (Kv-2"), md Geo. Ave 1.300 19.000 4.240 Equation of the Line  $\log Kv-2" = \alpha \log Kv-8" + \beta$  $\log Kv-2" = 1.2293 \log Kv-8" -0.2540$ Correlation Coefficient: 0.903 Vertical Permeability for 8" samples Vertical Permeability for 2" samples



STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

APPL	.ICATION	FOR	INJECTION	WELL	-	UIC	FORM	1

**.... 2 1**096

OPERATOR	Equitable Resources Energy Balcron Oil Division	Company,
ADDRESS	1601 Lewis Avenue	
-	Billings, MT 59102	

Well name and number:Balcron Monument Federal #33-8				
Field or Unit name: <u>Beluga Unit</u> Lease no. <u>U-007978</u>				
Well location: QQ NW SE section 8 township 9S range 17E county Duchesne				
Is this application for expansion of an existing project? Yes [] No [3]				
Will the proposed well be used for: Enhanced Recovery? Yes [X] No [] Disposal? Yes [] No [X] Storage? Yes [] No [X]				
Is this application for a new well to be drilled? Yes [] No [x]				
If this application is for an existing well, has a casing test been performed on the well? Yes [] No [X] Date of test:  API number: 43-013-31427				
Proposed injection interval: from 4104' to 5463'  Proposed maximum injection: rate 500 BPD pressure 2100 psig  Proposed injection zone contains [3] oil, [] gas, and/or [] fresh water within % mile of the well.				
IMPORTANT: Additional information as required by R615-5-2 should accompany this form.				
List of Attachments: <u>Will be filed separately.</u>				
I certify that this report is true and complete to the best of my knowledge.  Name Bobbie Schuman Signature Strue Chuman  Title Regulatory & Environmental Specialist Date November 14, 1995  Phone No. (406) 259-7860				
(State use only) Application approved by TitleApproval Date				

Comments:

Underground Injection Control(UIC)

Permit Application

Supplement Attachment To Form Four

Equitable Resources Energy Company, Western Region Beluga Unit Waterflood Duchesne County, Utah

#### Table Of Contents

### List of Figures

Figure	#1	Topographic Map - Area of Review
Figure	#2	Water Injection Facilities Map
Figure	#3	Produced Water Gathering Facilities Map
Figure	#4	Surface And Lease Ownership
Figure	#5	Produced Water Analysis Report
Figure	#6	Johnson Water Supply Analysis Report
		Without Chemical
Figure	#7	Johnson Water Supply Analysis Report
		With Chemical
Figure	#8	Pressure Build Up Test
		-

### List of Exhibits

Exhibit-A	Area of Review Well List
Exhibit-B	Well Data Sheets and Scout Cards
Exhibit-C	Individual Sand Isopach Maps
Exhibit-D	Well Perforation Intervals
Exhibit-E	Fracture Pressure Data
Exhibit-F	Packer Fluid Recommendation
Exhibit-G	Core Analysis
Exhibit-H	Proposed Injection Well Surface Equipment
Exhibit-I	· Proposed Injection Well Completion Diagrams
Exhibit-J	Plugging and Abandonment Diagrams
Exhibit-K	Evidence of Finanical Ability
Exhibit-L	Existing EPA Permits Held by Equitable
	Resources Energy Company

# Underground Injection Control (UIC) Permit Application Supplement Attachment To Form Four

Company:

Equitable Resources Energy Company (EREC)

Project:

Beluga Unit Waterflood Monument Butte Field

Section 7,8,16,17,& 18, T9S, R17E

Duchesne County, Utah

#### A) AREA OF REVIEW METHODS.

 The area of review is a fixed radius of 1/4 mile from the proposed Unit boundary and/or proposed injection wells. This area of review was selected to ensure that any future development in this area would be covered.

#### B) MAPS OF WELLS/AREA & AREA OF REVIEW.

 Figure #1 - Topographic Map showing the area of review. A 1/4 mile radius from the proposed injection wells is outlined with all wells in the prescribed area located and identified.

Refer to Exhibit-A for a list of wells within the area of review.

- 2) Figure #2 Proposed Water Injection Facilities Map.
- 3) Figure #3 Proposed Produced Water Gathering Facilities Map.
- 4) Figure #4 Surface and lease ownership map. All surface within the area of review is owned by the Bureau of Land Management except for Section 16, T9S, R17E which is owned by the State of Utah.

#### C) CORRECTIVE ACTION PLAN AND WELL DATA.

1) A tabulation of well data is presented for each well within the area of review, refer to Exhibit-B, well data sheets & scout cards. Note that the proposed area of review for the Beluga Unit overlaps with the approved area of review for the Jonah Unit (Operated by Equitable Resources Energy Company) and Pleasant Valley Unit (Operated by Enserch Exploration Inc.). Please refer to the approved UIC permits for details on the wells in these areas.

Jonah Unit Pleasant Valley Unit Area Permit Number UT2642 Area Permit Number UT2771

2) It is proposed to inject water into multiple sands of the Green River Formation using injection packer assemblies which will be landed on tubing. The annulus of the proposed injection wells will be filled with a protective corrosion inhibitor and the backside pressure will be monitored daily. If abnormal backside pressure is detected the well will be pulled to determine the source of the leak.

#### D) MAPS AND CROSS SECTIONS OF USDW.

-Does not apply to Class Two injection wells.

#### E) NAME AND DEPTH OF USDW.

1) There are no underground sources of drinking water or water wells in

the area of review. No fresh water sources will be affected by these water injection operations. The top of the saline water bearing horizon in this area is 4800 feet to 5000 feet mean sea level which falls in the Uintah Formation. This information was provided by Gil Hunt with the Division of Oil, Gas, & Mining, State of Utah. The average MSL elevation for the area of review is 5350 feet which basically puts the top of the saline water horizon at surface to approximately 500 feet. There have been no fresh water bearing zones encountered in this area of review.

#### F) MAPS AND CROSS SECTIONS OF GEOLOGIC STRUCTURE OF AREA.

- Does not apply to Class Two injection wells.

#### G) GEOLOGICAL DATA ON INJECTION AND CONFINING ZONES.

- 1) The flooding objectives of the proposed Beluga Unit waterflood are lenticular channel sandstones which are distributed throughout the Douglas Creek Member of the Green River Formation. These sands occur over 1550 feet of vertical section at an average depth range of 3750 feet to 5300 feet. They exhibit a fining upward grain size, typical of fluvial channel deposits, with an average thickness of 15 feet. Due to the multiple potential waterflood horizons in the Douglas Creek Member, Equitable Resources Energy Company is requesting approval to inject water into any or all of the occurring sands within this interval. Refer to Exhibit-C for individual sand isopach maps.
- 2) For specific injection intervals please refer to the perforation intervals of each proposed injection well outlined in Exhibit-D and the welldata sheets and wellbore diagrams provided in Exhibit-B.
- 3) Estimated Formation Tops: See Type Log for the Paiute Federal #43-8

Uintah FormationSurface to 1450 ft.Green River Formation1450 ft to 5400 ft.Douglas Creek Member4560 ft to 5400 ft.Douglas/Wasatch Transition5400 ft to 5950 ft.Wasatch Formation5950 ft.

Note: The Douglas Creek interval is shown as a member within the Green River Formation.

- 4) The confining zones for the proposed injection intervals consists of mixed continental and lacustrine shales. The Douglas Creek Member is primarily interbedded sand stringers and shale which will act as isolation barriers for the waterflood. The top confining zone is the shales of the Green River Formation and the bottom confining zone is the shales of the Wasatch Formation. Refer to the Type Log for the Beluga Unit area which has been submitted with this permit.
- 5) The injection interval water quality is an analysis of the produced water from the Paiute Federal #11-17. This sample represents an average of the produced water from the Beluga Unit wells. The analysis shows 11,800 mg/l chloride, 9,471 mg/l sodium, and 25,085 mg/l TDS. Refer to Figure-5 for the produced water analysis report.
- 6) The average fracture gradient for the Douglas Creek Member sands is 0.876627 psig/ft. This is an average of all the frac gradients calculated from jobs performed on all zones in the Beluga Unit. Refer to Exhibit-E for pressure and gradient data.
- 7) Calculations for the submitted frac gradients are based on the initial shut in pressures obtained from the frac jobs performed on the Beluga Unit wells. Fracture treatment records show that the frac sand was

displaced with 2% KCl water. The hydrostatic gradient for the 2% KCl water was calculated at 0.43836 psig/ft. This gradient was used to calculate the hydrostatic head of the KCl water and was added to the ISIP. The fracture gradient was then calculated by dividing the sum of these pressures by the average of the perforation depth.

Frac Gradient = (ISIP + 0.43836 psig/ft(Depth))/Depth

- 8) Cement Bond Logs for the proposed water injection wells and a Beluga Unit Type Log have been enclosed. Cement bond logs for the newly drilled wells will be submitted to the EPA as soon as available.
- 9) The proposed water injection wells were drilled with a rotary rig using a conventional water based mud and/or an air mist to an average total depth of 5800 feet. Production casing was run through the productive sands of the Green River Formation and cemented to a point well above the upper most sand. The wells were then perforated, hydraulically fractured, and put on production. Refer to the welldata sheets presented in Exhibit-B for specific completion details of each well.

#### H) OPERATING DATA.

- Average water injection volume of 250 STBWPD. Maximum water injection volume of 500 STBWPD.
- 2) EREC is requesting a maximum injection pressure of 1856 psig based on fracture pressure gradient calculations until step rate test studies can be performed. The average fracture gradient for the Douglas Creek Member sands is calculated at 0.876627 psig/ft. This is an average of all the frac gradients calculated from jobs performed on all zones in the Beluga Unit. However, due to the difference in depth and fracture gradients between the Y-Zones and R-Zones EREC is requesting a maximum injection pressure of 1856 psig based on the fracture gradient and depth of the Y-Zones. The average fracture gradient for the Y-Zones only is calculated at 0.898974 psig/ft. Using the average depth of the shallowest Y-Zone perforations of 3982 feet, the formation parting pressure is calculated at 1856 psig for the Y-Zones. The average fracture gradient for the remaining zones (Excluding Y-Zones) is calculated at 0.866360 psig/ft. Using the average depth of the shallowest perforations for the remaining zones of 4553 feet, the formation parting pressure is calculated at 1973 psig. Thus, by using the lesser of the two calculated formation parting pressures of 1856 psig for a maximum injection pressure, it is reasonable to assume that the formation will not propagate a fracture during injection operations.
- 3) The annulus of the proposed injection wells will be filled with a protective corrosion inhibitor (Cortron R-2383) supplied by Champion Technologies, Inc. The recommended chemical will be mixed with fresh water at a concentration of two percent by volume. A diesel blanket of approximately one barrel will be placed on the backside to prevent the valves from freezing. Refer to Exhibit-F for the recommendation of packer fluid.
- 4) The injection water for the Beluga Unit waterflood will be fresh potable water supplied by Johnson Water Association out of Myton, Utah. This water will be piped from the Johnson water facility approximately 7.5 miles to the Johnson Unit through a six inch fiberglass water supply line which is owned and operated by EREC. It is proposed to extend this line approximately two miles to the Beluga Unit waterflood facilities. The source for this water supply is the Starvation Reservoir which is owned by the Bureau of Reclamation, Central Utah Project. The water is gathered from the Strawberry and Duchesne Rivers into the reservoir just west of the city of Duchesne, Utah and sold accordingly. The analysis for this

water shows 1200 mg/l chloride and 2548 mg/l TDS with a specific gravity of 1.005. Chemicals will be added to the water to reduce oxygen and to prevent corrosion and scaling. The proposed chemicals will be supplied by Champion Technologies out of Vernal, Utah. Refer to Figure-6 and Figure-7 for the analysis of the Johnson water supply.

5) As the waterflood progresses and water breakthrough occurs, it is proposed to inject the produced water back into the reservoir. When it is time to inject this produced water the EPA will be notified via letter and a water analysis will be submitted.

#### I) FORMATION TESTING PROGRAM.

- 1) The porosity of the injection sands averages approximately 12% with a permeability range from 0.1 to 16 millidarcy. The porosity is determined using compensated neutron/density porosity logs and core analysis. The core analysis is from the Allen Federal #34-5, Paiute Federal #24-8, and the Paiute Federal #34-8. The Allen Federal #34-5 well is located outside the Beluga Unit waterflood boundary and the other two are within the unit. These wells represent similar conditions for depositional environment, and reservoir characteristics for the Beluga Unit. Refer to Exhibit-G for the core analysis.
- 2) A mechanical integrity test will be conducted on all proposed water injection wells prior to injection. The casing will be integrity tested by setting a tubing conveyed packer just above the perforations and pressuring the annulus to 1000 psig. The pressure will be held for a one hour test. The results of the mechanical integrity tests will be submitted to the EPA prior to water injection.
- 3) Fracture treating rates, average and maximum pressure, ISIP, and frac gradients have been tabulated for the Beluga Unit and are presented in Exhibit-E and on the welldata sheets in Exhibit-B.
- 4) The present reservoir pressure through out the Beluga Unit ranges from a normal pressured reservoir at 2100 psig to depleted conditions at 900 psig. Refer to Figure-8 for a recent pressure build up test performed on the Monument Federal #42-17 in the R2 zone.
- 5) A step rate test will be performed on at least one proposed injection well to determine the formation parting pressure and to more accurately define the maximum allowable injection pressure. It is proposed to perform individual step rate tests on the Y-Zones and R-Zones to better understand the differences in formation parting pressures and to assure that the maximum requested injection pressure does not propagate fractures in any zone during the injection operations.

#### J) STIMULATION PROGRAM.

- Refer to individual well data sheets for well stimulation and fracture data.

#### K) INJECTION PROCEDURES.

- 1) The injection procedure for the Beluga Unit waterflood will be as follows:
  - Water from the Johnson Water Association and/or produced water will be piped to the proposed water injection plant located at the Paiute Federal #24-8 well location.
  - The water will be filtered with 50 and 10 micron filters before entering the water storage tanks at the water injection plant.
  - Chemical will be added for oxygen, corrosion, and scaling.
  - A triplex injection pump will be used to pressurize the water to approximately 2300 psig plant pressure.
  - The pressurized water will travel through an injection manifold and

out to the well feed lines.

- Each feed line will supply one injection well.
- Each injection well will be equipped with a flowmeter, choke valve check valve, water filter, tubing and casing annulus pressure gauge.
- The water will be filtered with 5 micron filters before entering the tubing.
- The water will pass down the tubing, past the packer to the perforations.
- Tracer profiles will be run approximately every 6 months which will indicate the percentage of water exiting each set of perforations.
- 2) The injection facility will be equipped with pressure monitoring and safety shut-down devices to protect against high or low pressure failures. It will also have tank level, oil, temperature, and other safety shut-down devices.

#### L) CONSTRUCTION PROCEDURES.

1) It is proposed to drill or re-enter the following wells:

Drill the Monument Federal #23-17B

Re-enter the Monument Butte Fed. #1-8

Re-enter the State NGC #11-16

NE SW Sec.17, T9S, R17E

NW SW Sec.8, T9S, R17E

NW NW Sec.16, T9S, R17E

- 2) The Monument Federal #23-17B will be drilled and completed similar to the Monument Federal #13-16B, #22-16B, #23-16B, and #33-17B wells. The well will be completed as an oil production well.
- 3) The Monument Butte Federal #1-8 and State NGC #11-16 will be re-entered using a workover rig and power swivel. The wells will be cleaned out to plugback TD and recompleted in additional zones. Refer to the wellbore diagrams presented in Exhibit-B and the proposed injection well diagrams presented in Exhibit-H.

#### M) CONSTRUCTION DETAILS.

- 1) Refer to Exhibit-I for the proposed well surface injection equipment.
- 2) Refer to Exhibit-B for welldata sheets, wellbore diagrams, and scout cards for all wells in the proposed area of review. Refer to Exhibit-H for proposed injection well diagrams. Refer to approved UIC area permits for the Jonah Unit (UT2642) and Pleasant Valley Unit (UT2771) for additional information on wells in the overlapping area of reviews.
- 3) A 25'x 30' water injection plant will be constructed on the location of the Paiute Federal #24-8 proposed water injection well. The water injection plant will be equipped with a produced water gathering and filtering system to reinject produced water as required. High pressure steel water injection lines will be laid and buried from the injection plant to each of the proposed water injection wells.
- 4) The injection wells will be equipped with 2 7/8 inch tubing and an Arrow Set-1 packer set in tension to isolate the injection zones. The packer will be set within 100 feet of the top perforation and will be tested for mechanical integrity. Refer to Exhibit-H for proposed packer setting depths of each water injection well.
- 5) Results of mechanical integrity tests and step rate tests will be submitted to the EPA along with well rework forms for each proposed water injection well prior to injection.

#### N) CHANGES IN INJECTION FLUID.

1) As the waterflood progresses and water breakthrough occurs, it is proposed to inject the produced water back into the formation. When

it is time to inject this produced water the EPA will be notified via letter and a water analysis will be submitted. At this time it is not feasible to make estimates as to the volume or quality of the produced water.

#### O) PLANS FOR WELL FAILURES.

1) All injection wells and related facilities will be monitored daily for integrity. The backside pressure will be checked daily and if abnormal backside pressure is detected the well will be investigated to determine the source of the leak. If a casing leak is found the leak will be isolated and squeezed with cement. The casing will be checked for mechanical integrity to ensure that the squeeze job repaired the leak. If a leak cannot be repaired the well will either be returned to production and pumped off or plugged and abandoned according to the procedure outlined in Section-Q.

#### P) MONITORING PROGRAM.

1) The waterflood will be monitored through the existing oil production wells. Each production well will be monitored for waterflood response and records of daily oil and water production will be kept. Fluid levels will be shot when possible to monitor reservoir pressure and flood advancement. Refer to Figure-1 for the location of these oil production wells.

#### Q) PLUGGING AND ABANDONMENT PLAN.

- 1) The P&A plan proposed consists of running into the well with tubing and washing the well out to TD to ensure that the perforations are clear. If the well is not dead, mud will be mixed on location to a sufficient weight for killing the well. The mud will be circulated down the tubing and into the casing until the water has been displaced and/or the well has been killed. The well will then have a balanced cement plug using approximately 260 sacks of class-G cement placed over the Douglas Creek Member of the Green River Formation (i.e. over the perforation interval) from TD to a point at least 300 feet above the uppermost perforation. The top of the first cement plug will be at a depth of approximately 3800 feet. The tubing will be pulled out of the hole and the production casing will be perforated for two feet with four shots per foot at a point 100 feet below the surface casing shoe. Circulation will be established to surface, down the casing & up the annulus via the perforations. Cement will be circulated to fill the production casing and the annulus from the perforations to the surface using 100 sx of class-G cement. The top of the second cement plug will be at the surface and the bottom will be 100 feet below the surface casing shoe. A permanent marker will be set identifying the well name, lease, location, elevation, and plugging date.
- 2) Refer to Exhibit-J for plugging and abandonment plan and diagrams.

#### R) NECESSARY RESOURCES.

1) Refer to Exhibit-K for evidence of financial ability to plug and abandon the proposed injection wells.

#### S) AQUIFER EXEMPTION.


-No aquifer exemption is requested.

#### T) EXISTING EPA PERMITS.

1) Refer to Exhibit-L for existing EPA permits held by Equitable Resources Energy Company, Western Region.

#### U) DESCRIPTION OF BUSINESS.

1) Equitable Resources Energy Company is an independent oil and gas production company located in Billings, Montana. EREC employs engineers, geologists, and a field staff with the knowledge and technical experience required to maintain and operate the proposed facilities.



Unit Boundaries Area Of Review **Equitable Resources Energy Company** 

Beluga Unit
Figure 1
Duchesne County, Utah
Well spot man/Area of review

#### BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH

#### ---ooOoo---

IN THE MATTER OF THE

NOTICE OF AGENCY

APPLICATION OF EQUITABLE

**ACTION** 

RESOURCES ENERGY COMPANY

FOR ADMINISTRATIVE APPROVAL OF

CAUSE NO. UIC-170

THE 44-7, 13-8, 24-8, 33-8, 1-8, 11-16. 22-16, 13-16, 11-17, POMCO #5,

22-17, 31-17, 42-17, AND 33-17

WELLS LOCATED IN SECTIONS 7, 8, 16 AND 17, TOWNSHIP 9 SOUTH,

RANGE 17 EAST, S.L.M., DUCHESNE

COUNTY, UTAH, AS CLASS II

INJECTION WELLS

---00000---

#### THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Equitable Resources Energy Company for administrative approval of the 44-7, 13-8, 24-8, 33-8, 1-8, 11-16, 22-16, 13-16, 11-17, Pomco #5, 22-17, 31-17, 42-17, and 33-17 wells, located in Section 7, 8, 16 and 17, Township 9 South, Range 17 East, SLM, Duchesne County, Utah, for conversion to Class II injection wells. The proceeding will be conducted in accordance with Utah Admin. R.649-10. Administrative Procedures.

The interval from 3190 feet to 5596 feet (Green River Formation) will be selectively perforated for water injection. The maximum requested injection pressure will be limited to 1856 PSIG with a maximum rate of 500 BWPD.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. If such a protest or notice of intervention is received, a hearing will be scheduled before the Board of Oil, Gas and Mining. Protestants and/or intervenors should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 2nd day of April 1996.

STATE OF UTAH

DIVISION OF OIL, GAS & MINING

Associate Director, Oil & Gas

# Equitable Resources Energy Company 44-7, 13-8, 24-8, 33-8, 1-8, 11-16, 22-16, 13-16, 11-17, Pomco #5, 22-17, 31-17, 42-17, and 33-17 Wells Cause No. UIC-170

Publication Notices were sent to the following:

Newspaper Agency Corporation Legal Advertising Tribune Building, Front Counter 143 South Main Salt Lake City, Utah 84111

Uintah Basin Standard 268 South 200 East Roosevelt, Utah 84066

Bureau of Land Management 170 South 500 East Vernal, Utah 84078

Equitable Resources Energy Company 1601 Lewis Avenue Billings, Montana 59102-4126

U.S. Environmental Protection Agency Region VIII Attn. Dan Jackson 999 18th Street Denver, Colorado 80202-2466

ine Platt

Larraine Platt Secretary

April 2, 1996



Michael O. Leavitt Governor **Executive Director** 

Ted Stewart James W. Carter Division Director

# DIVISION OF OIL, GAS AND MINING

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

April 2, 1996

**Newspaper Agency Corporation** Legal Advertising Tribune Building, Front Counter 143 South Main Salt Lake City, Utah 84111

Re:

Notice of Agency Action - Cause No. UIC-170

Gentlemen:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please send proof of publication and billing to the Division of Oil, Gas and Mining, 355 West North Temple, 3 Triad Center, Suite 350, Salt Lake City, Utah 84180-1203.

Sincerely,

Larraine Platt

Pariame Plate

Secretary

**Enclosure** 





# State of Utah DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt Governor Ted Stewart Executive Director James W. Carter Division Director 355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

April 2, 1996

Uintah Basin Standard 268 South 200 East Roosevelt, Utah 84066

Re: Notice of Agency Action - Cause No. UIC-170

Gentlemen:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please send proof of publication and billing to the Division of Oil, Gas and Mining, 355 West North Temple, 3 Triad Center, Suite 350, Salt Lake City, Utah 84180-1203.

Sincerely,

Larraine Platt Secretary

Larraine Platt

**Enclosure** 



#### 143 SOUTH MAIN ST. P.O. BOX 45838 SALT LAKE CITY, UTAH 84145 FED. TAX I.D. # 87-0217663

### wspaper Agency Corporation The Salt Lake Tribune (NA) DESERET NEWS

#### PROOF OF PUBLICATION

CUSTOMER'S COPY

CUSTOMER NAME AND ADDRESS	ACCOUNT NUMBER	
DIV OF OIL, GAS & MINING 355 WEST NORTH TEMPLE 3 TRIAD CENTER #350 SLC, UT 84180	D5385340L-07	04/11/96

	ACCOL	JNT NAME			
	DIV OF OIL,	GAS & MINING			
TELEPHON	IE	INVOICE NUMBER			
801-538-53	40	TL488200561			
	SCH	IEDULE			
STAI	START 04/11/96 END 04/11/96 CUST, REF. NO.				
		CC-170 PTION			
NOTICE OF AGENCY ACTION (CAUSE NO. UIC. 170  BEFORE THE DIVISION OF OIL, GAS AND MINING)  DEFARMMENT OF NATURAL RESOURCES, STATE OF UTAH	<u> </u>	GENCY ACTIONCAUSE N			
IN THE MATTER OF THE APPLICATION OF EQUITABLE RESOURCES ENERGY COMPANY FOR ADMINISTRATIVE APPROVAL OF THE 44-7.	47 LINES	2.00 COLUMN			
ENERGY COMPANY FOR ADMINISTRATIVE AFTROVALOF ITS 23-97, 13-8, 24-8, 33-81-8, 11-16, 22-16, 13-16, 11-17, POMCO #5, 22-17, 31-17, 42-17, AND 33-17 WELLS LOCATED IN SECTIONS 7, 8, 16 AND 17, TOWNSHIP 9 SOUTH, RANGE 17, EAST, S.L.M., DUCHESNE COUNTY, UTAH, \$5 CLASS 11 INJECTION WELLS.	3	RATE			
	Application of the state of the	1.64			
THE STATE OF UTAL TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.  Notice is hereby given that the Division of Oil, Gas and	FES	AD CHARGES			
Mining (the "Division") is commending an informal adjudicative proceeding to consider the application of Equitable Resources Energy Company to administrative approval of the 447, 43-8.		154.16			
24-8, 33-8, 4-8, 41-46, 22-46, 13-46, 11-47, POMCU #5, 24-17, 31-47, 42-17, and 33-17, wells located in Sections 7.8, 16 and 47, Township 9 South, Range 47 East, S.L.M., Duchesne County, Utah.		TOTAL COST			
Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commending an informal adjudicative proceeding to consider the application of Equitable Resources energy Company for administrative approval of the 44-7, 13-8, 24-8, 33-8, 14-3, 14-6, 22-16, 13-16, 14-17, POMCO #5, 22-17, 31, 14-16, 22-16, 13-16, 14-17, POMCO #5, 22-17, 31, 14-16, 22-16, 13-16, 14-17, POMCO #5, 22-17, 31, 14-16, 14-17, 15-18, 14-16, 14-17, 15-18, 14-16, 14-18,		154.16			


AFFIDAVIT OF PUBLICATION

The interval from 3190 beet to 5595 feet (Green River Formation) will be selectively perforated for water injection. The most mum requested injection pressure will be limited to 4856 PSIG with a maximum rate of 500 WPD. \*\*\*

Any person desting to object to the application or offser wise intervene in the proceeding, must file a written protest or notice of intervention with the Division within titleen days following publication of this notice. If such a protest or notice of intervention with the Division within titleen days following publication of this notice. If such a protest or notice of intervention is received, a hearing will be scheduled before the 80ard of Oil; Gas and Mining, Rotestants and/or infervenors should be prepared to demonstrate of the hearing how this matter affects their interests. CORPORATION LEGAL BOOKKEEPER, I CERTIFY THAT THE ATTACHED CE OF AGENCY ACTIONCAUSE N FOR IS & MINING ther affects their interests.

DATED this 2nd day of April, 19%. WAS PUBLISHED BY THE NEWSPAPER AGENCY OR THE SALT LAKE TRIBUNE AND DESERET NEWS, DAILY NEWSPAPERS STATE OF UTAH DIVISION OF OIL GAS AND MINING R. J. Firth Associate Director, Oil and Gas 48820050 SH LANGUAGE WITH GENERAL CIRCULATION IN UTAH, AND PUBLISHED ALT LAKE COUNTY IN THE STATE OF UTAH.

PUBLISHED	ON	START 04	/11/96	END	04/11/96
SIGNATURE		basse	Mon	ly	
DATE	04/11/06			0	



# DIVISION OF OIL, GAS AND MINING UNDERGROUND INJECTION CONTROL PROGRAM

# PERMIT DECISION DOCUMENT

Applicant:

Equitable Resources

Location:

Belugu Unit

Wells:

44-7.13-8.24-8.33-8.1-8.11-16.22-16.13-16.11-17.Pomco#5.22-17.31-17.42-

17 and 33-17

Ownership Issues: The proposed wells are located in sections 7, 8 and 16, township 9 south, range 17 east, Duchesne County, Utah. Surface ownership within the 1/2 mile area is held by the BLM and the State of Utah. All of the wells are located on Federal land. Mineral interests are held by private individuals, the State of Utah, and the federal government. Equitable has submitted an affidavit stating that a copy of UIC form 1 was sent as notice to all surface owners and operators within a 1/2 mile radius of each of the proposed injection wells.

Well Integrity: The 14 wells proposed for conversion to injection all have surface casing set at approximately 300 feet ± 30 feet, and were all cemented to surface. Production casing was set at a depth of approximately 5600 feet - 6000 feet, and were all cemented above the injection zone. The 1-8 and 11-16 wells are plugged and abandoned wells. The Pomco # 5 well is an old shut in producer, there are no cement bond logs on these three wells. Equitable has been notified that they must run bond logs on these wells and submit them to the Division prior to conversion. Cement bond logs are on file with the Division and verify reported cement tops on the other proposed injectors. The interval from 3190-5596 feet (Green River Formation) will be selectively perforated for water injection. A 2 7/8 inch tubing with a packer will be set above the perforations for injection of water. There are 25 producing wells 5 plugged and abandoned wells, 5 shut in producers and 3 newly drilled wells in the 1/2 mile area of review. All wells in the AOR have sufficient cement behind the production string and have adequate surface casing to prevent migration of fluid up the hole. All of the plugged wells have adequate plugs. At the time of conversion the casing will be pressure tested. Casing/tubing annulus pressure will be monitored on a daily basis and reported on a monthly basis thereafter. Additional casing pressure tests shall be run every five years or whenever the tubing and packer assemblies are pulled for workover purposes.

**Ground Water Protection:** The base of moderately saline water in the area of the project is at a depth of approximately 300-500 feet. Each of the injection wells and offset producing wells have adequate surface casing and sufficient cement on the production casing to protect fresh water. The submitted fracture pressure for the field averages .87 psi/ft resulting in a maximum allowed surface pressure of 1975 psi. A maximum pressure of 1856 psig was requested and injection pressures for each of the injectors will be

Equitable Resources Energy Company page 2

maintained at this pressure. The confining intervals above and below the injection zone consists of tight shales, siltstones and limestones of the Green River Formation. Water analysis indicate that the TDS of injection zone is greater than 10,000 TDS.

Oil/Gas & Other Mineral Resources Protection: Equitable Resources is the operator of the Belgu Unit. A unit agreement was previously formed, correlative rights issues were addressed before the Board of Oil, Gas and Mining when the matter was heard.

**Bonding:** Equitable is the operator of all wells within the project and is bonded by the Federal Government.

Actions Taken and Further Approvals Needed: These applications are for wells in an existing waterflood unit, previously supplied data and information along with newly submitted data supports a decision to approve the wells for conversion to injection. A public notice has been published in both the Salt Lake Tribune and the Uinta Basin Standard. The applications for the injection wells are technically complete. Cement bon d logs need to be run on the 1-8,11-16 and pomco #5 wells. A casing pressure test needs to be conducted when the well is converted and a casing\tubing pressure test run prior to injection. The casing tubing annulas needs to be pressured to 1000 psi and not 500 psi as stated in the permit. Following the 15 day comment period if no objections are received it is recommended to issue an approval to convert the wells and an injection permit. There are no special conditions or stipulations other than runnung the bond logs on the specified wells and the permit should be granted in accordance with the conditions set forth in the application.

	<u>05-21-96</u>
Reviewers	Date



**★FAX TRANSMITTAL★** 

FAX NO.: (406) 245-1365

TO:

NAME:

Leesha

COMPANY:

Utah, Division of Oil, Gas, & Mining 02-21-96

DATE:

FAX #:

FROM:

Molly Conrad

Equitable Resouces Energy Company, Balcron Oil Division

1601 Lewis Avenue Billings, MT 59102

Phone: (406) 259-7860 ext 236

TOTAL # OF PAGES 2 (including this cover sheet)

If you do not receive all pages, please call back as soon as possible at (406) 259-7860.

TELECOMMUNICATOR:

mmc

#### **SPECIAL INSTRUCTIONS:**

Here is a list of the Beluga Unit wells that you requested yesterday. Please let me know when you come up with an Entity Action number for them. The unit was effective 2-1-96, so I will have to change all of my records before reporting February production. Thanks for your help!!

NOTE: The information contained in this facsimile message is privileged and confidential, and is intended only for the use of the individual(s) or entity name above who have been specifically authorized to receive it. If the reader is not the intended recipient, you are hereby notified that any dissemination, distribution or copying of this communication is strictly prohibited. If you have received this communication in error, please notify us immediately by telephone and return

all pages to the address shown above. THANK YOU.

- STATE OF UTAH DIVISION OF OIL, GAS AND MINING ENTITY ACTION FORM - FORM 6

OPERATOR	EQUITABLE RESOURCES ENERGY	
unnerec	BALCRON OIL DIVISION	

OPERATOR ACCT. NO. N9890

ACTION	CURRENT	нен	ADT NUMBER			<del></del>						V = = = = = = = = = = = = = = = = = = =
CODE	ENTITY NO.		API HUMBER	WELL N		00	SC	YELL TP	LOCATIO RG	COUNTY	SPUD DATE	EFFECTIVE DATE
D		11880					98	17E		DUCHESNE		
YELL 1 C	ОММЕНТS:	*BELUGA ENTITY	UNIT EFF 2-1- 11880).	96 (SEE ATTACHED	LIST OF WELLS	BEING	CHAN	GED F	ROM CU	RRENT ENTITY	TO NEW U	NIT
												·
HELL 2 (	COMMENTS:		1			I	I			<u>I</u>	<u> </u>	•
WELL 4 (	COMPLETES:											
											[	T
WELL 5	COMMENTS:	1					1			1	<u> </u>	
A B C D E	- Establish - Add new w - Re-assign - Re-assign - Other (ex	new entity ell to exis well from well from plain in co	numents section)	ngle well only) p or unit well) ty to another existin ty to a new entity						L. CORDOVA Signature ADMIN. ANA		2-22- Date
110TE: 1 (3/89)	Jse COHHENT	section to	explain why each	Action Code was selec	sted.					Phone No. (	}	

FORM 10

STATE OF UTAH

DIVISION OF OIL, GAS AND MINING
355 West North Temple, 3 Triad, Suite 350, Salt Lake City, UT 84180-1203

Page_1	of	11	

OPERATOR NAME AND ADDRESS:				UTAH ACCOUNT NUMBER: N9890				
BALCRON OIL DIVISION EQUITABLE RESOURCES END 1601 LEWIS AVE BILLINGS MT 59102-4126		REPORT PERIOD (MONTH/YEAR): 12 / 95						
	·		AME	NDED REPORT (F	Highlight Changes)			
Vell Name	Producing	Well	Days	T .	Production Volumes			
API Number Entity Location	Zone	Status	Орег	OIL(BBL)	GAS(MCF)	WATER(BBL)		
BOLL WEEVIL FED 26-13			<del>                                     </del>					
4301330770 00035 08S 16E 26	GRRV							
CASTLE PK ST 43-16		<del> </del>	<del> </del>					
4301330594 01181 09S 16E 16	GRRV							
PAILITEMEEDERAL 84-84						<del></del>		
4301330778 01200 09S 17E 8	GRRV							
MOCONSEED型位置了					<u> </u>	· · · · · · · · · · · · · · · · · · ·		
4301330666 01205 09S 17E 7	GRRV							
PAILITEMED MARKETTA								
4301330516 01210 09S 17E 17	GRRV							
PAIUTES ED 24:81								
' 9 <u>1330675</u> 01220 09S 17E 8	GRRV		e.					
JRNEY FED 1-9 4304730070 01260 095 19E 9	GRRV							
CASTLE PK FED 24-10A	0001							
4301330555 01281 09S 16E 10 HENDEL FED 1-17	GRRV		-					
4304730059 01305 09S 19E 17	GRRV					•		
HENDEL FED 3-17								
4304730074 01305 09S 19E 17	GRRV							
HENDEL FED. 1-9						······································		
4304720011 01310 09S 19E 9	GRRV							
PARIETTE BENCH FED 14-5								
4304731123 01335 095 19E 5 PARIETTE BENCH UNIT 2	GRRV							
4304715680 01345 095 19E 7	GRRV		j					
	unik							
		7	TOTALS					
•								
MMENTS:								
				· · · · · · · · · · · · · · · · · · ·	<del></del>	· · · · · · · · · · · · · · · · · · ·		
creby certify that this report is true and complete to the	ne best of my	knowledge		Dat	e:			
				Dat	~			
ne and Signature:				T	alankana Nijenhae			
					elephone Number:			

FORM 10

STATE OF UTAH DIVISION OF OIL, GAS AND MINING
355 West North Temple, 3 Triad, Suite 350, Salt Lake City, UT 84180-1203

OPERATOR NAME AND ADDRESS:		UTAH ACCOUNT NUMBER: N9890						
BALCRON OIL DIVISION EQUITABLE RESOURCES ENE 1601 LEWIS AVE		REPORT PERIOD (MONTH/YEAR): 12 / 95						
BILLINGS MT 59102-4126			AMENDED REPORT (Highlight Changes)					
ell Name	Producing	Well	Days	γ	Production Volumes	the state of the s		
Pl Number Entity Location	Zone	Status	Oper	OIL(BBL)	·	TYL (TTD (DDL)		
PARIETTE BENCH FED 41-7		Status	Oper	OIL(BBL)	GAS(MCF)	WATER(BBL)		
4304731584 01346 09S 19E 7	GRRV							
SUE MORRISM 6-3								
4301330562 01450 09S 17E 16	GRRV		]					
STATE 16-2						<del></del>		
4301330552 01451 09S 17E 16	GRRV							
K JORGENSON ST 16-4								
4301330572 01452 09S 17E 16	GRRV							
OSSOUNCANTSTELLES	CDDV							
4301330570 01453 095 17E 16 RA1UTE::FEDERAL::43-8	GRRV							
01330777 02042 09S 17E 8	GRRV			-	1			
DERAUM#18	GILLY		<u> </u>					
4301330332 08100 09S 17E 18	DGCRK		,					
PONGO##2#	Dusitit				<del></del>  -			
4301330505 08101 09S 17E 18	GR-WS							
POMGO##49								
4301330506 08102 09S 17E 17	GRRV			- -	·	,		
PONGO \$#51						·		
4301330499 08104 095 17E 17	GRRV							
PARIETTE BENCH FED 32-6						<del> </del>		
4304731554 09885 095 19E 6	GRRV		<u> </u>					
PARIETTE BENCH FED 43-6								
4304731616 10280 095 19E 6	GRRV							
MAXUS*FEDERAL=23=8* 4301331196 10800 095 17E 8	CDDV							
4301331196 10800 09S 17E 8	GRRV	·						
			TOTALS		ì			
			- 0 - 1 - 2 - 2					
MMENTS:								
	<del></del>	··	<del></del>					
			<del></del>					
reby certify that this report is true and complete to the	he best of my	knowledge.		Da	te:			
e and Signature:					elephone Number:			

STATE OF UTAH DIVISION OF OIL, GAS AND MINING

355 West North Temple, 3 Triad, Suite 350, Salt Lake City, UT 84180-1203

reby certify that this report is true and complete to the	ne best of my	knowledge.		Da	te:				
MMENTS:					•				
			TOTALS						
4301331432 11616 095 17E 7	GRRV								
4301331427 11613 095 17E 8 MONUMENT EEDERAL 43-74	GRRV	·							
MONUMENTS EDERATED 3-8 / 4301331382 11574 095 17E 8 MONUMENTS FEDERAL 33-8 /	GRRV								
FEDERAL 21-25Y 4301331394 11530 095 16E 25	GRRV								
######################################	GRRV								
MONUMENT FEDERAL 23537 4301331387 11528 095 17E 17	GRRV								
FEDERAL 21-9Y 4301331396 11513 095 16E 9	GRRV								
4304732438 11506 09S 17E 14 FEDERAL 21-13Y 71331400 11510 09S 16E 13	GRRV GRRV								
4301331392 11505 095 16E 21 FEDERAL 44-14Y	GRRV								
4301331395 11501 098 17E 10 FEDERAL 41-21Y	GRRV								
4304732261 11500 08S 25E 5 FEDERAL 22-10Y	GRRV								
COYOTE FEDERAL 21-5 4304732260 11500 08S 25E 5 COYOTE FEDERAL 13-5	GRRV								
IPI Number Entity Location	Producing Zone	Well Status	Days Oper	OIL(BBL)	Production Volumes GAS(MCF)	WATER(BBL)			
BILLINGS MT 59102-412  Vell Name			<del></del>	ENDED REPORT (	Highlight Changes)				
BALCRON OIL DIVISION EQUITABLE RESOURCES ENERGY 1601 LEWIS AVE			REPORT PERIOD (MONTH/YEAR): 12 / 95						
			UIA	H ACCOUNT NUMBE	N9890 				

FORM 10

STATE OF UTAH

DIVISION OF OIL, GAS AND MINING 355 West North Temple, 3 Triad, Suite 350, Salt Lake City, UT 84180-1203

Page 9	of 11
	01

OFERATOR NAME AND ADDRESS:			UTAH ACCOUNT NUMBER: N9890					
BALCRON OIL DIVISION EQUITABLE RESOURCES ENERGY 1601 LEWIS AVE BILLINGS MT 59102-4126			REPORT PERIOD (MONTH/YEAR): 12 / 95  AMENDED REPORT (Highlight Changes)					
Well Name	Producing	Well	Days		Dandarati At 1			
API Number Entity Location	Zone	Status	1	Ott (ppr)	Production Volumes			
MONUMENT FEDERAL 11-25	Zone	Status	Орег	OIL(BBL)	GAS(MCF)	WATER(BBL)		
4304732455 11625 085 17E 25	GRRV							
4301331428 11635 09S 17E 17	GRRV							
MONUMENT SEPTERAL 22-17-1								
4301331429 11638 095 17E 17 CBAUCRON MONUMENT SEEDERAL 2251	GRRV							
4301331431 11640 09S 17E 17	GRRV							
ALLEN FEDERAL 31-6G 4301331442 11642 09S 17E 6	GRRV		-					
BALCRON FEDERAL 41-19Y 34732504 11651 095 18E 19	GRRV							
ь LCRON MONUMENT STATE 14-2 4301331425 11656 09S 17E 2	GRRV							
FEDERAL 44-4Y 4301331452 11679 095 17E 4	GRRV							
FEDERAL 31-5Y 4304732503 11680 09S 18E 5	GRRV							
BALCRON MONUMENT FEDERAL 21-25 4304732528 11683 08S 17E 25	GRRV							
MONUMENT FEDERAL 41-17 4301331466 11692 095 17E 17	GRRV							
MONUMENT FEDERAL 12-25								
4304732526 11694 085 17E 25	GRRV							
MONUMENIM EDERAL 2-17 4301331467 11698 095 17E 17	GRRV							
		7	TOTALS					
			L					
)MMENTS:								
A. Marian III.		121 Charles						
iereby certify that this report is true and complete to the	ne best of my	knowledge.		Dat	e:			
me and Signature:								
					elephone Number:			

e and Signature:

STATE OF UTAH

### DIVISION OF OIL, GAS AND MINING

355 West North Temple, 3 Triad, Suite 350, Salt Lake City, UT 84180-1203

Page 10 of 11

# MONTHLY OIL AND GAS PRODUCTION REPORT

OPERATOR NAME AND ADDRESS:		UTAH ACCOUNT NUMBER:N9890						
BALCRON OIL DIVISION EQUITABLE RESOURCES ENERGY 1601 LEWIS AVE BILLINGS MT 59102-4126			REPORT PERIOD (MONTH/YEAR): 12 / 95  AMENDED REPORT (Highlight Changes)					
Pl Number Entity Location	Zone	Status	Орег	OIL(BBL)	Production Volumes  GAS(MCF)			
MONUMENTEDERAL 32-174			1	OH)(BBC)	OM(MCF)	WATER(BBL)		
4301331465 11704 09S 17E 17	GRRV		,	1				
MONUMENT FEDERAL 32-25			<del></del>	<del> </del>				
4304732524 11707 08S 17E 25	GRRV							
MONUMENT FEDERAL 31-25		·	<del> </del>			<del></del>		
4304732530 11710 085 17E 25	GRRV	,						
BALCRON FEDERAL 12-22Y					<del> </del>			
4301331476 11717 085 17E 22	GRRV							
MONUMENT FEDERAL 33-25 4304732525 11729 08S 17E 25		_						
4304/32525 11729 08S 17E 25 MONUMENT FEDERAL 23-25	GRRV							
14732529 11730 085 17E 25	GRRV	•						
BALCRON MONUMENT STATE 24-2	GRRV	<del></del>						
4304732612 11736 095 17E 2	GRRV							
BALCRON MONUMENT STATE 13-2	unit v							
4301331482 11738 09S 17E 2	GRRV				ľ			
BALCRON MONUMENT STATE 22-2								
4304732610 11742 09S 17E 2	GRRV		]	,				
BALCRON MONUMENT STATE 12-2		· · · · · · · · · · · · · · · · · · ·						
4301331481 11745 09S 17E 2	GRRV							
BALCRON FEDERAL 31-19Y								
4304732614 11751 095 18E 19 BALCRON FEDERAL 42-19Y	GRRV							
4304732616 11756 095 18E 19	CDDV							
BALCRON FEDERAL 12-20Y	GRRV							
4304732617 11758 09S 18E 20	GRRV							
		•	TOTALS		l			
			į.		·			
				,				
AMENTS:								
		12.6 (6) 1						
•								
reby certify that this report is true and complete to th	e best of my	knowledge.		Da	ta·			
	•			Da	te:			

Telephone Number:\_



**★FAX TRANSMITTAL★** 

FAX NO.: (406) 245-1365

TO:

NAME:

Leesha

COMPANY: DATE: Utah, Division of Oil, Gas, & Mining

02-21-96

FAX #:

FROM:

Molly Conrad

Equitable Resouces Energy Company, Balcron Oil Division

1601 Lewis Avenue Billings, MT 59102

Phone: (406) 259-7860 ext 236

TOTAL # OF PAGES 2 (including this cover sheet)

If you do not receive all pages, please call back as soon as possible at (406) 259-7860.

TELECOMMUNICATOR:

mmc

#### SPECIAL INSTRUCTIONS:

Here is a list of the Beluga Unit wells that you requested yesterday. Please let me know when you come up with an Entity Action number for them. The unit was effective 2-1-96, so I will have to change all of my records before reporting February production.

Thanks for your help!!

NOTE: The information contained in this facsimile message is privileged and confidential, and is intended only for the use of the individual(s) or entity name above who have been specifically authorized to receive it. If the reader is not the intended recipient, you are hereby notified that any dissemination, distribution or copying of this communication is strictly prohibited. If you have received this communication in error, please notify us immediately by telephone and return

all pages to the address shown above. THANK YOU,

ENTITY ACTION FORM - FORM 6

OPERATOR	EQUITABLE RESOURCES ENERGY
ANNDESS	BALCRON OIL DIVISION

OPERATOR	ACCT	110	พ9890
UPERATOR	ALLI	1111	.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,

ACTION	CURRENT	NEW	API NUMBER	WELL NAME			<del></del>	WELL	LOCATION	1	SPUD	EFFECTIVE
CODE	ENTITY NO.	ENTITY NO.				QQ	SC	TP	RG	COUNTY	DATE	DATE
D		11880					9S	17E		DUCHESNE		
WELL 1 C	OMMENTS:	*BELUGA ENTITY	UNIT EFF 2-1-11880).	-96 (SEE ATTACHED LIST OF	WELLS	BEING	CHAN	GED FI	ROM CUI	RRENT ENTITY	TO NEW U	NIT
HELL 2 C	OHHEHTS:	····				!		<u> </u>	<u> </u>		<del></del>	<u> </u>
WELL 3 C	OMMENTS:							<u> </u>	<u> </u> !	<u> </u>		
		·										
IELL 4 CI	OMMENTS:				<u>'</u>	<u>-</u> !			<u> </u>	<del></del>		
HELL 5 CO	OHMENTS:				<u>'</u>		!					!
				·~					٠	1		
A B C D	- Establish - Add new we - Re-assign - Re-assign	new entity 11 to exist well from on well from on	on back of form) for new well (sind ing entity (group ne existing entity ne existing entity ne existing entity ments section)	ngle well only) o or unit well) by to another existing entity by to a new entity						L. CORDOVA Signature ADMIN. ANAI		2-22-9 Date
OTE: Us	e COMMENT s	ection to ex	xplain why each /	action Code was selected.						Phone No.	· }	
3/89)										- 1/4 - I		

<del></del>	<del>                                     </del>		<del> </del>	<del></del>		<del></del>	·						
- <del></del>		<del>-}</del> -	98	17E	Duchesne	UT	Oil (SI)	Green River	ML-3453	43-013-15582	680' FSL, 560' FWL	T	Beluga
Monument Butte	SW NW	17	95	17E	Duchesne	UT	Ofi	Green River	UTU-72106	43-013-31431	1980' FNL, 660' FWL	Vernal	Beiuga
Monument Butte	NW SW	8	9\$	17E	Duchesne	UT	Oil	Green River	UTU-74108	43-013-31382	2060 FSL, 694 FWL	Vernal	Bekupa
Monument Butte	SW SW	8	95	17E	Duchesne	υT	Oil	Green River	UTU-74108	43-013-31398	660' FSL, 660' FWL	Verne	Bekuta
Monument Butte	NE NW	17	98	17E	Duchesne	UT	O()	Green River	U-3563-A	43-013-31387	500' FNL, 1980' FWL		Bekige
Monument Butte	SE NW	17	98	17E	Duchesne	UT	Oil	Green River	UTU-72106	43-013-31429	1800' FNL 1980' FWI	<del></del>	Beinga
Monument Butte	NE NW	17	98	17E	Duchesne	uT	CON	Green River	UTU-72106	43-013-31428	<del></del>	<del>                                     </del>	Belura
Monument Butte	SW ME	17	9\$	17E	Duchesne	UT	Oi	Green River	UTU-72106	43-013-31465		<del></del>	Betura
Monument Butte	NW SE	8	98	17E	Duchesne	UT	ON.	Green River	UTU-74108	<del> </del>	<del></del>	<del> </del>	Beluga
Monument Builie	NENE	17	95	17E	Duchesne	υT	OH	Green River	UTU-72106	<del>                                     </del>		<del></del>	Belupa
Monument Butte	SE NE	17	95	17E	Duchesne	UT	Oi	Green River	UTU-72106	<del>}</del>	<del></del>	<del></del>	Beluga
Monument Butte	NE SE	7	98	17E	Duchesne	UT	Oil	Green River	UTU-72106	<del></del>	·	<del> </del> -	Beluga
Monument Butte	SW NW	16	98	17E	Duchesne	UT	Oi	Green River	<del></del>	1		ACUITE	Beluxa
Monument Butte	NE SE	17	98	17E	Duchesne	UT	OI (SI)	Green River		<del></del>	<del></del>	Vormei	Beluga
Monument Butte	NW NE	18	98	17E	Duchesne	<del> </del>		Green River	U-3563	<del></del>			Beluga
Monument Butte	NE SW	В	98	17E	Duchesne	υT	Oil	Green River	UTU-74108	<del></del>	<del></del>	<del> </del>	Beluga
Monument Butte	SE SE	7	98	17E	Duchesne	υT	Oi	Green River	U-3563-A		<del></del>		Beluca
Monument Bulle	NE SW	17	98	17£	Duchesne	UT	PND	Green River	UTU-74108				Beluge
Monument Butte	NW SE	17	98	17E	Duchesne	UT	PND	Green River	U-72106	<del></del>	<del> </del>	<del></del>	Beluga
Monument Buttle	NW SW	16	9\$	17E	Duchesne	UT	PND	Green River	State ML-3453-R	43-013-31580	<del></del>	Action	Beluga
Monument Bulte	SE NW	16	9\$	17E	Durzhesne	UT	PND	Green River	· · · · · · · · · · · · · · · · · · ·		<del> </del>		Beluga
Monument Butte	NE SW	16	98	17E	Duchesne	υT	PND	Green River	<del> </del>	L	<del></del>		Beluca
Monument Butte	NVV NVV	17	98	17E	Duchesne	UT	Oil	Green River	<del> </del>	<del></del>	<del> </del>	Variation	Beluga
Monument Butte	SE SW	8	95	17E	Duchesne	UT	Oil	Green River	<del></del>		<del> </del>		Beluga
Monument Butte	SW SE	8	98	17E	Duchesne	UT	Oil	Green River	UTU-74108		<del> </del>	<u> </u>	Beluga
Monument Butte	NE SE	8	95	17E	Duchesne	υT	Oil	Green River			<del> </del>		Beluga
Monument Butte	NW SE	18	9\$	17E	Duchesne	UΤ	ОТА	Green River	<del> </del>		<del> </del>		Beluga Beluga
Monument Butte	SW SW	17	98	17E				·					Beluga Beluga
Monument Butte	NW SW	17	95	17E	Duchesne			<del></del>	<del> </del>				<u>-</u> -
Mora assent Redte	NE NW	16	98									क्ट्राह्य	Beluga Beluga
	Monument Butte	Monument Butte NE NW Monument Butte NE NW Monument Butte NW NE NW Monument Butte NW SE Monument Butte NE NE Monument Butte NE SE Monument Butte NE SW Monument Butte NE SE Monument Butte NE SW	Monument Butte SW NW 8 Monument Butte SW SW 8 Monument Butte NE NW 17 Monument Butte NE NE 17 Monument Butte NE SE 7 Monument Butte NE SE 7 Monument Butte NW NE 18 Monument Butte NW NE 18 Monument Butte NE SE 17 Monument Butte NE SE 17 Monument Butte NW NE 18 Monument Butte NE SW 16 Monument Butte NE SW 17 Monument Butte NW SE 16 Monument Butte NE SW 16 Monument Butte SW SE 8 Monument Butte SW SE 8 Monument Butte SW SE 8 Monument Butte NW SE 18 Monument Butte SW SE 8 Monument Butte SW SE 18 Monument Butte SW SW 17	Monument Butte SW NW 8 9S  Monument Butte NW SW 8 9S  Monument Butte SW SW 8 9S  Monument Butte NE NW 17 9S  Monument Butte SW NE 17 9S  Monument Butte NE NE 17 9S  Monument Butte NE NE 17 9S  Monument Butte NE NE 17 9S  Monument Butte SE NE 17 9S  Monument Butte NE SE 7 9S  Monument Butte NE SE 7 9S  Monument Butte NE SE 17 9S  Monument Butte NE SW 16 9S  Monument Butte NE SW 17 9S  Monument Butte NE SW 16 9S  Monument Butte SE SW 8 9S  Monument Butte SE SW 8 9S  Monument Butte NE SE 88 9S	Monument Butte         SW NW         17         9S         17E           Monument Butte         NW SW         8         9S         17E           Monument Butte         SW SW         8         9S         17E           Monument Butte         NE NW         17         9S         17E           Monument Butte         SE NW         17         9S         17E           Monument Butte         NE NW         17         9S         17E           Monument Butte         NW SE         8         9S         17E           Monument Butte         NE NE         17         9S         17E           Monument Butte         NE NE         17         9S         17E           Monument Butte         NE NE         17         9S         17E           Monument Butte         NE SE         7         9S         17E           Monument Butte         NW NW         16         9S         17E           Monument Butte         NW NE         18         9S         17E           Monument Butte         NW SE         17         9S         17E           Monument Butte         NW SE         17         9S         17E           Mo	Monument Butte SW NW 8 9S 17E Duchesne Monument Butte NW SW 8 9S 17E Duchesne Monument Butte NE NW 17 9S 17E Duchesne Monument Butte SE NW 17 9S 17E Duchesne Monument Butte SE NW 17 9S 17E Duchesne Monument Butte NE NW 17 9S 17E Duchesne Monument Butte SW NE 17 9S 17E Duchesne Monument Butte SW NE 17 9S 17E Duchesne Monument Butte NW SE 8 9S 17E Duchesne Monument Butte NW SE 8 9S 17E Duchesne Monument Butte NE NE 17 9S 17E Duchesne Monument Butte NE SE NE 17 9S 17E Duchesne Monument Butte NW SE 7 9S 17E Duchesne Monument Butte NW NE 16 9S 17E Duchesne Monument Butte NW NE 18 9S 17E Duchesne Monument Butte NW NE 18 9S 17E Duchesne Monument Butte NW NE 18 9S 17E Duchesne Monument Butte NE NE SE 7 9S 17E Duchesne Monument Butte NE NE NE 17 9S 17E Duchesne Monument Butte NE NE NE 17 9S 17E Duchesne Monument Butte NE SW 8 9S 17E Duchesne Monument Butte NE SW 17 9S 17E Duchesne Monument Butte NE SW 17 9S 17E Duchesne Monument Butte NE SW 16 9S 17E Duchesne Monument Butte NE SW 16 9S 17E Duchesne Monument Butte NW SW 17 9S 17E Duchesne Monument Butte SE SW 8 9S 17E Duchesne Monument Butte NW SE 8 9S 17E Duchesne Monument Butte NW SW 17 9S 17E Duchesne Monument Butte NW SW 17 9S 17E Duchesne	Monument Buttle SW NW 8 9S 17E Duchesne UT Monument Buttle SW SW 8 9S 17E Duchesne UT Monument Buttle SW SW 8 9S 17E Duchesne UT Monument Buttle SW SW 17 9S 17E Duchesne UT Monument Buttle SE NW 17 9S 17E Duchesne UT Monument Buttle SE NW 17 9S 17E Duchesne UT Monument Buttle SW NE 17 9S 17E Duchesne UT Monument Buttle SW NE 17 9S 17E Duchesne UT Monument Buttle SW NE 17 9S 17E Duchesne UT Monument Buttle SE NE 17 9S 17E Duchesne UT Monument Buttle SE NE 17 9S 17E Duchesne UT Monument Buttle SE NE 17 9S 17E Duchesne UT Monument Buttle SW NW 16 9S 17E Duchesne UT Monument Buttle SW NW 16 9S 17E Duchesne UT Monument Buttle SW NW 16 9S 17E Duchesne UT Monument Buttle NW NE 18 9S 17E Duchesne UT Monument Buttle NW NE 18 9S 17E Duchesne UT Monument Buttle NW NE 18 9S 17E Duchesne UT Monument Buttle NW NE 18 9S 17E Duchesne UT Monument Buttle NE SW 8 9S 17E Duchesne UT Monument Buttle NE SW 17 9S 17E Duchesne UT Monument Buttle NE SW 17 9S 17E Duchesne UT Monument Buttle NE SW 17 9S 17E Duchesne UT Monument Buttle NE SW 17 9S 17E Duchesne UT Monument Buttle NE SW 16 9S 17E Duchesne UT Monument Buttle NE SW 16 9S 17E Duchesne UT Monument Buttle NE SW 16 9S 17E Duchesne UT Monument Buttle NE SW 16 9S 17E Duchesne UT Monument Buttle NE SW 16 9S 17E Duchesne UT Monument Buttle NE SW 16 9S 17E Duchesne UT Monument Buttle NE SW 8 9S 17E Duchesne UT Monument Buttle NE SW 8 9S 17E Duchesne UT Monument Buttle NE SW 8 9S 17E Duchesne UT Monument Buttle NE SW 8 9S 17E Duchesne UT Monument Buttle NE SE 8 9S 17E Duchesne UT Monument Buttle NE SE 8 9S 17E Duchesne UT Monument Buttle NE SE 8 9S 17E Duchesne UT Monument Buttle NW SE 8 9S 17E Duchesne UT Monument Buttle NW SE 8 9S 17E Duchesne UT Monument Buttle NW SE 8 9S 17E Duchesne UT Monument Buttle NW SE 18 9S 17E Duchesne UT Monument Buttle NW SW 17 9S 17E Duchesne UT Monument Buttle NW SW 17 9S 17E Duchesne UT Monument Buttle NW SW 17 9S 17E Duchesne UT Monument Buttle NW SW 17 9S 17E Duchesne UT Monument Buttle NW SW 17 9S 17E Duchesne UT Monument Buttle NW SW 17 9S 17E Duch	Monument Butte SW NW 17 9S 17E Duchesne UT Oli Monument Butte SW SW 8 9S 17E Duchesne UT Oli Monument Butte SW SW 8 9S 17E Duchesne UT Oli Monument Butte SW SW 8 9S 17E Duchesne UT Oli Monument Butte SE NW 17 9S 17E Duchesne UT Oli Monument Butte SE NW 17 9S 17E Duchesne UT Oli Monument Butte SE NW 17 9S 17E Duchesne UT Oli Monument Butte SV NE 17 9S 17E Duchesne UT Oli Monument Butte NE NE 17 9S 17E Duchesne UT Oli Monument Butte SE NE 17 9S 17E Duchesne UT Oli Monument Butte NE SE 7 9S 17E Duchesne UT Oli Monument Butte NE SE 7 9S 17E Duchesne UT Oli Monument Butte NE SE 17 9S 17E Duchesne UT Oli Monument Butte NE SE 17 9S 17E Duchesne UT Oli Monument Butte NE SE 17 9S 17E Duchesne UT Oli Oli Monument Butte NE SE 17 9S 17E Duchesne UT Oli Oli Monument Butte NE SE 17 9S 17E Duchesne UT Oli Oli Monument Butte NE SE 17 9S 17E Duchesne UT Oli Oli Monument Butte NE SW 8 9S 17E Duchesne UT Oli Oli Monument Butte NE SW 8 9S 17E Duchesne UT Oli Monument Butte NE SW 17 9S 17E Duchesne UT Oli Monument Butte NE SW 17 9S 17E Duchesne UT Oli Monument Butte NE SW 16 9S 17E Duchesne UT PND Monument Butte NE SW 16 9S 17E Duchesne UT PND Monument Butte NE SW 16 9S 17E Duchesne UT PND Monument Butte NE SW 8 9S 17E Duchesne UT PND Monument Butte NE SW 8 9S 17E Duchesne UT PND Monument Butte NE SW 8 9S 17E Duchesne UT PND Monument Butte NE SW 8 9S 17E Duchesne UT PND Monument Butte NE SW 8 9S 17E Duchesne UT PND Monument Butte NE SW 8 9S 17E Duchesne UT Oli Monument Butte NE SW 8 9S 17E Duchesne UT Oli Monument Butte NE SW 8 9S 17E Duchesne UT Oli Monument Butte NE SW 8 9S 17E Duchesne UT Oli Monument Butte NE SW 9S 17E Duchesne UT Oli Monument Butte NE SW 9S 17E Duchesne UT Oli Monument Butte NE SW 9S 17E Duchesne UT Oli Monument Butte NE SW 9S 17E Duchesne UT Oli Monument Butte NE SW 9S 17E Duchesne UT Oli Monument Butte NW SW 17 9S 17E Duchesne UT Oli Oli Monument Butte NW SW 17 9S 17E Duchesne UT Oli Oli Monument Butte NW SW 17 9S 17E Duchesne UT Oli Oli Monument Butte NW SW 17 9S 17E Duchesne UT Oli Oli Monument Butte NW SW	Monument Butte SW NW 17 95 17E Duchesne UT Oil Green River Monument Butte SW SW 8 95 17E Duchesne UT Oil Green River Monument Butte SW SW 8 95 17E Duchesne UT Oil Green River Monument Butte NE NW 17 95 17E Duchesne UT Oil Green River Monument Butte NE NW 17 95 17E Duchesne UT Oil Green River Monument Butte NE NW 17 95 17E Duchesne UT Oil Green River Monument Butte NW SE 8 95 17E Duchesne UT Oil Green River Monument Butte NW SE 8 95 17E Duchesne UT Oil Green River Monument Butte NW SE 8 95 17E Duchesne UT Oil Green River Monument Butte NE NE NE 17 95 17E Duchesne UT Oil Green River Monument Butte NE NE NE 17 95 17E Duchesne UT Oil Green River Monument Butte NE NE 17 95 17E Duchesne UT Oil Green River Monument Butte NE SE NE 17 95 17E Duchesne UT Oil Green River Monument Butte NE SE 7 95 17E Duchesne UT Oil Green River Monument Butte NE SE 7 95 17E Duchesne UT Oil Green River Monument Butte NE SE 7 95 17E Duchesne UT Oil Green River Monument Butte NE SE 7 95 17E Duchesne UT Oil Green River Monument Butte NE NE SE 7 95 17E Duchesne UT Oil Green River Monument Butte NE NE NE 95 17E Duchesne UT Oil Green River Monument Butte NE NE NE 95 17E Duchesne UT Oil Green River Monument Butte NE SW 17 95 17E Duchesne UT Oil Green River Monument Butte NE SW 17 95 17E Duchesne UT Oil Green River Monument Butte Ne SW 17 95 17E Duchesne UT Oil Green River Monument Butte Ne SW 17 95 17E Duchesne UT Oil Green River Monument Butte Ne SW 16 95 17E Duchesne UT PND Green River Monument Butte Ne SW 16 95 17E Duchesne UT PND Green River Monument Butte Ne SW 16 95 17E Duchesne UT PND Green River Monument Butte Ne SW 16 95 17E Duchesne UT Oil Green River Monument Butte Ne SW 16 95 17E Duchesne UT Oil Green River Monument Butte Ne SW 16 95 17E Duchesne UT Oil Green River Monument Butte Ne SW 16 95 17E Duchesne UT Oil Green River Monument Butte Ne SW 16 95 17E Duchesne UT Oil Green River Monument Butte Ne SW 16 95 17E Duchesne UT Oil Green River Monument Butte Ne SW 16 95 17E Duchesne UT Oil Green River Monument Butte Ne SW 16 95 17E Duchesn	Monument Buttle   SW NW   17   9S   17E   Duchesne   UT   Oil   Green River   UTU-74108	Monument Buttle   SW NNV	Monument Buttle   SW NW   17   95   17E   Duchesne   UT   Oil   Green River   UTU-74108   43-013-31382   200 FSL, 500 FWL	Monumer Butte   SW NW

N4940-Enserch Explor. Inc. (Open.chg. in Progress)

N8395-Prod. Lecovery Corp. (Open. Chg. in Progress)

# STATE OF UTAH DIVISION OF OIL, GAS AND MINING 355 West North Temple, 3 Triad, Suite 350, Salt Lake City, UT 84180-1203

Page 11 of 11

## MONTHLY OIL AND GAS PRODUCTION REPORT

OPERATOR NAME AND ADDRESS:			UTAI	H ACCOUNT NUMBE	n9890			
BALCRON OIL DIVISION EQUITABLE RESOURCES ENE 1601 LEWIS AVE BILLINGS MT 59102-4126			REPORT PERIOD (MONTH/YEAR): 3 / 96					
			Alvie.	NDED REPORT (1	Highlight Changes)	,		
Well Name	Producing	Well	Days	<u> </u>	Production Volumes			
API Number Entity Location	Zone	Status	Oper	OIL(BBL)	GAS(MCF)	WATER(BBL)		
MAXUS FEDERAL 23-8								
4301331196 11880 09S 17E 8  MONUMENT FEDERAL 13-8	GRRV							
4301331382 11880 09S 17E 8	GRRV							
4301331387 11880 09S 17E 17	GRRV							
FEDERAL 14-8 4301331398 11880 095 17E 8	GRRV				·			
MONUMENT FEDERAL 33-8 4301331427 11880 098 17E 8	GRRV							
MONUMENT FEDERAL 31-17								
01331428 11880 09S 17E 17	GRRV	<u>-</u> -				<del></del>		
4301331429 11880 095 17E 17 BALCRON MONUMENT FEDERAL 12-17	GRRV							
4301331431 11880 09S 17E 17	GRRV							
MONUMENT FEDERAL 43-7 4301331432 11880 095 17E 7	GRRV							
MONUMENT FEDERAL 32-17 4301331465 11880 095 17E 17								
MONUMENT FEDERAL 41-17	GRRV							
4301331466 11880 095 17E 17	GRRV							
BALCRON MONUMENT FEDERAL 42-17 4301331467 11880 098 17E 17	GRRV							
			TOTALS					
			•		1			
OMMENTS:		·						
hereby certify that this report is true and complete to	the best of my	knowledge	•	Da	ate:			
lame and Signature:					Telephone Number:			
(12/93)								

Balcron Monument Fed. #32-1J	Monument Butte	SW NE	1	98	16E	Duchesne	UT	Oil	Green River	U-33992	43-013-31414	2143' FNL. 1987' FEL	Vernal	Jonah
Balcron Monument Fed. #32-25	Undesignated	SW NE	25	88	17E	Uintah	UT		Green River	U-67845	43-047-32524	1980' FNL, 1980' FEL	Vernal	Jonan
Balcron Monument Fed. #33-11J	Monument Butte	NW SE	11	98	16E	Duchesne	UT		Green River	U-096550	43-013-31451	1971' FSL, 2032' FEL	+	1
Balcron Monument Fed. #33-25	Undesignated	NW SE	25	88	17E	Uintah	UT		Green River	U-67845	43-047-32525		Vernal	Jonah
Balcron Monument Fed. #33-6	Monument Butte	NW SE	6	98	17E	Duchesne	UT		Green River	U-020252-A	43-047-32525	2097' FSL, 2067' FEL	Vernal	
Balcron Monument Fed. #33-8	Monument Butte	NW SE	8	98	17E	Duchesne	UT		Green River	UTU-74108	43-013-31361	1832' FSL, 1829' FEL	Vernal	Jonah
Balcron Monument Fed. #34-10J	Monument Butte	SW SE	10	98	16E	Duchesne	UT	WIW	Green River	U-017985	43-013-31427	1980' FSL, 1980' FEL	Vernal	Beluga
Balcron Monument Fed. #34-25	Undesignated	SW SE	25	88	17E	Uintah	UT	PND	Green River	U-67845	43-013-31416	592' FSL, 1979' FEL	Vernal	Jonah
Balcron Monument Fed. #34-7	Monument Butte	SW SE	7	98	17E	Duchesne	UT	PND	Green River	UTU-72106	43-013-31426	800' FSL, 2100' FEL	Vernal	
Balcron Monument Fed. #41-12J	Monument Butte	NE NE	12	98	16E	Duchesne	UT	Oil	Green River	U-44426	43-013-31426	810' FSL, 1736' FEL	Vernal	ļ
Balcron Monument Fed. #41-14J	Monument Butte	NE NE	14	98	16E	Duchesne	UT	wiw	Green River		40.040.04400	395' FNL, 476' FEL	Vernal	Jonah
Balcron Monument Fed. #41-15	Monument Butte	NE NE	15	98	16E	Duchesne	UT	WIW	Green River	U-096550 U-017985	43-013-31408	363' FNL, 600' FEL	Vernal	Jonah
Balcron Monument Fed. #41-17	Monument Butte	NE NE	17	98	17E	Duchesne	UT	Oil	Green River		43-013-31367	460' FNL, 500' FEL	Vernal	Jonah
Balcron Monument Fed. #41-26	Monument Butte	NE NE	26	88	17E	Uintah	UT	PND	Green River	UTU-72106 U-67845	43-013-31466	660' FNL, 660' FEL	Vernal	Beluga
Balcron Monument Fed. #42-11J	Monument Butte	SE NE	11	98	16E	Duchesne	UT	Oil	Green River	<del> </del>	43-047-32456	660' FNL, 500' FEL	Vernal	
Baicron Monument Fed. #42-12J	Monument Butte	SE NE	12	98	16E	Duchesne	UT	Oil	Green River	U-096550	43-013-30066	1992' FNL, 496' FEL	Vernal	Jonah
Balcron Monument Fed. #42-14J	Monument Butte	SE NE	14	98	16E	Duchesne	UT	PND	Green River	U-035521	43-013-31486	2550' FNL, 391' FEL	Vernal	Jonah
Balcron Monument Fed. #42-17	Monument Butte	SE NE	17	98	17E	Duchesne	ut	Oil		U-096550	43-013-21491	1882' FNL, 773' FEL	Vernal	Jonah
Balcron Monument Fed. #42-18	Monument Butte	SE NE	18	98	17E	Duchesne	UT	PND	Green River Green River	UTU-72106	43-013-31467	1800' FNL, 700' FEL		Beluga
Balcron Monument Fed. #42-1J	Monument Butte	SE NE	1	98	16E	Duchesne	UT	WIW	Green River	UTU-72106	43-013-31433	1800' FNL, 800' FEL	Vernal	
Balcron Monument Fed. #42-26	Undesignated	SE NE	26	88	17E	Uintah	UT	PND	Green River	U-40652	43-013-31404	2087' FNL, 692' FEL	+	Jonah
Balcron Monument Fed. #42-6	Monument Butte	SE NE	6	98	17E	Duchesne	UT	WIW	Green River	U-67845		2100' FNL, 660' FEL	Vernal	
Balcron Monument Fed. #43-11J	Monument Butte	NE SE	11	98	16E	Duchesne	UT	WIW		U-020252-A	43-013-31364	1806' FNL, 921' FEL	Vernal	Jonah
Balcron Monument Fed. #43-26	Undesignated	NE SE	26	88	17E	Uintah	UT	PND	Green River	U-096550	43-013-31002	2127' FSL, 693' FEL	<del></del>	Jonah
Balcron Monument Fed. #43-7	Monument Butte	NE SE	7	98	17E	Duchesne	UT	Oil	Green River	U-67845	<u> </u>	1880' FSL, 379' FEL	Vernal	
Balcron Monument Fed. #44-1J	Monument Butte	SE SE	1	98	16E	Duchesne	UT	WIW	Green River	UTU-72106	43-013-31432	1850' FSL, 850' FEL		Beluga
Balcron Monument State #12-2	Undesignated	SW NW	2	98	17E	Duchesne	UT	+	Green River	U-44426	<del></del>	338' FSL, 859' FEL	Vernal	Jonah
Balcron Monument State #13-2	Undesignated	NW SW	2	98	17E	Duchesne	UT	Oil	Green River	ML-45555	<del> </del>	1980' FNL, 660' FWL		
Balcron Monument State #14-2	Undesignated	SW SW	2	98	17E			Oii	Green River	ML-45555	<del> </del>	2210' FSL, 604' FWL		
Balcron Monument State #21-2-9-17	Undesignated	NE NW	2	95	17E	Duchesne Uintah	UT	Oil	Green River	ML-45555		513' FSL, 787' FWL		
Balcron Monument State #22-2	Undesignated	SE NW	2	95				Oil	Green River	ML-45555		821' FNL, 2187' FWL		
Balcron Monument State #23-2	Undesignated	NE SW	2	98	17E	Uintah		Oil	Green River	ML-45555	43-047-32610	1980' FNL, 1980' FWL		
Balcron Monument State #24-2	Undesignated	SE SW			17E	Uintah	UT	WSW	Green River	ML-45555	43-047-32613	1980' FSL, 1980' FWL	]	
Balcron Monument State #32-2	Undesignated	SW NE	2	98		Uintah		Oil	Green River	ML-45555	43-047-32612	660' FSL, 1980' FWL		
Balcron Monument State #34-2	<del></del>		2	98		Uintah		PND	Green River	ML-45555	43-047-32609	1980' FNL, 1980' FEL		
Table 1 - Charles 1 - Charles #34-2	Undesignated	SW SE	2	98	17E	Uintah	υT	PND	Green River	ML-45555	43-047-32611	800' FSL, 1980' FEL		



1601 Lewis Avenue Billings, MT 59102 Office: (406) 259-7860 FAX: (406) 245-1365 FAX: (406) 245-1361 \[ \]

March 22, 1996

Utah Division of Oil, Gas and Mining 355 West North Temple Salt Lake City, UT 84180



#### Gentlemen:

Effective April 1, 1996, our name will change from Equitable Resources Energy Company, Balcron Oil Division to Equitable Resources Energy Company. Attached is a sundry notice reflecting that change. To simplify paperwork, I have done one sundry notice with copies for each of the wells. To this letter I have attached a list of our wells for your ease in filing the sundry notices in the well files. This should be sufficient for your purposes.

I have the listings on a spreadsheet so if it would be easier for you to have them sorted differently (for example, the Montana Board of Oil and Gas prefers them sorted by API number), please give me a call at (406) 259-7860, extension 240 and I would be glad to provide a list to your specifications.

This change affects only our company name. The physical locations of our offices and the personnel remain the same. We will be changing our well signs and ask for your patience and cooperation as this will be done as soon as possible but may take some time since we do have so many properties at which to make the change.

If you have any questions, please do not hesitate to give me a call.

Sincerely,

Bobbie Schuman Regulatory and

Environmental Specialist

/hs

Enclosures

ST OF UTAH								
IVISION	OF	OIL	GAS	AND	MINING			

JIVISION OF OIL, GAS AND MINII	NG	
	•	5. Lease Designation and Serial Number: See attached listing
SUNDRY NOTICES AND REPORTS	ON WELLS	6. If Indian, Allottee or Tribe Name:
Do not use this form for proposals to drill new wells, deepen existing wells, or to reent Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for si	er plugged and abandoned wells. uch proposals.	7. Unit Agreement Name: See attached listing
1. Type of Well: OIL ☐ GAS ☐ OTHER: See attached lis	ting	8. Well Name and Number: See attached listing
2. Name of Operator: Equitable Resources Energy Company, Balc	ron Oil Division	9. API Well Number: See attached listing
3. Address and Telephone Number: 1601 Lewis Avenue Avenue; Billings, MT 5		10. Field and Pool, or Wildcat: See attached listing
4. Location of Well Footages: See attached listing		county: See attached list
QQ, Sec.,T.,R.,M.:		State: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE N	ATURE OF NOTICE, REPO	RT, OR OTHER DATA
NOTICE OF INTENT (Submit in Duplicate)	1	UENT REPORT  Original Form Only)
Abandon	e Must be accompanied by a cement verifical emperiment dates. If well is directionally drilled, thange its name from Equitable Resources Ers as: 1601 Lewis Avenue is is to report the ope	d Recompletions to different reservoirs on WELL RT AND LOG form.  tition report.  give subsurface locations and measured and true  quitable Resources nergy Company.  e: Billings. MT 59102
		APR - 8 1996
13.  Name & Signature: Dobbie Schuman  Bobbie Schuman	Regulatory an THHe: <u>Environmental</u>	nd Specialist Date: March 27, 199

(This space for State use only)

OPERA'	TOR CHANGE F	ORKSHEET						7000	ypg: \$~7–SJ ∨	./
			by the division pleted. Write N/			le.		2- <b>D</b> A 3-VI	# /-SJ #/58-FILE D/GII/	
	nge of Opera ignation of		sold)	□ Designa <b>KKX</b> Operato					IM V	
The or	perator of t	the well(s)	listed below	has change	d (EFFECTI	IVE DATE:	4-1-96	)		
TO (ne	(address)	1601 LEWI BILLINGS	MT 59102-412 06 ) 259-7860		(former c	operator) (address)	EQUITABLE BALCRON 1601 LEW BILLINGS phone (4 account 1	OIL DIVI IS AVE MT 591 06)259-	02-4126 7860	Y C(
	) (attach addi									
Name: Name: Name:			API: 013-3 API: API: API: API: API: API: API: API:	Entity Entity Entity Entity	/: /: /:	SecTwp SecTwp SecTwp	Rng Rng Rng	_ Lease   _ Lease   _ Lease   _ Lease   _ Lease	Type: Type: Type: Type: Type:	
Lec 1.	Operator (A	-8-10) Su Attach to -8-10) Sun	ndry or othe this form). <sub>CL</sub>	ect 4-4-96 &	4-8-96/					
<i>I∕A</i> 3.	operating a	ment of Con any wells	nmerce has be in Utah. Is e number:	company re	d if the n gistered w	new operat with the	tor above state? (	is not yes/no)	currently If	
	comments se	lephone De ection of ould take r	eral Hells On ocumentation this form. place prior to	Form to th Management	is report review of	t). Make F <b>ederal</b> Sthrough	note o and Indi	f BLM s ian well	operator	
<u>li</u> c 5.	Changes hav <del>listed abov</del>	e been ent e. <i>(4-10-94</i> )	tered in the (	Oil and Gas	Informati	on System	ı (Wang/I	BM) <del>for</del>	<del>each-well</del>	
<u>lie</u> 6.	Cardex file	has been	updated for e	ach well li	sted above	e. (4-11-96)	)			
1207.	Well file l	abels have	been updated	for each w	ell listed	d above. (	4-11-967			
ec8.	Changes hav for distrib	e been industrial	cluded on the tate Lands an	monthly "O d the Tax Co	perator, a	Address, (4-10-967	and Acco	unt Chan	ges" memo	
<u>v</u> 9.	A folder ha placed there	s been se e for refe	t up for the rence during	Operator Ch	ange file, processin	, and a cong of the	opy of th original	nis page documen	has been ts.	

Division of Oil, Gas and Mining

OPERATOR CHANGE WORKSHEET (CONTINUED) Initial each item when completed. Write N/A if item is not applicable.	
ENTITY REVIEW  (Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. We entity changes made? (yes/no) (If entity assignments were changed, attach copies Form 6, Entity Action Form).	re of
N/4 2. State Lands and the Tax Commission have been notified through normal procedures entity changes.	of
BOND VERIFICATION (Fee wells only) # 5578314 (\$80,000) Setes Ins. Co. (Bond Rider In Progress)	
(Rule R615-3-1) The new operator of any fee lease well listed above has furnished proper bond.	a
2. A copy of this form has been placed in the new and former operators' bond files.	
3. The former operator has requested a release of liability from their bond (yes/no) Today's date 19 If yes, division response was made by lett dated 19	 er
LEASE INTEREST OHNER NOTIFICATION RESPONSIBILITY	
1. (Rule R615-2-10) The former operator/lessee of any fee lease well listed above has be notified by letter dated	ny
2. Copies of documents have been sent to State Lands for changes involving State leases.	
FILMING  1. All attachments to this form have been microfilmed. Date: May 20 1994	_ 
FILING	
1. <u>Copies</u> of all attachments to this form have been filed in each well file.	
2. The <u>original</u> of this form and the <u>original</u> attachments have been filed in the Operato Change file.	)r
COMMENTS	_
9/004/10 Blm/BIA Formal approved not necessary"	_
	_
	_

WE71/34-35



# State of Utah DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor
Ted Stewart
Executive Director
James W. Carter
Division Director

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

May 21, 1996

Equitable Resources Energy Company 1601 Lewis Avenue Billings, MT 59102

Re: Application for Injection Wells

Sections 7, 8, 16 and 17

Township 9 South, Range 17 East

Duchesne County, Utah

#### Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the following listed wells to Class II injection wells:

Monument State 22-16-9-17B

Monument State 13-16-9-17B

Monument State 33-17-9-17B

Balcron Monument Federal 42-17

Balcron Monument Federal 31-17

Balcron Monument Federal 22-17

Pomco 5

Paiute Federal 11-7

State NGC 11-16

Monument Butte Federal 1-8

Balcron Monument Federal 33-8

Paiute Federal 24-8

Balcron Monument Federal 13-8

Mocon Federal 44-7

Accordingly, the following stipulations shall apply for full compliance with this approval:

1. Compliance with all applicable requirements for the operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.



Equitable Resources Energy Company May 21, 1996 Page 2

- 2. Conformance with all conditions and requirements of the complete application submitted by Equitable Resources Energy Company.
- 3. Cement bond logs shall be run on the Monument Butte Federal 1-8, State NGC 11-16 and Pomco # 5 wells prior to conversion. Copies of the bond logs shall be submitted to the Division for review to determine if remedial cement work is necessary.

If you have any questions regarding this approval or the necessary requirements, please contact Dan Jarvis at this office.

Sincerely.

Associate Director

cc: Chuck Williams, Environmental Protection Agency Bureau of Land Management, vernal

## EREC Western Region DAILY OPERATING REPORT

MONUMENT FEDERAL #33-8

Operator:

**EREC/Western Region** 

Location:

NW SE Section 8, T98, R17E

Duchesne County, Utah

Prospect:

Monument Butte/Beluga Unit

10/15/96

Re-Completion for Injection

MIRU Pennant Well Service Rig #4. Hang well off. Pump 75 bbls hot wtr down csg. Unseat DHP. Flush rods w/55 bbls hot wtr. Pull & LD rod string. 218 - ¾" x 25' D-61 Plain (B). ND well head. NU BOP. SWIFN.

DC: \$2,017

CC: \$2,017

10/17/96

Re-Completion for Injection

Release tbg anchor. Tag fill @ 5572' KB. TOOH w/tbg string. TIH w/TS RBP, retrieving tool, 2-3/8" x 6' sub, HD pkr, SN & 172 jts tbg. Set BP @ 5486' KB, pkr @ 5421' KB (Zone 5444' - 5463'). Pump 1-1/2 bpm @ 756 psi, ISP @ 5500 psi. Reset BP @ 4694' KB, pkr @ 4598' KB (Zone 4656' - 4662'). Pump 1-1/4 bpm @ 800 psi, ISIP @ 500 psi. Reset BP @ 4162' KB, pkr @ 4004' KB (Zone 4104' - 4144'). Pump 1-1/4 bpm @ 725 psi, ISIP @ 475 psi. Reset BP @ 4064' KB. Press test csg to 1000 psi. BP failed. SWIFN.

DC: \$6,622

CC: \$8,639

10/17/96

Re-Completion for Injection

Set BP @ 4038' KB, set pkr @ 4030' KB. Press test down csg to 1000 psi, lost 200 psi in 5 minutes. TOOH w/tbg, pkr & BP. TIH w/injection string (tbg) as follows:

A second	<u>LENGTH</u>	<u>DEPTH KB</u>
1 - Arrow Set-1 pkr 2-3/8" x 5-1/2"	7.30'	4029.33'
1 - Cross Over 2-3/8" x 2-7/8"	.40'	4022.03'
1 - SN 2-7/8"	1.10'	4021.63'
130 - jts 2-7/8" EUE J-55 8rd 6.5#	4010.53'	4020.53'
КВ	10.00'	

ND BOP, drop standing valve. Press test tbg to 3000 psi, ½ hr, no loss. Set pkr @ 4029' KB. Flange up well head. Press test pkr & csg to 1000 psi, ½ hr, no loss. SWIFN w/1000 psi on csg.

DC: \$4,384

CC: \$13,023

Form 3160-5 (June 1990)

# DEPARTMENT OF THE INTERIOR

Budget Bureau No. 1004-0135 Expires: March 31, 1993 5. Lease Designation and Serial No. BUREAU OF LAND MANAGEMENT 11-74108 SUNDRY NOTICES AND REPORTS ON WELLS 6. If Indian, Allonee or Tribe Name Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.

Use "APPLICATION FOR PERMIT—" for such proposals n/a 7. If Unit or CA, Agreement Designation SUBMIT IN TRIPLICATE Beluga Unit I. Type of Well 8. Well Name and No. Oil Well Balc. Mon. 2. Name of Operator 9. API Well No. 43-013-31427 Equitable Resources Energy Company 3. Address and Telephone No. 10. Field and Pool, or Exploratory Area Monument Butte/Green River 1601 Lewis Avenue; Billings, MT 59102

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

NW SE 8-T95-RITE (406) 259-7860 11. County or Parish, State Duchesne Co. Utah 1980' FNL 1980' FEL CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA 12. TYPE OF ACTION TYPE OF SUBMISSION Change of Plans Abandonment Notice of Intent **New Construction** Recompletion Non-Routine Fracturing Plugging Back Subsequent Report Water Shut-Off Casing Repair Conversion to Injection Altering Casing Final Abandonment Notice Other request for approval to inject Dispose Water (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.) 13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\* This well has been coverted to a water injection well in accordance with the attached wellbore diagram and EPA Well Rework form. Water injection will commence when final approval has been received from the EPA, BLM, and Utah DOGM. This sundry notice is to request that approval to inject. ORIGINAL: Bureau of Land Management (Vernal, UT) (Attention: Wayne Bankert COPY: Utah Division of Oil, Gas and Mining (Attention: Dan Jarvis) COPY: U.S. EPA (Attention: Chuck Williams) NOV 1 3 1996 DIV. OF OIL, GAS & MINING Regulatory and November 12, 1996 14. I hereby certify that the foregoing is true and correct Environmental Specialist Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements

FORM APPROVED

or representations as to any matter within its jurisdiction. 9/97\*See Instruction on Reverse Side

11-11-96

· ^ ====		TTED STATES I V	ENVIRONMENT VASHINGTON,			GENCY			
<b>⇔EPA</b>	,	WELL	REWOR	ΚR	ECOR	)	·		
NAME AND ADDRESS OF PERMITT Equitable Resour Western Region 1601 Lewis Aven Dillings, Mon	ine i i i i i i i i i i i i i i i i i i		×	Per 60	AND ADDRE VNANT OO 17† enver	ss of contractor Well Servic h street 16 , Colora elo	80202		
LOCATE WELL AND OUTLINE SECTION PLAT — 640 AG	UNIT ON	STATE  UHAN  SURFACE LO  NW 14 C  LOCATE WEL  Surface 10  Location 11  and 1980 fr  WELL  Brine Di  KEnhance	CATION DESCRIPTION DESCRIPTION DIRECTOR (N/L. from (E/W) ACTIVITY asposal and Recovery	RIPTION 4 OF ECTION	IS FROM NE. Line of quarter Total Dep	AREST LINES OF QUARTE	PERMIT NUMBER FLANC #  WAN THIP 95 RANGE 175  ER SECTION AND DRILLING UNIT  TYPE OF PERMIT  Individual  Area		
		BeLv	ga Uni	+	Date Rew	vork Commenced vork Completed vork Completed	Number of Wells—— Well Number Balcron Monument Federal # 33-8		
		WELL CASIN				NORK	A. I. I. P.		
Casing	Cement			Perforations			Acid or Fracture		
Size Depth	Sacks	Туре	From		· To		Treatment Record		
Sec	Attache	J							
	WELL CASING RE	CORD — A	FTER REWO	RK ///	ndicate Add	litions and Changes Or	nly)		
Casing	Cement	<u> </u>	Pe	rforati	ons		Acid or Fracture		
Size Depth	Sacks	Туре	From		То		Treatment Record		
See	Attache	d							
	<del> </del>	•	. ,	+					
DESCRIBE REWO	RK OPERATIONS IN	I DETAIL				WIRE LINE LOGS, LI	ST EACH TYPE		
	AL SHEETS IF NECE		.		Log	Гуреѕ	. Logged Intervals		
I solated indivi	dual zones seach zon set Arro KB. Load (	testal ve, hil w Set- casins	ONNULS	HE.		ALT,	TD to Surface		
I certify under to submitted in the immediately re and complete.	his document au sponsible for ob	w that I hand all attached all attached all attached all attached attached are significant.	chments a e informati gnificant p	ally e nd tl on, l enal	xamined hat, base believe t ties for se	d on my inquiry o hat the informatio	rith the information of those individuals on is true, accurate, ormation, including		
NAME AND OFFICIAL TITLE (Plaa.  Soky Zell	se type or print)	SIGI	NATURE			_	DATE SIGNED		
150MM Zell	VITT 1	1 _				7 11.11	111-11-96		

Senior Prod EPA Form 7520-12 (2-84)



WELL NAME: BALCRON MONUMENT FEDERAL #33-8

FIELD: Monument Butte Field (Beluga Unit)

FEDERAL LEASE NO.: U-74108

LOCATION: NW SE Section 8, T9S, R17E FOOTAGE: 1980' FSL, 1980' FEL COUNTY/STATE: Duchesne County, Utah

WORKING INTEREST: 0.91491728
PRODUCING FORMATION: Green River
COMPLETION DATE: 3-30-94
INITIAL PRODUCTION: 65 BO, 200 MCF

OIL/GAS PURCHASER: Amoco

PRESENT PROD STATUS: WO Surface Equipment

ELEVATIONS - GROUND: 5,318.6' GL TOTAL DEPTH: 5,700' KB

**SURFACE CASING** 

STRING: 1 CSG SIZE: 8-5/8" GRADE: J-55 WEIGHT: 24# LENGTH: 6 jts (254.03')

DEPTH LANDED: 262' KB HOLE SIZE: 12-1/4"

CEMENT DATA: Western - 150 sxs Class "G" +

(2% CCI + 1/4 Celeflake)per sx.

**TUBING RECORD** 

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5# NO. OF JOINTS: 130 Jts (4010.53') SEATING NIPPLE: 2-7/8"x1.10' ARROW SET 1 PACKER: 2-3/8"x5-1/2"x7.30'

PACKER SET AT: 4022' KB

LOGS: IPLT, ALT, MSC

Well was cored on 2-26-94.

DATE: 11/2/95 vk

API NO.: 43-013-31427

NET REVENUE INTEREST: 0.80471769 Oil

0.73108274 Gas

SPUD DATE: 2/14/94 OIL GRAVITY: 34 BHT:

KB: 5,328.6' KB (10' KB)

PLUG BACK TD: 5633.74' KB

**PRODUCTION CASING** 

STRING: 1 CSG SIZE: 5-1/2" GRADE: K-55 WEIGHT: 15.5 #

LENGTH: 129 jts (5672.25') DEPTH LANDED: 5681.25' KB HOLE SIZE: 7-7/8"

CEMENT DATA: 132 sxs Thrifty-lite and

tail w/257 sxs 50-50 POZ.

CEMENT TOP AT: 2390' KB

PERFORATION RECORD

3/9/94 4104' - 4116' (12') 4 SPF Y3
3/9/94 4138' - 4144' (6') 4 SPF Y3
Communication between 4104' - 4116' & 4138' - 4144'
3/7/94 4656' - 4662' (6') 4 SPF R2

3/2/94 5444' - 5463'

(19') 4 SPF B1

ACID JOB / BREAKDOWN JOB

3-3-94: 5444' - 5463'

500 gallons 15% HCL. Balled off. ATP 2300 psi, max 4590 psi. ATR 7 bpm, max-7 bpm, ISIP 1200 psi, rate 13 bpm @ 5000 psi

3-7-94: 4656' - 4662'

500 gals 15% HCL. Good ball action. ATP-3300 psi, max 5000 psi.

ISIP 1600 psi, Rate 20 bpm @ 5290 psi

ATR 3.2 bpm, max 3.9 bpm

3-9-94: 4104' - 4116'

500 gais 15% HCL. Balled Off. ATP 2600 psi, max 4950 psi.

ATR 4 bpm, max 4 bpm, ISIP 430 psi Pump for rate 9.1 bpm @ 2150 psi

3-9-94: 4138' - 4144'

500 gals 15% HCL. No Ball Off. ATP 1500 psi, max 2600 psi.

ATR 3 bpm, max 8.9 bpm, ISIP 850 psi Pump for rate 8 bpm @ 2600 psi

Before Rework



**BALCRON MONUMENT FEDERAL #33-8** NW SE Section 8, T9S, R17E 1980' FSL, 1980' FEL LEASE No. U-7978 Monument Butte Field (Beluga Unit) **Duchesne County, Utah** 

11/3/95 vk

**WELL DATA SHEET CONTINUED PAGE TWO** 

#### **FRAC JOB**

3-3-93: 5444' - 5463'

24,500# 20/40 mesh sand & 25,300# 16/30 mesh sand in 5441 gals 2% KCL wtr. Ave pressure 1700 psi, max 2150 psi. Avg rate 26 BPM max 28.1 BPM. ISIP 1650 5 min 1480#, 10 min 1350# 15 min 1240#, run trace isotope.

3-7-94: 4656' - 4662'

18,100# 16/30 mesh sand in 5700 gals 2% KCL wtr. Avg Press 2700 psi, max 3550 psi. Ave Rate 20.2 BPM max 20.5 BPM. ISIP 2150 psi, 5 min 1580 psi, 10 min 1400 psi, 15 min 1340 psi.

3-9-94: 4104' - 4144' & 4138' - 4144'

52,200# 16/30 mesh sand in 19,830 gals 2% KCL wtr. Avg Press 2500 psi, max 2950 psi. Avg Rate 24.7 BPM, max 25.1 BPM. ISIP 1750 psi, 5 min 1400 psi 10 min-1350, 15 min-1320

efore Rework



BALCRON MONUMENT FEDERAL #33-8 NW SE Section 8, T9S, R17E 1980' FSL, 1980' FEL LEASE No. U-74108 Monument Butte Field (Beluga Unit) Duchesne County, Utah

Elev.GR - 5318.6' GL Elev.KB - 5328.6' KB (10' KB)

#### WELLBORE DIAGRAM

DATE: 11/3/95 vk

SUPPLOT 0.000		11.1	1		
SURFACE CASING				ACID JOB /BREAKDOWN	
CSG SIZE: 8-5/8" GRADE: J-55 WEIGHT: 24#				3-3-94: 5444' - 5463'	500 gallons 15% HCL. Balled off. ATP 2300 psi, max 4590 psi. ATR 7 bpm, max-7 bpm, ISIP
LENGTH: 254.03' (6 jts) DEPTH LANDED: 262' KB HOLE SIZE: 12-1/4" CEMENT DATA: Westem - 150 sxs Class "G" + (2% CCI + 1/4 Celeflake)per sx.				3-7-94: 4656' - 4662'	1200 psi, rate 13 bpm @ 5000 psi 500 gals 15% HCL. Good ball action. ATP-3300 psi, max 5000 psi. ATR 3.2 bpm, max 3.9 bpm ISIP 1600 psi, Rate 20 bpm @ 5290 psi
PRODUCTION CASING	262' KB			3-9-94: 4104' - 4116'	500 gals 15% HCL. Balled Off. ATP 2600 psi, max 4950 psi.
CSG SIZE: 5-1/2" GRADE: K-55 WEIGHT: 15.5# LENGTH: 5672.25' (129 jts) DEPTH LANDED: 5681.25				3-9-94: 4138' - 4144'	ATR 4 bpm, max 4 bpm, ISIP 430 psi Pump for rate 9.1 bpm @ 2150 psi 500 gals 15% HCL. No Ball Off. ATP 1500 psi, max 2600 psi. ATR 3 bpm, max 8.9 bpm, ISIP 850 psi Pump for rate 8 bpm @ 2600 psi
HOLE SIZE: 7-7/8" CEMENT DATA: 132 sxs Thrifty-lite and		$\parallel \parallel \parallel \parallel$		FRAC JOB	
tail w/257 sxs 50-50 POZ. CEMENT TOP AT: 2390' KB				3-3-93: 5444' - 5463'	24,500# 20/40 mesh sand & 25,300# 16/30 mesh sand in 5441 gals 2% KCL wtr.
TUBING			<b></b>		Ave pressure 1700 psi, max 2150 psi. Avg rate 26 BPM
SIZE/GRADE/WT.: 2-7/8", EUE J-55, 6.5# NO. OF JOINTS: 128 jts @ 4049.21' TUBING ANCHOR: 2-1/2" x 5-1/2" (Trico)			TOC @ 2390' KB	3-7-94: 4656' - 4662'	max 28.1 BPM. ISIP 1650 5 min 1480#, 10 min 1350# 15 min 1240#,run trace isotope. 18,100# 16/30 mesh sand
NO. OF JOINTS: 45 jts @ 1410.45' SEATING NIPPLE: 2-7/8" x 1.10' PERFORATED SUB: 2-7/8" x 3' MUD ANCHOR: 1 jt @ 30.52' STRING LENGTH: 5495'					in 5700 gals 2% KCL wtr. Avg Press 2700 psl, max 3550 psi. Ave Rate 20.2 BPM max 20.5 BPM. ISIP 2150 psi, 5 min 1580 psi, 10 min
SN LANDED AT: 5473.11' KB				3-9-94: 4104' - 4144' & 4138' - 4144'	1400 psi, 15 min 1340 psi. 52,200# 16/30 mesh sand in 19,830 gals 2% KCL wtr.
SUCKER RODS					Avg Press 2500 psi, max 2950 psi. Avg Rate 24.7
POLISHED ROD: 1-1/4" X 22' SUCKER RODS: 1 - 3/4" X 4' PONY 218 - 3/4" X 25' D-61 Rods			•		BPM, max 25.1 BPM. ISIP 1750 psi, 5 min 1400 psi 10 min-1350, 15 min-1320
STRING LENGTH: 5471.5'	•			PERFORATION RECORD	
PUMP NUMBER: 1041 (Trico) PUMP SIZE: 2.5"x1.5"x16' RWAC w/PA plunger	\$5.70 \$3.50 \$3.50		4104' - 16'	3/9/94 4104' - 4116' 3/9/94 4138' - 4144'	(12') 4 SPF Y3 1 (6') 4 SPF Y3 2
STROKE LENGTH: 87" PUMP SPEED. SPM: 4.5	i.e.		4138' - 44'	Communication between 4104' 3/7/94 4656' - 4662'	(-)
PUMPING UNIT: LUFKIN LM-228D-213-86T PRIME MOVER: AJAX CMA 8-1/2" x 10"	E (*)		<b>3 4656' - 62'</b>	3/2/94 5444' - 5463'	(19') 4 SPF B1 5
LOGS: IPLT, ALT, MSC					
Well was cored on 2-26-94.					
	• [7]		S 5444' - 63'		
			SN LANDED @ 5 EOT @ 5505' KB		

PBTD @ 5633.74' KB TD @ 5700' KB

Before Rework



BALCRON MONUMENT FEDERAL #33-8 NW SE Section 8, T9S, R17E 1980' FSL, 1980' FEL **LEASE No. U-74108** Monument Butte Field (Beluga Unit) Duchesne County, Utah

Elev.GR - 5318.6' GL Elev.KB - 5328.6' KB (10' KB) Injection Wellbore Diagram

DATE: 10/28/96 DZ

#### SURFACE CASING

CSG SIZE: 8-5/8" GRADE: J-55 WEIGHT: 24# LENGTH: 254.03' (6 jts) DEPTH LANDED: 262' KB HOLE SIZE: 12-1/4"

CEMENT DATA: Western - 150 sxs Class "G" +

(2% CCI + 1/4 Celeflake)per sx.

#### PRODUCTION CASING

CSG SIZE: 5-1/2" GRADE: K-55 WEIGHT: 15.5# LENGTH: 5672.25' (129 jts)

DEPTH LANDED: 5682.25' KB HOLE SIZE: 7-7/8"

CEMENT DATA: 132 sxs Thrifty-lite and

tail w/257 sxs 50-50 POZ.

CEMENT TOP AT: 2390' KB

#### TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5# NO. OF JOINTS: 130 Jts (4010.53') **SEATING NIPPLE: 2-7/8"x1.10"** ARROW SET 1 PACKER: 2-3/8"x5-1/2"x7.30" 4022' KB

PACKER SET AT:

PKR Set w/ 9" Tension

CONVERSION:

1.) Tag fill @ 5572' KB

2.) TIH w/ RBP & PKRand pump filtered KCL water to establish injection rate

into each zone.

3.) Replace 2-3/8" tbg with new 2-7/8" tbg from Marta-Co.

4.) Pump PKR fluid and Set Arrow Set-1 PKR @ 4022'. Press. test csg to 1000 psi. Good.

PACKER FLUID: Champion Cortron 2383 PKR fluid

mixed w/ 62 bbis 2% KCL water. 10/18/96

MIT RECORD:

Post Rework

262' KB

Uinta Formation Surface to 1450 ft.

TOC @ 2390' KB

#### PERFORATION RECORD

(12') 4 SPF 4104' - 4116' 3/9/94 3/9/94 4138' - 4144' (6') 4 SPF Communication between 4104' - 4116' & 4138' - 4 (6') 4 SPF 4656' - 4662' 3/7/94 3/2/94 5444' - 5463' (19') 4 SPF

Green River Formation 1450 to 5400 ft.

ARROW SET-1 PACKER SET @ 4022' KB

4104' - 16'

ੋ 4138' - 44'

4656' - 62'

35444' - 63'

Douglas Creek Member 4550 to 5400 ft. Wasatch Fm. Transition 5400 to 5950 ft.

点线[1]编数

PBTD @ 5633.74' KB TD @ 5700' KB

Wasatch Formation 5950 ft.



Michael O. Leavitt
Governor
Ted Stewart
Executive Director
James W. Carter
Division Director

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

November 20, 1996

Equitable Resources Energy Company 1601 Lewis Avenue Billings, Montana 59102

Re:

Administrative Approval for Conversion of Wells to Class II Injection Wells, Duchesne County, Utah

#### Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced wells to Class II injection wells:

Monument State 22-16-9-17B

Monument State 33-17-9-17B

Balcron Monument Federal 31-17

Pomco 5

State NGC 11-16

Balcron Monument Federal 33-8

Balcron Monument Federal 33-8

Balcron Monument Federal 13-8

Monument State 13-16-9-17B

Balcron Monument Federal 42-17

Balcron Monument Federal 31-17

Monument Butte Federal 1-8

Paiute Federal 24-8

Mocon Federal 44-7

Accordingly, the following stipulations shall apply for full compliance with this approval:

- 1. Compliance with all applicable requirements for the operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.
- 2. Conformance with all conditions and requirements of the complete application submitted by Equitable Resources Energy Company.



Page 2 Equitable Resources Energy Company November 20, 1996

Enclosed with this letter is the Underground Injection Control Permit for this well. If you have any questions regarding this approval or the necessary requirements, please contact Dan Jarvis at this office.

Sincerely,

Associate Director

lwp

cc: Dan Jackson, Environmental Protection Agency

Bureau of Land Management, Vernal



Michael O. Leavitt Governor Ted Stewart Executive Director James W. Carter Division Director

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

#### UNDERGROUND INJECTION CONTROL PERMIT

Cause No. UIC-170

Operator:

Equitable Resources Energy Company

Wells:

Monument State 22-16-9-17B
Monument State 13-16-9-17B
Monument State 33-17-9-17B
Balcron Monument Federal 42-17
Balcron Monument Federal 31-17
Balcron Monument Federal 22-17

Pomco 5

Paiute Federal 11-7 State NGC 11-16

Monument Butte Federal 1-8 Balcron Monument Federal 33-8

Paiute Federal 24-8

Balcron Monument Federal 13-8

Mocon Federal 44-7

Location:

Sections 7,8,16 and 17, Township 9 South, Range 17

East,

County: Duchesne

Well Type:

Enhanced Recovery (waterflood)

#### Stipulations of Permit Approval

1. Approval for conversion to Injection Well issued on May 21, 1996



UIC Permit UIC-170 Euitable Resources Company Page 2

- 2. Maximum Allowable Injection Pressure: 1856 psig
- 3. Maximum Allowable Injection Rate: (restricted by pressure limitation)
- 4. Injection Interval: 3190 feet to 5596 feet (Green River Formation)

Approved by:

R.J. Kirth

Associate Director, Oil and Gas

11 20 96 Date Form 3160-5 (June 1990)

#### UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM	APPR	OVED
Budget Bure	au No.	1004-0135
Expires:		

5. Lease	Designation and	Serial No.	
See	attached	list	

BUREAU OF L	BATAN ATAN ANTIN METALLINIA	See attached list
SUNDRY NOTICES A	AND REPORTS ON WELLS	6. If Indian, Allottee or Tribe Name
Do not use this form for proposals to dril	or to deepen or reentry to a different rese	n/a
Use "APPLICATION FOR	PERMIT—" for such proposals   (/ / /	7. If Unit or CA, Agreement Designation
SUBMIT	IN TRIPLICATE	
,	49 JAN 1 5.007 F	Beluga Unit
1. Type of Well    Coli		8. Well Name and No. See attached list
2. Name of Operator	DIV OF OUR CAS PAINT	9. API Well No.
Equitable Resources Energy Co	mpany (NV Crabb, Crabb, Crabb)	See attached list
1601 Lewis Avenue; Billings,	MT 59102 (406) 259-7860	10. Field and Pool, or Exploratory Area Mon. Butte/Grn. River
4. Location of Well (Footage, Sec., T., R., M., or Survey De	scription)	11. County or Parish, State
See attached 1		Duchesne County, UTAH
See abbasilea .		
TO THE POPULATE POV	s) TO INDICATE NATURE OF NOTICE,	REPORT, OR OTHER DATA
	TYPE OF A	ACTION
TYPE OF SUBMISSION	1172 077	Change of Plans
Notice of Intent	Abandonment	New Construction
· <del></del>	Recompletion Plugging Back	Non-Routine Fracturing
X Subsequent Report	Casing Repair	Water Shut-Off
The state of the Marine	Altering Casing	Conversion to Injection
Final Abandonment Notice	Other	Dispose Water (Note: Report results of multiple completion on Well
		Completion or Recompletion Report and Log form.)
13. Describe Proposed or Completed Operations (Clearly state a	all pertinent details, and give pertinent dates, including estimated dateal depths for all markers and zones pertinent to this work.)*	ne of starting any proposed work. If wen is discussed,
give subsurface locations and measurement		
The Dalcron	Monument Federal # 33.	-8 has been
and the second to the	ustor injection for Secondary Pet	Covery of remaining
oil reserves.	The well was treated with 5 gal	F happole of 25 KCl
and 10 gallons	s of 940 surfactant mixed with 75 mperature of approximately 160 F	to clear the wellbore
water at a ter	of residual oil. The well was	then placed on injection
and formation	approximately 475	STBWPD.
Water injecti	on commenced on December 3, 1996	•
222241	of Land Management (Vernal	UT)
ORIGINAL: Bu	reau of Land Management (Vernal,	017
COPY: Utah D	ivision of Oil, Gas and Mining nvironmental Protection Agency (	UIC Section)
COPY: U.S. E	TVIPOIMMENTAL PLOCECTION Agency	
		:
·	Regulatory and	
14. I hereby certify that the foregoing is true and correct	Environmental Speci	ialist Date January 13, 1997
Signed Dobbie Schuman	TitleTitle	
(This space for Federal or State office use)		Date
Approved by	Title	
Conditions of approval, if any:		•

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

								_	Sheet1	Federal		~	` <b>,</b>
	Field					•		Status	tormation	• .	APT #	Footages	TINS
Balcron Monument Fed. #13-8	Monument Butte	NW SW	8	98	17E	Duchesne	UΤ			UTU-74108	43-013-31382	2060' FSL, 694' FWL	Beluga
Balcron Monument Fed. #22-17	Monument Butte	SE NW	17	98	17E	Duchesne	UT	Oil	Green River	UTU-72106	43-013-31429	1800' FNL, 1980' FWL	Beluga
Balcron Monument Fed. #31-17	Monument Butte	NE NW	17	98	17E	Duchesne	UT	Oil	Green River	UTU-72106	43-013-31428	660' FNL, 1980' FEL	Beluga
Balcron Monument Fed. #33-8	Monument Butte	NW SE	8	98	17E	Duchesne	UT	Oil	Green River	UTU-74108	43-013-31427	1980' FSL, 1980' FEL	Beluga
Balcron Monument Fed. #42-17	Monument Butte	SE NE	17	98	17E	Duchesne	UT	Oil	Green River	UTU-72106 -	43-013-31467	1800' FNL, 700' FEL	Beluga
Balcron Monument Fed. #43-7	Monument Butte	NE SE	7	98	17E	Duchesne	UT	Oil	Green River	UTU-72106	43-013-31432	1850' FSL, 850' FEL	Beluga
Monument Federal #23-17-9-17B	Monument Butte	NE SW	17	98	17E	Duchesne	UT	OIL	Green River	UTU-74108		2217' FSL, 2187 FWL	Beluga
Mocon Federal #44-7	Monument Butte	SE SE	7	98	17E	Duchesne	UT	Oil	Green River	U-3563-A	43-013-30666	670' FSL, 663' FEL	Beluga
15.1.1.1.20.47.0.470	Monument Butte	NW SE	17	98	17E	Duchesne	LIT	COMPL	Green River	U-72106		1926' FSL, 2000' FEL	Beluga
Monument Federal #33-17-9-17B	Monument Butte	SE SE				Duchesne		PND		U-74398	43-013-30643	602' FSL, 598' FEL	Beluga
Monument Federal #44-8-17B	Monument Butte	NW NW			<u></u>	Duchesne		DRLG		State ML-21844	43-013-30616	660' FNL, 659' FWL	Beluga
Monument State #11-16-9-17B (Re-entry)	Monument Butte	NW SW				Duchesne	UT	<u> </u>	Green River	State ML-3453-B	43-013-31580	1980' FSL, 660' FWL	В
Monument State #13-16-9-17B		SE NW	16			Duchesne	UT		Green River	State ML-3453-B	43-013-31579	1824' FNL, 1981' FWL	Beluga
Monument State #22-16-9-17B	Monument Butte			98		Duchesne				U-3563-A	43-047-30516	661' FNL, 664' FWL	Beluga
Paiute Federal #11-17	Monument Butte	NW NW						<u> </u>		UTU-74108	43-013-30675	660' FSL, 1980' FWL	Beluga
Paiute Federal #24-8	Monument Butte	SE SW	8			Duchesne				<u> </u>	43-013-30499	1980' FSL, 660' FWL	Beluga
POMCO #5	Monument Butte	NW SW	17	98	17E	Duchesne	UT	OII	Green River	010-74108	143-013-30499	1300 1 02, 000 1 442	Doruga

1-10-97/20

Page No. 5 06/16/97

## STATE OF UTAH INVENTORY OF INJECTION WELLS

	OPERATOR ******	API NO.	WELL *******	TNS	RGE ***	SE **	WELL'	TYPE I	NDIA	N COUNT
	EQUITABLE RE	<b>43-013-31410</b>	12-12J	098	16E	12	INJW			*****
	EQUITABLE RE	43-013-31408		09S	16E	14			N	
	EQUITABLE RE	43-013-31421	21-14J	098	16E	14	INJW		N	
	EOUITABLE RE	43-013-31373	23-15J	09S			INJW		N	
•	EQUITABLE RE	¥43-013-31368	32-15J		16E	15	WLMI		N	
	EQUITABLE RE	43-013-31367	41-15J	09S	16E	15	INJW		N	
	EQUITABLE RE	43-013-31370		09S	16E	15	WUNI		N	
	EQUITABLE RE	<b>*43-013-31370</b>	FEDERAL 13-5 24-5	09S	17E	5	WLNI		Y	
	EQUITABLE RE	43-013-31375		09S	17E	5	INJW		Y	
	EQUITABLE RE	43-013-31384	22-5	09S	17E	5	WLMI		Y	
	EQUITABLE RE	43-013-31195 343-013-31492	ALLEN FEDERA	09S	17E	6	INJW		N	
	EQUITABLE RE	43-013-31492	11-7J	09S	17E	7	WLMI		Y	
	EQUITABLE RE	43-013-31405	31-7J	09S	17E	7	WLNI		Y	
	EQUITABLE RE	43-047-20252	E. RED WASH	085	25E	5	INJW		N	
	EQUITABLE RE	43-047-20261	ERW 4-6	08S	25E	6	INJW		Y	
	EQUITABLE RE		42-6X	08S	25E	6	INJW		N	
	EQUITABLE RE	43-047-20245	AMERADA GUIN	08S	25E	7	INJW		Y	
	EQUITABLE RE	<b>43</b> ÷013÷30666 <b>43</b> ÷013÷31382	44-7	09S	17E	7		43563	Y	11880
	EQUITABLE RE		13-8	09S	17E	8		4007978		11880
	EQUITABLE RE	43-013-31427	33-8	09S	17E	8	NUNI	NO07978		11880
	EQUITABLE RE	43-013-30675	24-8	095	17E	8	WLMI	47978	Y	11880
	EQUITABLE RE	43-013-30648	44-8-17B	09S	17E	8	INJW	440326		1523
	EQUITABLE RE	43-013-31580	13-16-9-17B	09S	17E	16		ML34536		11880
		43-013-30616	11-16-9-17B	09S	17E	16	WLNI	mL2184	Ϋ́	6130
	EQUITABLE RE	43-013-31145	22-16-9-17B	09S	17E	16	INJW	mL3453	B Y	11880
	EQUITABLE RE	43 013 30518	11 17 POMGO 5	<del>- 09S -</del>	-17E	<del>-17-</del>	WUNI	11000	Y	
	EQUITABLE RE	43-013-30499	POMCO 5	09S	17E	17	WLMI	U7978	Y	11880
	EQUITABLE RE	43-013-30516 43-013-31428	11-17	09S	17E	17	WUNI	435631		11880
	EQUITABLE RE	43-013-31428	31-17	09S	17E	17	WLMI	WTU 721		11880
	EQUITABLE RE	43-013-31381	33-17-9-17B 22-17	09S	17E	17	WLNI	472106	Y	11880
	EQUITABLE RE	43=013-31467	42-17	09S	17E	17	INJW	UT4721		11880
	EQUITABLE RE	43-047-32610	22-2	09S	17E	17	INJW	WT47216	ob Y	11880
	EQUITABLE RE	43-013-31425	14-2	09S	17E	2	WUNI		Y	
	GIANT EXPLOR	43~013~31423		09S	17E	2	WLNI		Y	
	GIANT EXPLOR	43-037-13042	GOTHIC MESA SENTINEL PEA	41S	23E	16	INJD		Y	
	GIANT EXPLOR	43-037-20292		41S	26E	27	INJD		Y	
	HAY HOT OIL	43-037-10432	9-24	41S	23E	9	INJI		Y	
	INLAND PRODU	43-013-30843	MCCRAKEN PT	40S	23E	19	INJI		N	
	INLAND PRODU	43-013-30843	MONUMENT BUT 15-25	08S	16E	34	WLNI		Y	
	INLAND PRODU	43-013-31559	FEDERAL 3-33	08S	16E	25	INJW		N	
	INLAND PRODU	43-013-30898		08S	16E	33	INJW		N	
	INLAND PRODU	43-013-30686	FED 1-34	08S	16E	34	INJW		N	
	INLAND PRODU	43-013-30606	FEDERAL 5-35 MONUMENT BUT	08S	16E	35	INJW		N	
	INLAND PRODU	43-013-30745	MONUMENT BUT	08S	16E	35	WUNI		N	
	INLAND PRODU	43-013-30743	1A-35	085	16E	35	WCMI		N	
	INLAND PRODU	43-013-31514	MONUMENT BUT	08S	16E	35	INJW		Y	
	INLAND PRODU	43-013-31264	MONUMENT FED	08S	16E	35	INJW		N	
	INLAND PRODU	43-013-31264	MONUMENT BUT	08S	16E	35	WCMI		N	
	INLAND PRODU	43-013-30608	STATE 5-36	08S	16E	35	INJW		N	
	INLAND PRODU	43-013-30524	STATE 1-36	08S	16E	36	INJW		N	
	INLAND PRODU	43-013-30392	12-32	08S	16E	36	INJW		N	
	INLAND PRODU	43-013-30787	FED 15-28	08S 08S	17E	32	INJW		Y	
	INLAND PRODU	43-013-30779	14A-28		16E	28	INJW		N	
•		010 01012	~ 112 ~ 70	08S	16E	28	WLMI		N	



October 7, 1997

Bureau of Land Management Vernal District Office 170 South 500 East Vernal, UT 84078

RE: Change of Operator

Duchesne & Vernal Counties, Utah

Dear Mr. Forsman:

Please find attached Sundry Notices and Reports on Wells for Change of Operator, previously operated by Equitable Resources Energy Company for approval.

If you should have questions regarding this matter, please do not he sitate to contact me at the number listed below.


Sincerely,

INLAND PRODUCTION COMPANY

Barrean

Patsy Barreau

/pb encls.



# STATE OF UTAH DIVISION OF OIL, GAS AND MINING

		5. Lease Designation and Serial Number:			
		See Attached			
SUNDRY NOTICES AND REPORTS	ON WELLS	6. If Indian, Allottee or Tribe Name:			
	n/a				
Do not use this form for proposals to drill new wells, deepen existing wells, or to reen	ter plugged and abandoned wells	7. Unit Agreement Name;			
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for a	uch proposals.	See Attached			
1. Type of Well: OIL T GAS OTHER:		8. Well Name and Number:			
	-DECENIED	See Attached			
2. Name of Operator:		9. API Well Number:			
Inland Production Company	OCT 1 3 <b>1997</b>	See Attached			
3. Address and Telephone Number:		10. Field and Pool, or Wildcat:			
475 - 17th Street, Suite 1500, Der	ver, CO 80202	See Attached			
4. Location of Well					
Footages: See Attached Exhibit		County:			
OQ, Sec.,T.,R.,M.:		State:			
11. CHECK ADDRODDIATE BOYES TO INDICATE N					
11. CHECK APPROPRIATE BOXES TO INDICATE N	ATURE OF NOTICE, REPOR	T, OR OTHER DATA			
NOTICE OF INTENT	SUBSEQU	ENT REPORT			
(Submit in Duplicate)	(Submit Ork	ginel Form Only)			
☐ Abandon ☐ New Construction	☐ Abandon *	☐ New Construction			
☐ Repair Casing ☐ Pull or Alter Casing	☐ Repair Casing	☐ Pull or Alter Casing			
☐ Change of Plans ☐ Recomplete	Change of Plans	☐ Reperforate			
☐ Convert to Injection ☐ Reperforate	☐ Convert to Injection	☐ Vent or Flare			
☐ Fracture Treat or Acidize ☐ Vent or Flare	☐ Fracture Treat or Acidize	☐ Water Shut-Off			
☐ Multiple Completion ☐ Water Shut-Off	(X) Other Change of Opera	<del></del>			
☑ Other <u>Change of Operator</u>	Change of Opera	açor			
0,001,0001	Data of week assemble 20	0.07:			
Approximate date work will start	•	0-97'			
- Province duto from this dut	Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.				
	Must be accompanied by a cement verification report.				
2. DESCRIPE PROPOSED OF COMPLETED OFFICE PROPOSED OF					
<ol><li>DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and givertical depths for all markers and zones pertinent to this work.)</li></ol>	e pertinent dates. If well is directionally drilled, gi	ive subsurface locations and measured and true			
Effortive Contember 20, 1007, Total 1 - 1					
Effective September 30, 1997, Inland Producti	on Company will take ov	ver operations of the			
wells on the attached list. The previous ope	rator was :	_			
	Equitable Resou 1601 Lewis Aven	arces Energy Company			
		59102			
Effective September 30, 1997, Inland Producti	on Company is responsib	ole under the terms			
and conditions of the leases for operations of	conducted on the leased	lands for a portion			
thereof under State of Utah Statewide Bond No	. 4471291.				
		OCT 1 (1997)			
3.					
lame & Signature: CHRIS	A. POTTER, ATTORNEY-IN-FA	$CT \qquad \qquad Date: \qquad 9/30/97$			

his space for State use only)

#### INLAND

Inland Resources Change of Operator	l;						
WELL NAME	LOCATION	COUNTY	ST	FIELD NAME	API NUMBER	LEASE NO.	AGEEMENT
AL OPON FEBRUARY							
BALCRON FEDERAL #22-20Y	SE NW 209S 18E	UINTAH	UΤ	MONUMENT BUTTE (8)	43-047-32711-00	UTU64917	
BALCRON FEDERAL #41-19Y	NENE 199S 18E	UINTAH	UT	MONUMENT BUTTE (8)	43-047-32504-00	UTU65635	
MONUMENT FEDERAL #43-19Y	NE SE 199S 18E	UINTAH	UT	MONUMENT BUTTE (8)	43-047-32730-00	UTU65635	
MONUMENT FEDERAL #14-21Y	SW SW 219S 18E	UINTAH	UT	MONUMENT BUTTE (8)	43-047-32726-00	UTU68105	
A ANDERSON STATE #1-16	SW SW 169S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-15582-00		UTU75023X
D. DUNCAN STATE #16-5	SWNW 169S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30570-00		UTU75023X
DMD FEDERAL #17-1	NE SE 179S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30689-00		UTU75023X
FEDERAL #1-18	NWNE 189S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30332-00		UTU75023X
MAXUS FEDERAL #23-8	NESW 8 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31196-00		UTU75023X
MONUMENT BUTTE FED. #12-17	SWNW 179S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31431-00		UTU75023X
MONUMENT BUTTE FED. #14-8	SWSW 8 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31398-00		UTU75023X
MONUMENT BUTTE FED. #21-17	NENW 179S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31387-00		UTU75023X
MONUMENT BUTTE FED. #32-17	SWNE 179S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31465-00		UTU75023X
MONUMENT BUTTE FED. #41-17	NENE 179S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31466-00	**	UTU75023X
MONUMENT BUTTE FED. #43-7	NESE 7 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31432-00	• • • • • • • • • • • • • • • • • • •	UTU75023X
MONUMENT FEDERAL #23-17B	NE SW 179S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31582-00	UTU74108	UTU75023X
MONUMENT STATE #23-16B	NE SW 169S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31578-00	The same of the same and descriptions to a part and common	UTU75023X
PAIUTE FEDERAL #34-8	SWSE 8 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30778-00		UTU75023X
PAIUTE FEDERAL #43-8	NESE 8 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30777-00		UTU75023X
POMCO #2	NWSE 189S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30505-00		UTU75023X
POMCO #4	NWSW 179S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30506-00	and the specific control of the state of the second section is a second	UTU75023X
SUE MORRIS #16-3	NENW 169S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30562-00		UTU75023X
MOCON FEDERAL #44-7	SE SE 7 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30666-00		UTU75023X
MONUMENT FEDERAL #13-8	NW SW 8 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31382-00		UTU75023X
MONUMENT FEDERAL #33-8	NW SE 8 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31427-00		UTU75023X
MONUMENT FEDERAL #22-17	SE NW 179S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31429-00		UTU75023X
MONUMENT STATE #13-16B	NW SW 169S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31580-00		UTU75023X
MONUMENT STATE #11-16B	NW NW 169S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30616-00	ML21844 Beliga	UTU75023X
MONUMENT STATE #22-16B	SE NW 169S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013 <del>-31579-0</del> 0	31145	UTU75023X
MONUMENT FEDERAL #31-17	NW NE 179S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31428-00		UTU75023X
MONUMENT FEDERAL #33-17B	NW SE 179S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-31581-00		UTU75023X
MONUMENT FEDERAL #42-17	SE NE 179S 17E	DUCHESNE	UT	The state of the s	43-013-31467-00	UTU74108	UTU75023X
MONUMENT FEDERAL #44-8-9-17B	SE SE 8 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30643-00	UTU74398	UTU75023X
PAIUTE FEDERAL #24-8	SE SW 8 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30675-00		UTU75023X
PAIUTE FEDERAL #11-17	NW NW 179S 17E	DUCHESNE	UT		43-013-30516-00		UTU75023X
POMCO #5	SW SW 179S 17E	DUCHESNE	UT		43-013-30499-00		UTU75023X
BALCRON FEDERAL #12-10Y	SW NW 109S 17E	DUCHESNE	UT	MONUMENT BUTTE (CD)		UTU65210	0.0700207
BALCRON FEDERAL #21-10Y	NE NW 109S 17E	DUCHESNE	UT	MONUMENT BUTTE (CD)	43-013-31537-00	UTU65210	
BALCRON FEDERAL #22-10Y	SENW 109S 17E	DUCHESNE	UT	MONUMENT BUTTE (CD)	43-013-31395-00	UTU65210	

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

OCT 1 0 1997

**PECEIVED** 

TRANSFER OF AUTHORITY TO INJECT - UIC FORM 5

OCT 1 3 1997

	and the second s
Well name and number: See Attached	BELUGA (GREEN RIVER) UNIT
Field or Unit name: See Attached	API no. See Attached
Well location: QQ section tow	unship range county
See Attached  Effective Date of Transfer:Septemb	i
CURRENT OPERATOR	
Transfer approved by:	
Name David M. McCoskery	Company Equitable Resources Energy Co.
1 Postall	Address 1601 Lewis Avenue
Title Director of Operations & Engineer	<b>.</b>
	Phone ( 406 ) 259-7860 ·
Comments:	
· ·	
_	
NEW OPERATOR	
Transfer approved by:	
Name Christ Potter	Company Inland Deschaption Command
(1) 121	Company Inland Production Company
title CHRIS A. POTTER, ATTORNEY-IN-FAC	Address 475 - 17th Street, Suite 1500
	Denver, CO 80202
ate _9_30_97	Phone ( 303 ) 292–0900
Comments:	
State use only) ransfer approved by	Title MANNAR
pproval Date 3-19-98	Title Thungar
phinal nate 2 1/ / 0	
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	06.7 26 1997

#### Injection wells

С,

MONUMENT BUTTE STATE #14-2	SW SW 2 9S 17E	DUCHESNE	UT	UNDESIGNATED (CD)	43-013-31425-00	UTU45555	
MONUMENT BUTTE STATE #22-2	SE NW 2 9S 17E	UINTAH		UNDESIGNATED (CD)	43-047-32610-00	UTU45555	
	The second secon					01040000	man to the state and the state of the state of
MOCON FEDERAL #44-7	SE SE 7 9S 17E	DUCHESNE	UT	MONUMENT BUTTE (B)	43-013-30666-00	+- · · · · · · · · · · · · · · · · · · ·	UTU75023X
MONUMENT FEDERAL #13-8	NW SW 8 9S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-31382-00		UTU75023X
MONUMENT FEDERAL #33-8	NW SE 8 9S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-31427-00		UTU75023X
MONUMENT FEDERAL #22-17	SE NW 179S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-31429-00		UTU75023X
MONUMENT STATE #13-16B	NW SW 169S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-31580-00	4	UTU75023X
MONUMENT STATE #11-16B	NW NW 169S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-30616-00	ML21844	UTU75023X
MONUMENT STATE #22-16B	SE NW 169S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-34579-00	the state of the s	
MONUMENT FEDERAL #31-17	NW NE 179S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-31428-00	31145 mL34538	
MONUMENT FEDERAL #33-17B	NW SE 179S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-31581-00	†··	UTU75023X
MONUMENT FEDERAL #42-17	SE NE 179S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-31467-00	UTU74108	UTU75023X
MONUMENT FEDERAL #44-8-9-17B	SE SE 8 9S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-30643-00	UTU74398	UTU75023X
PAIUTE FEDERAL #24-8	SE SW 8 9S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-30675-00	dependent of the second of the second	UTU75023X
PAIUTE FEDERAL #11-17	NW NW 179S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-30516-00	UTU74108	UTU75023X
POMCO #5	SW SW 179S 17E	DUCHESNE		MONUMENT BUTTE (B)	43-013-30499-00		UTU75023X
The second secon			<u> </u>	MOTOMETAL BOLLE (B)	43-013-30499-00	<del>-</del>	UTU75023X
PARIETTE BENCH #4 (SWD)	SWSE 7 9S 19E	UINTA	UT	PARIETTE BENCH	43-047-15681-00	UTU017992	0040000000
	The second secon	E. T. T. T.	Ϋ,	TO THE BEINGIT	40-047-10001-00	01001/995	8910069630
	<del></del>			<u> </u>			



(406) 259-7860 Telephone (406) 245-1361 Fax

December 10, 1997

Lisha
State of Utah
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, UT 84114-5801

Dear Lisha:

RE: Equitable Sale of Utah Properties

Effective September 30, 1997, Equitable Resources Energy Company sold all of its Utah properties to Inland Production Company.

Please feel free to contact me if you require additional information.

Sincerely,

Molly Conrad

Agent for Equitable Resources

**Energy Company** 

/mc



Crazy Mountain Oil & Gas Services P.O. Box 577 Laurel, MT 59044 (406) 628-4164 (406) 628-4165

TO: Lishar St of Wan.

FROM.

Molly Conrad Crazy Mountain Oil & Gas Services (406) 628-4164

Pages Attached - Including Cover Sheet 2.

Callief you need anything further.



### United States Department of the Interior

#### **BUREAU OF LAND MANAGEMENT**

Utah State Office P.O. Box 45155 Salt Lake City, UT 84145-0155

IN REPLY REFER TO UT-931

March 2, 1998

Inland Production Company 475 17th Street, Suite 1500 Denver, Colorado 80202

Re:

Beluga (Green River) Unit Duchesne County, Utah

#### Gentlemen:

On February 26, 1998, we received an indenture dated November 17, 1997, whereby Equitable Resources Energy Company resigned as Unit Operator and Inland Production Company was designated as Successor Unit Operator for the Beluga (Green River) Unit, Duchesne County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective March 2, 1998. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the Beluga (Green River) Unit Agreement.

Your statewide (Utah) oil and gas bond No. 0056 will be used to cover all operations within the Beluga (Green River) Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks Chief, Branch of Fluid Minerals

#### **Enclosure**

bcc:

District Manager - Vernal (w/enclosure)

Division of Oil, Gas & Mining Minerals Adjudication Group U-932

File - Beluga (Green River) Unit (w/enclosure)

MMS - Data Management Division

Agr. Sec. Chron/Fluid Chron

UT931:TAThompson:tt:3/2/98

Page No. 03/02/98


#### Well Status Report Utah State Office Bureau of Land Management

Lease Api Number Well Name QTR Section Township Range Well Status Operator

** Inspection I	tem: UTU75023X					
STATE	4301315582 1-16 SHELL-STATE	SWSW	16 T 9S	R17E	POW	EQUITABLE RESOURCES ENERGY CO
UTU3563	4301330332 1-18 FEDERAL	NWNE	18 T 9S	R17E	TA	EQUITABLE RESOURCES ENERGY CO
STATE	4301330616 11-16 STATE-NGC	NUNU	16 T 9S	R17E	ABD (WIW)	EQUITABLE RESOURCES ENERGY CO
UTU <b>7</b> 2106	4301330516 11-17 PIUTE-FEDERAL	NWNW	17 T 9S	R17E	WIW	EQUITABLE RESOURCES ENERGY CO
UTU72106	4301331431 12-17	SWNW	17 T 9S	R17E	POW	EQUITABLE RESOURCES ENERGY CO
STATE	4301331580 13-16-9-17B	NWSW	16 T 9S	R17E	WIW	EQUITABLE RESOURCES ENERGY CO
UTU74108	4301331382 13-8 MONUMENT FED	NWSW	8 T 9S	R17E	WIW	EQUITABLE RESOURCES ENERGY CO
UTU74108	4301331398 14-8 MONUMENT FED	SWSW	8 T 9S	R17E	POW	EQUITABLE RESOURCES ENERGY CO
STATE	4301330562 16-3 MORRIS SUE	NENW	16 T 98	R17E	POW	EQUITABLE RESOURCES ENERGY CO
STATE	4301330570 16-5 DUNCAN-STATE	SWNW	16 T 9S	R17E	PO₩	EQUITABLE RESOURCES ENERGY CO
UTU44430	4301330689 17-1 FEDERAL-DMD	NESE	17 T 98	R17E	POW	EQUITABLE RESOURCES ENERGY CO
UTU3563	4301330505 2 POMCO	NWSE	18 T 9S	R17E	TA	EQUITABLE RESOURCES ENERGY CO
UTU <b>7</b> 2106	4301331387 21-17 MONUMENT FED	NENW	17 T 9S	R17E	POW	EQUITABLE RESOURCES ENERGY CO
STATE	4301331145 22-16-9-17B	SENW	16 T 9S	R17E	WIW	EQUITABLE RESOURCES ENERGY CO
UTU72106	4301331429 22-17 MONUMENT FED	SENW	17 T 9S	R17E	MIM	EQUITABLE RESOURCES ENERGY CO
STATE	4301331578 23-16-9-17B	NESW	16 T 9S	R17E	PO₩	EQUITABLE RESOURCES ENERGY CO
UTU74108	4301331582 23-179-17B	NESW	17 T 9S	R17E	POW	EQUITABLE RESOURCES ENERGY CO
UTU74108	4301331196 23-8 MAXUS-FEDERAL	NESW	8 T 9S	R17E	POW	EQUITABLE RESOURCES ENERGY CO
UTU74108	4301330675 24-8 PIUTE-FEDERAL	SESW	8 T 9S	R17E	WIW	EQUITABLE RESOURCES ENERGY CO
UTU72106	4301331428 31-17 MONUMENT BUTTE	NWNE	17 T 9S	R17E	WIW	EQUITABLE RESOURCES ENERGY CO
UTU72106	4301331465 32-17	SWNE	17 T 9S	R17E	POW	EQUITABLE RESOURCES ENERGY CO
UTU72106	4301331581 33-17-9-17B	NWSE	17 T 98	R17E	WIW	EQUITABLE RESOURCES ENERGY CO
บาบ74108	4301331427 33-8 MONUMENT FED	NWSE	8 T 9S	R17E	WIW	EQUITABLE RESOURCES ENERGY CO
UTU <b>7</b> 4108	4301330778 34-8 PAIUTE	SWSE	8 T 9S	R17E	POW	EQUITABLE RESOURCES ENERGY CO
UTU74108	4301330506 4 POMCO	SWSW	17 T 9S	R17E	POW	EQUITABLE RESOURCES ENERGY CO
UTU72106	4301331466 41-17	NENE	17 T 9S	R17E	POW	EQUITABLE RESOURCES ENERGY CO
UTU <b>7</b> 2106	4301331399 41-18 BALCRON FED	NENE	18 T 9S	R17E	ABD (PA)	EQUITABLE RESOURCES ENERGY CO
UTU <b>7</b> 2106	4301331467 42-17	SENE	17 T 9S	R17E	WIW	EQUITABLE RESOURCES ENERGY CO
UTU72106	4301331432 43-7 MONUMENT BUTTE	NESE	7 T 98	R17E	POW	EQUITABLE RESOURCES ENERGY CO
UTU74108	4301330777 43-8 PAIUTE	NESE	8 T 9S	R17E	POW	EQUITABLE RESOURCES ENERGY CO
UTU72106	4301330666 44-7 MOCOW-FEDERAL	SESE	7 T 9S	R17E	WIW	EQUITABLE RESOURCES ENERGY CO
UTU74398	4301330643 44-8-9-17	SESE	8 T 9S	R17E	WIW	EQUITABLE RESOURCES ENERGY CO
UTU74108	4301330499 5 POMCO	NWSW	17 T 9S	R17E	WIW	EQUITABLE RESOURCES ENERGY CO

# BELUGA (GREEN RIVER) UNIT DUCHESNE COUNTY, UTAH

EFFECTIVE: FEBRUARY 1, 1996



17E

-- UNIT OUTLINE (UTU75023X)
2,223.13 ACRES

SECONDARY
ALLOCATION

FEDERAL 89.74% STATE 10.26%

Division	of Oil,	Gas and	d Mining

#### **OPERATOR CHANGE WORKSHEET**

Attach all documentation received by the division regarding this change. Initial each listed item when completed. Write N/A if item is not applicable.

Routing	0/
1-17Ce	6-12
2-GL# B	7-KAS
3-11- Jul	8-SI V
4-VLD	9-FILE
5-IRR 1	

							_5 <u>-</u> JB	2B 1/		
XX			tor (well sold)		Designation of Age					
<u> </u>	De	signation of O	perator		Operator Name Ch	ange Only	•			
The	е ор	erator of the w	vell(s) listed below	ow has change	ed, effective:9-	30-97				
TO: (new operator) <u>INLA</u>			INLAND PROD	NLAND PRODUCTION CO. FROM: (old operator)		EQUITABLE	RESOUR	CES ENERGY		
		(address)	PO BOX 1446				C/O CRAZY MTN O&G SVS'S			
			ROOSEVELT U	T 84066	<del></del>		PO BOX 57			
			Dh (4.25)	700 5100	<del></del> .		LAUREL MT			
			Phone: (435)				Phone: <u>(40</u>		164	
			Account no1	N3100			Account no	<u> N9890</u>		
WE	WELL(S) attach additional page if needed: *BELUGA (GREEN RIVER) UNIT									
Nam	e: _	**SEE ATTAC	HED** A	PI:4 <u>3-013-3</u>	1427 Entity:	S 7	ΓR	Lease:		
Nam	_		A	PI:	Entity:	s ī	R R	_ Lease:		
Nam Nam	_			PI:	Entity:	s T	R R	_ Lease:		
Nam				PI: PI:	Entity:	S 1	[ R	_ Lease:		
Name			AI		Entity:	$\begin{array}{cccccccccccccccccccccccccccccccccccc$	R R	_ Lease: Lease:		
Name	e:		AI	PI:	Entity:	S T		Lease:		
Lec Lec Va	<ol> <li>2.</li> <li>3.</li> </ol>	(r649-8-10) form). (feel) The <b>Depart</b>	3-10-47     Sundry or othe   (0-20-97)   ment of Comm	legal documen er legal docum	tation has been received an entation has been a contacted if the newith the state? (y	received from	the <b>NEW</b> op	erator (A	ttach to this	
Lec	4.	FOR INDIA note of BLM	→ N AND FEDER  I status in community to the properties of the	RAL WELLS ments section	ONLY. The BLM of this form. BLM or to the division's	has been cont	tacted regardir	ng this cha	ange. Make	
lec	5.	Changes have	e been entered i	n the <b>Oil and</b>	Gas Information	System (3270	l) for each wel	l listed al	2070	
$\rho^-$		(3-11-98)	* Quattro Pr	o s'. DBASE (	Gas Information (	J3500 (32/0	, ioi cacii wei	i iiswu al	JO V C.	
<u>jec</u>	6.	Cardex file h	nas been update	d for each wel	l listed above. (3-1	1-987				
ec	7.	Well file labo	els have been up	pdated for eacl	h well listed above.	(3-11-98)				
he I	8.	Changes have to Trust Land	been included o ls, Sovereign La	on the monthly ands, UGS, Ta	v "Operator, Addres x Commission, etc.	ss, and Accou	nt Changes" <b>n</b>	nemo for	distribution	
Lec	9.	A folder has reference dur	been set up for ing routing and	r the <b>Operato</b> processing of	r Change file, and the original docum	i a copy of the	nis page has b	een place	ed there for	

### STATE OF UTAH DIVISION OF OIL GAS AND MINING

#### **INJECTION WELL - PRESSURE TEST**

Company Name:	ection: 8 Township: Township: Township: Federal	Paw Υ Indian
Inspector: Jimio	This ram Date: 10	0-04-01
Initial Conditions:		
Tubing - Rate:	Pressu	re: <u>/800</u> psi
Casing/Tubing Annulus -	Pressure:psi	
Conditions During Test:		
Time (Minutes)	Annulus Pressure	Tubing Pressure
0	1150	1800
5	1150	18-00
10	1150	1800
15	1150	18 00
20	1150	1800
25	1150	1800
30	1156	1806
Results: Pass/Fail		***************************************
Conditions After Test:		
Tubing Pressure: _/	fcc psi	
Casing/Tubing Annu	lus Pressure: 1/50 psi	
COMMENTS: 1. full	Sum le grit	1 Luit DONE BPD
COMMENTS: Two ful fa	1 + + Bartis	learder + ti-) = 9:58 pm
17533.7 109ac, K	cropa (no or phase)	arong in 1,50 pm
Brent Coo	<u>/</u> (	
Operator Representative		

### STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES

DEPARTMENT OF NATURAL RESOURCES			
DIVISION OF OIL, GAS, AND MINING		5. LEASE DESIGNATION AND SERIA UTU-74108	AL NO.
SUNDRY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBA	L NAME
(Do not use this form for proposals to drill or to deepen or plug back to a difference of the Use "APPLICATION FOR PERMIT" for such proposals.)	N/A		
	7. UNIT AGREEMENT NAME		
OIL GAS WELL OTHER X Injection	BELUGA	·	
2. NAME OF OPERATOR INLAND PRODUCTION COMPANY		8. FARM OR LEASE NAME  MONUMENT FEL	33-8-9-17
3. ADDRESS OF OPERATOR Rt. 3 Box 3630, Myton Utah 84052 435-646-3721		9. WELL NO.  MONUMENT FEL	33-8-9-17
<ol> <li>LOCATION OF WELL (Report location clearly and in accordance with any State requ See also space 17 below.)</li> </ol>	uirements.*	10. FIELD AND POOL. OR WILDCAT	
At surface		MONUMENT BUT	ГТЕ
NW/SE Section 8, T09S R17E 1980 FSL 1980 FEL		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA NW/SE Section 8, 7	
14 API NUMBER 43-013-31427  15. ELEVATIONS (Show whether DF, RT, G	R, etc.)	12. COUNTY OR PARISH DUCHESNE	13. STATE UT
16. Check Appropriate Box To Indicate Nature of No	1		
NOTICE OF INTENTION TO:	SUBSEC	DUENT REPORT OF:	
TEST WAYER SHIT-OFF PULL OR ALTER CASING	WATER SHUT-OFF	REPAIRING WELL	
FRACTURE TREAT MULTIPLE COMPLETE	FRACTURE TREATMENT	ALTERING CASING	
SHOOT OR ACIDIZE ABANDON°	SHOOTING OR ACIDIZING	ABANDONMENT*	
REPAIR WELL	(OTHER)	X 5 Year MIT	
(OTHER)	' '	ults of multiple completion on Well	
17 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertin proposed work. If well is directionally drilled, give subsurface locations and measur			
A 5 year MIT was conducted on the subject well.			
Ingram w/ State DOGM was notified of the inten			
was pressured to 1150 psi w/ no pressure loss charto witness the test. The well is shut in and waitin			
to withess the test. The wen is shut in and waitin	g on permission to m		ECEIVED
10-7/214 10 CT 17/101	Oil, Gas and Mir	ing	007 1 2001
Idilidix <u>CHI</u>	10-15-01 R 1000	JIC JIC	DIVISION OF GAS AND MINING
18 I hereby certify that the foregoing is true and correct  SIGNED HUMA HUSSELL  Kristla Russell	Production Clerk	DATE	10/9/01
cc: BLM			
(This space for Federal or State office use)			· · · · · · · · · · · · · · · · · · ·
APPROVED BYTITLE		DATE	
CONDITIONS OF APPROVAL. IF ANY:			

# Mechanical Integrity Test Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency


/3	ol Program, UIC Direct In treet, Suite 590. Denver,			V
// ( <b>.</b>	ar-Dogn	1	(0   4	<u> </u>
Well Name: Balcon Men Fed 33-8 Field: Beloga Location: 33 Sec: 6 T 9 Operator: Inland Production Last MIT: 11 / 13 / 96 Maximum		/W County:	Doch	State: _ <i>v+</i> _ PSIG
Is this a regularly scheduled test? Initial test for permit? Test after well rework? Well injecting during test? Pre-test casing/tubing annulus pressure:	[ ]Ye [ ]Ye [ <b>∠</b> ]Ye	s [ ] No s [ ] No s [ ] No	-	e: <u>&amp;</u> bpd
MIT DATA TABLE	Test #1	Te	est #2	Test #3
	TUBING PRESSU	RE		
Initial pressure	1800 p	sig	psig	psig
End of test pressure	1800 p	sig	psig	psig
CASING/	TUBING ANNULUS	PRESSURE		· .
0 minutes	/150 p	sig	psig	psig
5 minutes	1150 p	sig	psig	psig
10 minutes	//50 p	sig	psig	psig
15 minutes	<i>1150</i> p	sig	psig	psig
20 minutes	1150 p	sig	psig	psig
25 minutes	<i>1150</i> p	sig	psig	psig
30 minutes	р	sig	psig	psig
minutes	р	sig	psig	psig
		امند	psig	neia
minutes	<b></b>	sig	paig	psig

## MECHACICAL INTEGRITY PRESSURE TEST

·		<del></del>		· .	
		<del></del>			
			·		
			·		
	· · · · · · · · · · · · · · · · · · ·				
<b>A</b>					
ignature of Witness: Lumb Le	Ingra				
gnature of Witness: Ummo Z	Ingra				
ignature of Witness:	Ingra_				
OFFICE USE ONLY - COMPLIANCE FOLL	Ingra_		Date:	ı	ı
OFFICE USE ONLY - COMPLIANCE FOLL Staff Do you agree with the reported test results?			Date:	ı	1
	[ ] YES		Date:	1	1

[ ] Hardcopy Filing

[ ] Data Entry [ ] Compliance Staff [ ] 2<sup>nd</sup> Data Entry



# DIVISION OF OIL, GAS AND MINING UNDERGROUND INJECTION CONTROL PROGRAM PERMIT AMMENDED STATEMENT OF BASIS

**Applicant: Inland Production Company** 

Well	API Number	Location	Unit
Mon. Butte Fed. 3-25	43-013-31605	25-8S-16E	Mon. Butte NE
Mon. Butte Fed. 13-25	43-013-31513	25-8S-16E	Mon. Butte NE
State 14-32	43-013-31039	32-8S-16E	Wells Draw
Federal 44-33B	43-013-31240	33-8S-16E	Wells Draw
Mon. Butte 5-34	43-013-31499	34-8S-16E	Travis
Mon. Federal 9-34	43-013-31407	34-8S-16E	Monument Butte
Federal 23-34B	43-013-31241	34-8S-16E	Wells Draw
Mon. Federal 15-35	43-013-31264	35-8S-16E	Monument Butte
Mon. Federal 1A-35	43-013-31514	35-8S-16E	Monument Butte
MB 3-35-8-16	43-013-30608	35-8S-16E	Monument Butte
Federal 5-35	43-013-30686	35-8S-16E	Monument Butte
MB 13-35-8-16	43-013-30745	35-8S-16E	Monument Butte
MB 1-36-8-16	43-013-30592	36-8S-16E	Monument Butte
MB 13-36-8-16	43-013-30623	36-8S-16E	Monument Butte
State 5-36	43-013-30624	36-8S-16E	Monument Butte
Mon. Federal 12-25	43-047-32526	25-8S-17E	Humpback
Gilsonite St. 13-32	43-013-31403	32-8S-17E	Gilsonite
Odekirk 7-36-8-17	43-047-33078	36-8S-17E	Odekirk Spring
Mon. Federal 42-1J	43-013-31404	01 <b>-</b> 9S-16E	Jonah
Federal 41-5G	43-013-31205	05-9S-16 <del>E</del>	Wells Draw
Castle Peak Fed. 43-5	43-013-30858	05 <b>-</b> 9S-16E	Wells Draw
Allen Fed. 1-5A	43-013-15780	05-9S-17E	Jonah
Mon. Fed. 24-6	43-013-31363	06-9S-17E	Jonah
Allen Fed. 1-6	43-013-15779	06-9S-17E	Jonah
Mon. Fed. 33-8	43-013-31427	08-9S-17E	Beluga

The wells listed above are all currently permitted Class II injection wells in the Monument Butte Secondary Recovery area. The wells are located in various secondary recovery units as shown above. Inland has requested approval to open additional perforations in these injection wells. Some of the requested perforations are above existing perforations, some are in the existing perforated interval and some are below the existing perforations. All requested perforations are within the Green River Formation which is the unitized interval for all of the Monument Butte area secondary recovery units. Cement Bond Logs were checked on all wells requesting additional perforations above the original permitted perforations. All wells have adequate

cement above the requested intervals. These requemodifications and approval is recommended.	ests by Inland are being treated as minor permit
Reviewer(s): Brad Hill	Date03/20/2003



### United States Department of the Interior



BUREAU OF LAND MANAGEMENT
Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
http://www.blm.gov

IN REPLY REFER TO: 3106 (UT-924)

September 16, 2004

Memorandum

To:

Vernal Field Office

From:

Acting Chief, Branch of Fluid Minerals

Subject:

Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Milas Lloutars

Michael Coulthard Acting Chief, Branch of Fluid Minerals

#### Enclosure

1. State of Texas Certificate of Registration

cc:

MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225 State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114

Teresa Thompson Joe Incardine

Connie Seare

1 15

			•		
UTSL-	15855	61052	73088	76561	-
071572A	16535	62848	73089	76787	
065914	16539	63073B	73520A	76808	
	16544	63073D	74108	76813	
	17036	63073E	74805	76954	
	17424	63073O	74806	76956	
	18048	64917	74807	77233 .	
UTU-	18399	64379	74808	77234	
	19267	64380	74389	77235	•
02458	26026A	64381	74390	77337	
03563	30096	64805	74391	77338	
03563A	30103	64806	74392	77339	
04493	31260	64917	74393	77357	
05843	33992	65207	74398	77359	
07978	34173	65210	74399	77365	
09803	34346	65635	74400	77369	
017439B	36442	65967	74404	77370	
017985	36846	65969	74405	77546	
017991	38411	65970	74406	77553·	
017992	38428	66184	74411	77554	
018073	38429	66185	74805	78022	
019222	38431	66191	74806	79013·	
020252	39713	67168	74826	79014	
020252A	39714	67170	74827	79015	
020254	40026	67208	74835	79016	
020255	40652	67549	74868	79017	
020309D	40894	67586	74869	79831	
022684A	41377	67845	74870	79832	
027345	44210	68105	74872	79833 <sup>,</sup>	
034217A	44426	68548	74970	79831	
035521	44430	68618	75036	79834	
035521A	45431	69060	75037	80450	
038797	47171	69061	75038	80915	
058149	49092	69744	75039	81000	
063597A	49430	70821	75075		
075174	49950	72103	75078		
096547	50376	72104	75089		
096550	50385	72105	75090		
•	50376	72106	75234		
40#20	50750	72107	75238	. •	
10760	51081	72108	76239		
11385	52013	73086	76240		
13905	52018	73087	76241		
15392	58546	73807	76560	•	
			•		

63073X 63098A 68528A 72086A 72613A 73520X 74477X 75023X 76189X 76331X 76788X 77098X 77107X 77236X 77376X 78560X 79485X 79641X 80207X 81307X

Corporations Section P.O.Box 13697 Austin, Texas 78711-3697



Geoffrey S. Connor Secretary of State

#### Office of the Secretary of State

The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company Filing Number: 41530400

**Articles of Amendment** 

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004





Secretary of State

# ARTICLES OF AMENDMENT TO THE ARTICLES OF INCORPORATION OF INLAND PRODUCTION COMPANY

In the Office of the Secretary of State of Texas

SEP 02 2004

Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

#### ARTICLE 1 - Name

The name of the corporation is Inland Production Company.

#### ARTICLE 2 - Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE - The name of the corporation is Newfield Production Company."

ARTICLE 3 - Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1<sup>st</sup> day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs, Treasurer



# STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

UIC FORM 5

Vell Namo an	TRANSFER OF A	UTHORITY TO	NJECT
-cc AIMCI	d Number ed List		API Number
ocation of We		·	Field or Unit Name
Footage :		County ;	See Attached List
QQ, Section	n, Township, Range:	State: UTAH	Lease Designation and Number
FFECTIVE	DATE OF TRANSFER: 9/1/2004		
URRENT O	PERATOR		
Company:	Inland Production Company	Name;	Brian Harris
Address:	1401 17th Street Suite 1000	Signature:	Bro Jan
	city Denver state Co zip 80202	Title:	Engineering Tech.
Phone:	(303) 893-0102	Date:	9/15/2004
Comments	÷		
W OPERA	TOR		
Company:	Newfield Production Company	Name;	Brian Harris
	1401 17th Street Suite 1000	•	(X) > //
	TION THE CHIEF COLLE	Cianatura	
		Signature:	7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7
Address:	city Denver state Co zip 80202	Tîtle:	Engineering Tech.
Address: Phone:		Title:	7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7
Address: Phone:		Tîtle:	Engineering Tech.
Address: Phone: Comments:		Tîtle:	Engineering Tech.
Address:		Tîtle:	Engineering Tech.
Address:  Phone:  Comments:	city Denver state Co zip 80202	Tîtle:	Engineering Tech.
Address:  Phone:  Comments:	state Co zip 80202	Title: _ _ Date:	Engineering Tech. 9/15/2004
Address: Phone: Comments:	state Co zip 80202	Title: _ _ Date:	Engineering Tech.
Address: Phone: Comments: epace for St	state Co zip 80202  state use only)  proved by:  Title: Feeth Services Villances	Title: Date: Approval Date	Engineering Tebh. 9/15/2004  1e: 9-20-84
Address: Phone: Comments: Space for St	state Co zip 80202  state use only)  proved by:  Title: Feeth Services Villances	Title: Date: Approval Date	Engineering Tebh. 9/15/2004  1e: 9-20-84
Address: Phone: Comments: space for St	state Co zip 80202	Title: Date: Approval Date	Engineering Tech. 9/15/2004  1e: 9-20-84
Address: Phone: Comments: space for St	state Co zip 80202  state use only)  proved by:  Title: Feeth Services Villances	Title: Date: Approval Date	Engineering Tebh. 9/15/2004  1e: 9-20-84

(5/2000)

SEP 2 0 2004

Division of Oil, Gas and Mining

#### **OPERATOR CHANGE WORKSHEET**

ROUTING 1. GLH

1. GLH 2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

#### X Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:		9/1/2004
FROM: (Old Operator):	TO: ( New Opera	ator):
N5160-Inland Production Company	N2695-Newfield I	Production Company
Route 3 Box 3630	Route 3 Bo	ox 3630
Myton, UT 84052	Myton, UT	84052
Phone: 1-(435) 646-3721	Phone: 1-(435) 64	6-3721
CA No.	Unit:	BELUGA (GREEN RIVER)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
MONUMENT FED 43-7	07	090S	170E	4301331432	11880	Federal	ow	P
BELUGA 15-7-9-17	07	090S	170E	4301331579	11880	Federal	OW	P
BELUGA 10-7-9-17	07	090S	170E	4301332048	11880	Federal	WI	A
BELUGA 14-7-9-17	07	090S	170E	4301332049	11880	Federal	WI	A
MON FED 33-8	08	090S	170E	4301331427	11880	Federal	WI	A
MON ST 23-16-9-17B	16	090S	170E	4301331578	11880	State	ow	P
MON ST 13-16-9-17B	16	090S	170E	4301331580	11880	State	WI	A
MON FED 31-17	17	090S	170E	4301331428	11880	Federal	WI	A
MON FED 22-17	17	090S	170E	4301331429	11880	Federal	WI	A
BALCRON MON FED 12-17	17	090S	170E	4301331431	11880	Federal	OW	P
MONUMENT FED 32-17	17	090S	170E	4301331465	11880	Federal	OW	P
MONUMENT FED 41-17	17	090S	170E	4301331466	11880	Federal	OW	P
BALCRON MON FED 42-17	17	090S	170E	4301331467	11880	Federal	WI	A
MON FED 33-17-9-17B	17	090S	170E	4301331581	11880	Federal	WI	A
MON FED 23-17-9-17B	17	090S	170E	4301331582	11880	Federal	OW	P
BELUGA 3-18-9-17	18	090S	170E	4301332050	11880	Federal	OW	P
BELUGA 7-18-9-17	18	090S	170E	4301332051	11880	Federal	OW	TA
BELUGA 8-18-9-17	18	090S	170E	4301332052	11880	Federal	WI	A
BELUGA 9-18-9-17	18	090S	170E	4301332053	11880	Federal	OW	P
BELUGA U 4-18-9-17	18	0908	170E	4301332274	11880	Federal	OW	P

#### **OPERATOR CHANGES DOCUMENTATION**

Enter date after each listed item is completed

(R649-8-10) Sundry or legal documentation was received from the FORMER operator on: 9/15/2004
 (R649-8-10) Sundry or legal documentation was received from the NEW operator on: 9/15/2004

3. The new company was checked on the Department of Commerce, Division of Corporations Database on: 2/23/2005

4. Is the new operator registered in the State of Utah: YES Business Number: 755627-0143

5. If NO, the operator was contacted contacted on:

6a. (R649-9-2)Waste Management Plan has been received on:	IN PLACE
6b. Inspections of LA PA state/fee well sites complete on:	waived
7. Federal and Indian Lease Wells: The BLM and o	or the BIA has approved the merger, name change,
or operator change for all wells listed on Federal or Indian	
O Federal and Indian United	
8. Federal and Indian Units: The BLM or BIA has approved the successor of unit open	rator for wells listed on:
The second secon	
9. Federal and Indian Communization Agreeme	· · · · ·
The BLM or BIA has approved the operator for all wells	listed within a CA on: na/
10. C	The Division has approved UIC Form 5, Transfer of Authority to
Inject, for the enhanced/secondary recovery unit/project for	or the water disposal well(s) listed on: $2/23/2005$
	· .
DATA ENTRY:	
1. Changes entered in the Oil and Gas Database on:	2/28/2005
2. Changes have been entered on the Monthly Operator Cha	ange Spread Sheet on: 2/28/2005
3. Bond information entered in RBDMS on:	2/28/2005
4. Fee/State wells attached to bond in RBDMS on:	2/28/2005
5. Injection Projects to new operator in RBDMS on:	2/28/2005
6. Receipt of Acceptance of Drilling Procedures for APD/Nev	w on: waived
FEDERAL WELL(S) BOND VERIFICATION:	
1. Federal well(s) covered by Bond Number:	UT 0056
INDIAN WELL(S) BOND VERIFICATION:	
1. Indian well(s) covered by Bond Number:	61BSBDH2912
FEE & STATE WELL(S) BOND VERIFICATIO	
1. (R649-3-1) The NEW operator of any fee well(s) listed cov	vered by Bond Number 61BSBDH2919
2. The FORMER operator has requested a release of liability f	from their bond on:n/a*
The Division sent response by letter on:	n/a
LEASE INTEREST OWNER NOTIFICATION:	
3. (R649-2-10) The FORMER operator of the fee wells has be	· · · · · · · · · · · · · · · · · · ·
of their responsibility to notify all interest owners of this cha	ange on:n/a
COMMENTS:	
*Bond rider changed operator name from Inland Production Con	mpany to Newfield Production Company - received 2/23/05

STATE OF UTAH

#### DEPARTMENT OF NATURAL RESOURCES 5. LEASE DESIGNATION AND SERIAL NUMBER; DIVISION OF OIL, GAS AND MINING UTU74108 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: SUNDRY NOTICES AND REPORTS ON WELLS 7. UNIT or CA AGREEMENT NAME: o not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, BELUGA UNIT to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. 8. WELL NAME and NUMBER: 1. TYPE OF WELL: Injection well OIL WELL GAS WELL OTHER **MON FED 33-8** 9. API NUMBER: 2. NAME OF OPERATOR: Newfield Production Company 4301331427 3. ADDRESS OF OPERATOR: PHONE NUMBER 10. FIELD AND POOL, OR WILDCAT: STATE UT 435.646.3721 Route 3 Box 3630 ZIP 84052 Monument Butte CITY Myton 4. LOCATION OF WELL: FOOTAGES AT SURFACE: 1980 FSL 1980 FEL COUNTY: Duchesne Utah STATE: OTR/OTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NW/SE, 8, T9S, R17E CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA TYPE OF ACTION SubDate TYPE OF ACTION TYPE OF SUBMISSION ACIDIZE DEEPEN REPERFORATE CURRENT FORMATION NOTICE OF INTENT ALTER CASING FRACTURE TREAT SIDETRACK TO REPAIR WELL (Submit in Duplicate) NEW CONSTRUCTION CASING REPAIR TEMPORARITLY ABANDON Approximate date work will CHANGE TO PREVIOUS PLANS OPERATOR CHANGE TUBING REPAIR CHANGE TUBING PLUG AND ABANDON VENT OR FLAIR CHANGE WELL NAME PLUG BACK WATER DISPOSAL SUBSEQUENT REPORT (Submit Original Form Only) PRODUCTION (START/STOP) WATER SHUT-OFF CHANGE WELL STATUS Date of Work Completion COMMINGLE PRODUCING FORMATIONS OTHER: -RECLAMATION OF WELL SITE 09/12/2005 CONVERT WELL TYPE X RECOMPLETE - DIFFERENT FORMATION 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The subject well was recompleted in the Green River Formation. Four new intervals were perferated. The A3 sds @ 5074-5080'; A1 sds @ 5024-5030', 5010-5016', B2 sds @ 4898-4904', DS3 sds @ 4522-4534 & PB10 sds @ 4312-4320' all with 4 JSPF for a total of 176 shots. On 9-6-05 Nathan Wisner with the EPA was contacted concerning the MIT on the above listed well. Permission was given at that time to perform the test on 9-7-05. On 9-7-05 the csg was pressured up to 1100 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tbg pressure was 1500 psig during the test. There was not an EPA representative available to witness the test. Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY TITLE Office Manager Kathy Chapman NAME (PLEASE PRINT) DATE\_09/12/2005

(This space for State use only)

SIGNATURE

FORM 3160-5 (September 2001)

### UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM A	PPROVED
OMB No.	1004-0135
Expires Janu	uary 31.2004

Lease Serial No.

SUNDRY NOTICES AND REPORTS Of Do not use this form for proposals to drill or	UTU74108 ,		
abandoned well. Use Form 3160-3 (APD) for s	uch proposals.	6. If Indian, Allottee or Tribe Name.	
SUBMIT IN TRIPLICATE - Other Instruction  1. Type of Well	s on reverse side	7. If Unit or CA/Agreement, Name and/or No. BELUGA UNIT	
☐ Oil Well ☐ Gas Well ☐ Other Injection well		8. Weil Name and No.	
Name of Operator     Newfield Production Company		MON FED 33-8	
	ne No. (include are code)	9. API Well No. 4301331427	
Myton, UT 84052 435.646	.3721	10. Field and Pool, or Exploratory Area  Monument Butte	
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 1980 FSL 1980 FEL		11. County or Parish, State	
NW/SE Section 8 T9S R17E		Duchesne, UT	
12. CHECK APPROPRIATE BOX(ES) TO I	NIDICATE NATURE OF N	NOTICE, OR OTHER DATA	
TYPE OF SUBMISSION	TYPE OF ACTION	N	
Notice of Intent  Alter Casing  Fra  Subsequent Report  Casing Repair  Net	cture Treat Reclama w Construction Recomp	<b>—</b> · · · · · · · · · · · · · · · · · · ·	
The transfer of the control of the c	g & Abandon	· — — — — — — — — — — — — — — — — — — —	
The subject well was recompleted in the Green River Formation 5074-5080; A1 sds @ 5024-5030', 5010-5016', B2 sds @ 48 with 4 JSPF for a total of 176 shots. On 9-6-05 Nathan Wisnellisted well. Permission was given at that time to perform the transport and charted for 30 minutes with no pressure loss. The well with during the test. There was not an EPA representative available.	98-4904', DS3 sds @ 4522- r with the EPA was contacte est on 9-7-05. On 9-7-05 th as not injecting during the te	4534 & PB10 sds @ 4312-4320' all ed concerning the MIT on the above ne csg was pressured up to 1100 psig	
I hereby certify that the foregoing is true and correct Name (Printed Typed) Kathy Chapman	Title Office Manager		
Signature State Mason	Date 00/12/2005		
	09/12/2005 ERAL OR STATE OFFIC	CE USE	
Amazoued bu	Title	Date	
Approved by  Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	1240	
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any processes any false, fictitious and fraudulent statements or representations as to any matter with the control of	erson knowingly and willfully to make the thin its jurisdiction	to any department or agency of the United	

	Form	Approved. O	MB No 2000-00					TECTIC	ON AGENCY					
SE	and the same training		UNI		HINGTO	ON, DC 2	204	60						
NAME AND ADD Newfield Pro 410 17th Stre Denver, Colo	et, Suite 700	npany )		***************************************		N	ΑM		DRESS OF CONTRACTOR				,	
	WELLAND OUT	- 153D694518D	Company of the second s	Itah	COUNTY			Duc	hesne	PE	RMIT NU	IMBER	Ų-	74108
SEC	TION PLAT — 6 <sup>2</sup> N	40 ACRES		CE LOCATION  'A OF	1	√W %		F890133000099-00030030399-	SECTION 8	Self-walk				17
			Su Su	rface cation	980		rom	n (N/S)	S Line of Quarter section					
<b>w</b>			E	WELL AC Brine Disposal Enhanced Rec			L		Before Rework 5700 After Rework				E OF PER	MIT
				Hydrocarbon S e Name	Storage		D		57.00 k Commenced 8/1/2005	7	mber of V Il Numbe	_	1	
	. J.			M	lonumei	nt Feder			k Completed 8/4/2005			3	3-8-9-1	7
								BEFOR	RE REWORK					
Cas Size	ing Depth	Ce Sacks	ment Type	From	erforations	To	_	ł			or Fractur ent Reco			
8:5/8"	262	150	Class G	5444		5463		Perf an	d fraced					
5 1/2	:5682	132	Thrify lite	-4656		4662		Pref an	d fraced					Park Land
1.0		257	50/50 POZ	-4104	Activity and American	4144		Perf an	d fraced	4, 7,				
		WELL	CASING R	ECORD	AFTE	R REW	0	RK (Indi	icate Additions and Cha	anges	Only)			
Cas	ing		ment	T	erforations					_	or Fractur	е		
Size	Depth	Sacks	Туре	From		То		Treatment Record						
		-14		5010		5080			3 & S1 and fraced					
				4898		4904	_		2 and fraced					
				4522 4312	<del></del>	4534 4320			S3 and fraced 310 and fraced					
			<u> </u>	7312		4320	_	10111	o and maced					
	DESCRIE	BE REWORK OF	PERATIONS IN DE	TAIL	_			<u> </u>	WIRE LINE I	.OGS, L	IST EAC	H TYPE		
			ETS IF NECESSA						Log Types	T			ged Interv	als
				See atta	iched "l	Daily W	or	kover R	leport"			,	,	
							Ц	<b></b>	<b></b>	-			<u> </u>	
			<u></u>				<u> </u>		<u> </u>		<u> </u>		Ь	l
in this docume for obtaining th	nt and all att e information,	achments and I believe tha	d that, based of the the information	on my inquir on is true, ac	d am fan y of thos ccurate,	se indivionant	h th dua ple	ne inform als imme ete. I am	nation submitted diately responsible aware that there conment. (Ref. 40 CFF	R 144.3	32)			
NAME AND OFFI	CIAL TITLE (Diag	se type or print		CICNATURE						D.A.	TE CICNI	En		
Kathy Chapm	an	ae type or print)		SIGNATURE	an	f L	4	hus	m	DA	TE SIGN		nber 13	, 2005
Office Manag EPA Form 7520-12					-6		_							

# Mechanical Integrity Test Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency Underground Injection Control Program 999 18th Street, Suite 500 Denver, CO 80202-2466


EPA Witness:			Date:	9102	105	
Test conducted by:	Horrocks				<del></del>	
Others present:		· · · · · · · · · · · · · · · · · · ·			<del></del>	
				<b>—</b>	A C. T.L. TIC	
Well Name: Balcron M	onument Fed	33-8-9-17	Type: ER SV	VD Statu	is: AC TA UC	
Field: <u>Beluga</u> Location: <u>NW/ SE</u> Sec:	Q T Q 1	_ J 🔗 D / 🔿	A/W Count		a State:	
		NON KIZ	CE/W Count	y. Duckesn	<u> </u>	_
Operator: <u>New Fe le</u> Last MIT:/		imim Allows	able Pressure:	1855	PSIG	*
Last Mill.	/ IVIAX	unum Anowe	ibic i ressure.	ررن،		<del></del> .
Is this a regularly scheduled	l test? [ ]	Yes [x	l No	•		
•	[ ]					
Test after well rework?	[x]	Yes [	] No		•	
Well injecting during test?		Yes [x	] No If Yo	es, rate:	bp	d
		^		سننم		
Pre-test casing/tubing annulu	s pressure:			psig		
MIT DATA TABLE	Test #1		Test #2		Test #3	
TUBING	PRESSURE		1 CSL #Z		1000 110	
Initial Pressure		psig		psig		psig
End of test pressure	500	psig		psig		psig
CASING / TUBING	<u> 500</u> ANNULUS		PRESSURE	<u> </u>	<del></del>	
0 minutes	1340	psig		psig		psig
5 minutes	1340	psig		psig		psig
10 minutes	1340	psig		psig	To the second se	psig
15 minutes	1340	psig		psig		psig
20 minutes	1340	psig		psig	·	psig
25 minutes	1340	psig	·	psig		psig
30 minutes		psig		psig		psig
minutes	1340	psig	-	psig		psig
minutes		psig		psig		psig
RESULT	[X] Pass	[ ]Fail	[ ] Pass	[ ]Fail	[ ] Pass [	]Fail

Does the annulus pressure build back up after the test? [ ] Yes [X] No

### MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness:	
Signature of Withess.	



#### STATE OF UTAH

	5. LEASE DESIGNATION AND SERIAL NUMBER: USA UTU-74108			
SUNDRY	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
Do not use this form for proposals to dri	7. UNIT OF CA AGREEMENT NAME: BELUGA UNIT			
1. TYPE OF WELL: OIL WELL	8. WELL NAME and NUMBER: MON FED 33-8			
2. NAME OF OPERATOR:				9. API NUMBER:
NEWFIELD PRODUCTION COM	IPANY			4301331427
3. ADDRESS OF OPERATOR:			PHONE NUMBER	10. FIELD AND POOL, OR WILDCAT:
Route 3 Box 3630 CIT	ry Myton state UT	ZIP 84052	435.646.3721	MONUMENT BUTTE
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 1980 FSL 1	980 FEL			COUNTY: DUCHESNE
OTR/OTR. SECTION. TOWNSHIP. RANGE.	MERIDIAN: NWSE, 8, T9S, R17E			STATE: UT
11. CHECK APPROF	PRIATE BOXES TO INDICATI	E NATURE (	OF NOTICE, REP	ORT, OR OTHER DATA
TYPE OF SUBMISSION		TY	PE OF ACTION	
<b>—</b>	ACIDIZE	DEEPEN		REPERFORATE CURRENT FORMATION
NOTICE OF INTENT (Submit in Duplicate)	ALTER CASING	FRACTURE T	REAT	SIDETRACK TO REPAIR WELL
•	CASING REPAIR	NEW CONSTI		TEMPORARITLY ABANDON
Approximate date work will	1=	OPERATOR C		=
	CHANGE TO PREVIOUS PLANS	=		TUBING REPAIR
	CHANGE TUBING	PLUG AND A	BANDON	VENT OR FLAIR
SUBSEOUENT REPORT (Submit Original Form Only)	CHANGE WELL NAME	PLUG BACK		WATER DISPOSAL
	CHANGE WELL STATUS	PRODUCTION	N (START/STOP)	WATER SHUT-OFF
Date of Work Completion:	COMMINGLE PRODUCING FORMATIONS	RECLAMATI	ON OF WELL SITE	OTHER: -
09/12/2005	CONVERT WELL TYPE	X RECOMPLET	E - DIFFERENT FORMATION	<u> </u>
12. DESCRIBE PROPOSED OR CO	MPLETED OPERATIONS. Clearly show a	all pertinent details	including dates, depths,	volumes, etc.
sds @ 5024-5030', 5010-50 176 shots. On 9-6-05 Natha at that time to perform the t	016', B2 sds @ 4898-4904', DS3 sd an Wisner with the EPA was contac test on 9-7-05. On 9-7-05 the csg w as not injecting during the test. The t	s @ 4522-4534 ted concerning vas pressured ι	4 & PB10 sds @ 43 the MIT on the abo up to 1100 psig and	
NAME (PLEASE PRINT) Kathy Chapman	n		TITLE Office Manager	
SIGNATURE	cething I hup	<u> </u>	DATE 09/12/2005	

(This space for State use only)

RECEIVED FEB 1 1 2008

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES 5. LEASE DESIGNATION AND SERIAL NUMBER: DIVISION OF OIL, GAS AND MINING USA UTU-74108 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: SUNDRY NOTICES AND REPORTS ON WELLS 7. UNIT or CA AGREEMENT NAME: Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged **GMBU** wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. 8. WELL NAME and NUMBER: 1 TYPE OF WELL: OIL WELL GAS WELL OTHER **MON FED 33-8** 9. API NUMBER: 2. NAME OF OPERATOR 4301331427 NEWFIELD PRODUCTION COMPANY 10. FIELD AND POOL, OR WILDCAT: PHONE NUMBER 3. ADDRESS OF OPERATOR: STATE UT 435.646.3721 GREATER MB UNIT ZIP 84052 CITY Myton Route 3 Box 3630 4. LOCATION OF WELL: COUNTY: DUCHESNE FOOTAGES AT SURFACE: 1980 FSL 1980 FEL STATE: UT OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: NWSE, 8, T9S, R17E CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA TYPE OF ACTION TYPE OF SUBMISSION REPERFORATE CURRENT FORMATION DEEPEN ACIDIZE NOTICE OF INTENT FRACTURE TREAT SIDETRACK TO REPAIR WELL ALTER CASING (Submit in Duplicate) NEW CONSTRUCTION TEMPORARITLY ABANDON CASING REPAIR Approximate date work will TUBING REPAIR OPERATOR CHANGE CHANGE TO PREVIOUS PLANS VENT OR FLAIR PLUG AND ABANDON CHANGE TUBING WATER DISPOSAL PLUG BACK CHANGE WELL NAME X SUBSEQUENT REPORT (Submit Original Form Only) WATER SHUT-OFF PRODUCTION (START/STOP) CHANGE WELL STATUS Date of Work Completion: COMMINGLE PRODUCING FORMATIONS X OTHER: - Five Year MIT RECLAMATION OF WELL SITE 08/05/2010 RECOMPLETE - DIFFERENT FORMATION CONVERT WELL TYPE 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. On 07/26/2010 Nathan Wiser with the EPA was contacted concerning the 5 year MIT on the above listed well. On 08/05/2010 the casing was pressured up to 1490 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 1720 psig during the test. There was not an EPA representative available to witness the test. EPA# UT20798-04307 API# 43-013-31427 Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY

NAME (PLEASE PRINT) Lucy Chavez-Naupoto TITLE Administrative Assistant

SIGNATURE DATE 08/06/2010

(This space for State use only)

The state of the s

AUG 1 1 2010

The Mark Committee of the Committee of t

### Mechanical Integrity Test Casing or Annulus Pressure Mechanical Integrity Test U.S. Environmental Protection Agency Underground Injection Control Program

999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness:  Test conducted by: Scott Others present:			Date:	\$ 15	110	
Well Name: Monument Ru Field: MONUMENT Ru Location: 33-8-9-17 Sec Operator: NEWFIELD Last MIT: /  Is this a regularly schedule Initial test for permit? Test after well rework?	of TE  :	imum Allow Yes [ Yes [ Yes [	able Pressure: 1  No No No	Dur <i>he</i> sno 855	PSIG	pd
Well injecting during test?  Pre-test casing/tubing annulu			] No If Yes,	rate:		
MIT DATA TABLE	Test #1		Test #2		Test #:	3
TUBING	PRESSURE					
Initial Pressure	1720	psig		psig		psig
End of test pressure	1720	psig		psig		psig
CASING / TUBING	ANNULUS		PRESSURE			
0 minutes	1490	psig		psig		psig
5 minutes	1490	psig		psig		psig
10 minutes	1490	psig		psig		psig
15 minutes	1490	psig		psig	· .	psig
20 minutes	1490	psig		psig		psig
25 minutes	1490	psig		psig		psig
30 minutes	1490	psig	·	psig		psig
minutes	17 10	psig		psig		psig
minutes		psig		psig		psig
RESULT	[X] Pass	[ ]Fail	[ ] Pass	[ ]Fail	[ ] Pass	[ ]Fail

Does the annulus pressure build back up after the test? [ ] Yes

### MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness:	•	
Organical Contract Co		

Sundry Number: 64477 API Well Number: 43013314270000

	STATE OF UTAH		FORM 9
ı	DEPARTMENT OF NATURAL RESOURCE DIVISION OF OIL, GAS, AND MINI		5.LEASE DESIGNATION AND SERIAL NUMBER: UTU-7978
SUNDR	RY NOTICES AND REPORTS O	N WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	posals to drill new wells, significantly d reenter plugged wells, or to drill horizont n for such proposals.		7.UNIT or CA AGREEMENT NAME: GMBU (GRRV)
1. TYPE OF WELL Water Injection Well			8. WELL NAME and NUMBER: MON FED 33-8
2. NAME OF OPERATOR: NEWFIELD PRODUCTION CO	DMPANY		<b>9. API NUMBER:</b> 43013314270000
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT		PHONE NUMBER: Ext	9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1980 FSL 1980 FEL			COUNTY: DUCHESNE
QTR/QTR, SECTION, TOWNSH	<b>HIP, RANGE, MERIDIAN:</b> 08 Township: 09.0S Range: 17.0E Meridia	an: S	STATE: UTAH
11. CHECI	K APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
Approximate date work will start.	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN [	FRACTURE TREAT	NEW CONSTRUCTION
6/30/2015	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
SPUD REPORT Date of Spud:	<u></u>	7	
	L REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	LI TEMPORARY ABANDON
DRILLING REPORT	L TUBING REPAIR	UVENT OR FLARE	WATER DISPOSAL
Report Date:	WATER SHUTOFF L	SI TA STATUS EXTENSION	APD EXTENSION
	WILDCAT WELL DETERMINATION	OTHER	OTHER: 5 YR MIT
5 YR MIT perforr casing was pressur no pressure loss. pressure was 1	COMPLETED OPERATIONS. Clearly show all med on the above listed well. ed up to 1151 psig and chart The well was not injecting du 630 psig during the test. Ther vailable to witness the test. El	On 06/30/2015 the ed for 30 minutes with ring the test. The tbg e was not an EPA	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY July 08, 2015
NAME (PLEASE PRINT) Lucy Chavez-Naupoto	<b>PHONE NUMBE</b> 435 646-4874	R TITLE Water Services Technician	
SIGNATURE N/A		<b>DATE</b> 7/1/2015	

Sundry Number: 64477 API Well Number: 43013314270000

## Mechanical Integrity Test Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency Underground Injection Control Program 999 18th Street, Suite 500 Denver, CO 80202-2466


EPA Witness:			Date: _	6 130	115					
Test conducted by: John of Dancels  Others present:										
Onicis present.					······································	N				
Well Name: Monnment Fed. 33-8-9-17 Type: ER SWD Status: AC TA UC Field: GimBin										
Location: NW/SE Sec: 8 T 9 N/S R 17 E/W County: Dicheshe State: 41										
Operator: NF										
Last MIT: /	/ Ma	ximum Allow	able Pressure: _	17127	P	SIG				
	10									
Is this a regularly schedule Initial test for permit?		] Yes [ ] Yes [	] No ] No							
Test after well rework?	-	-	] No							
Well injecting during test?			No If Ye	s, rate:		bpd				
Pre-test casing/tubing annul	IC Transier					<b>1</b>				
Tie-test casing woning aimini	as pressure			psig						
MIT DATA TABLE	Test #1		Test #2		Tes	1 #3				
TUBING	PRESSURE	1								
Initial Pressure	1630	psig		psig		psig				
End of test pressure	1630	psig		psig		psig				
CASING / TUBING	ANNULUS	2007	PRESSURE	multiment of the second	37000					
0 minutes	1151	psig		psig	and the second s	psig				
5 minutes	1150	psig	<del></del>	psig		psig				
10 minutes	1151	psig		psig		psig				
15 minutes	1151	psig		psig	1-11-1-11-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-	psig				
20 minutes	1151	psig		psig		psig				
25 minutes	1151	psig		psig		psig				
30 minutes	1151	psig		psig	****	psig				
minutes		psig		psig		psig				
minutes		psig		psig		psig				
RESULT	N Pass	[ ]Fail	Pass	[ ]Fail	Pass	Fail				
		T. S.	T 49		The state of the s	12 4414				

Does the annulus pressure build back up after the test? [ ] Yes [ > No MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness:	han Dans	The state of the s
The second section of the sect	3	The second secon

Sundry Number: 64477 API Well Number: 43013314270000




#### Spud Date: 2-14/94 Put on Production: 3/30/94 Put on Injection: 12/1/96

NW SE Section 8-T9S-R17E Duchesne Co, Utah API #43-013-31427; Lease #U-74108

#### Monument Federal 33-8-9-17

Initial Production: 65 BO, 200 MCF, 0 BWPD.





WELL NAME: BALCRON MONUMENT FEDERAL #33-8

FIELD: Monument Butte Field (Beluga Unit)

FEDERAL LEASE NO.: U-7978

LOCATION: NW SE Section 8, T9S, R17E

FOOTAGE: 1980' FSL, 1980' FEL COUNTY/STATE: Duchesne County, Utah

WORKING INTEREST: 0.91491728

PRODUCING FORMATION: Green River

**COMPLETION DATE: 3-30-94** INITIAL PRODUCTION: 65 BO, 200 MCF

OIL/GAS PURCHASER: Amoco

PRESENT PROD STATUS: WO Surface Equipment

ELEVATIONS - GROUND: 5,318.6' GL

TOTAL DEPTH: 5,700' KB

**SURFACE CASING** 

STRING: 1

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 6 jts (254.03')

DEPTH LANDED: 262' KB

HOLE SIZE: 12-1/4"

CEMENT DATA: Western - 150 sxs Class "G" +

(2% CCI + 1/4 Ceieflake)per sx.

**TUBING RECORD** 

SIZE/GRADE/WT.: 2-7/8", EUE, J-55, 6.5#

NO. OF JOINTS: 128 jts @ 4049.21'

TUBING ANCHOR: 2-7/8" x 5-1/2" (Trico)

NO. OF JOINTS: 45 jts @ 1410.45' **SEATING NIPPLE: 2-7/8" x 1.10"** 

PERFORATED SUB: 2-7/8" x 3'

MUD ANCHOR: 2 7/8" x 30.52'

TOTAL STRING LENGTH: 5495'

SN LANDED AT: 5473.11' KB

SUCKER ROD RECORD

POLISHED ROD: 1-1/4" x 22' Polish Rod

SUCKER RODS: 1 - 3/4" x 4' Pony

218 - 3/4"x 25' D-61 Rods

**TOTAL ROD STRING LENGTH: 5470.5'** 

PUMP NUMBER: 1041 (Trico)

PUMP SIZE: 2.5"x1.5"x16' RWAC w/PA plunger

STROKE LENGTH: 87"

PUMP SPEED, SPM: 4.5

PUMPING UNIT SIZE: LUFKIN LM-228D-213-86T

PRIME MOVER: AJAX CMA 8-1/2" x 10"

LOGS: IPLT, ALT, MSC

Well was cored on 2-26-94.

DATE: 11/2/95 vk

API NO.: 43-013-31427

NET REVENUE INTEREST: 0.80471769 Oil

0.73108274 Gas

SPUD DATE: 2/14/94 OIL GRAVITY: 34

BHT:

KB: 5,328.6' KB (10' KB)

PLUG BACK TD: 5633.74' KB

**PRODUCTION CASING** 

STRING: 1

CSG SIZE: 5-1/2"

GRADE: K-55

WEIGHT: 15.5 #

LENGTH: 129 jts (5672.25')

DEPTH LANDED: 5681.25' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 132 sxs Thrifty-lite and

tail w/257 sxs 50-50 POZ.

CEMENT TOP AT: 2390' KB

PERFORATION RECORD

3/9/94 4104' - 4116'

(12') 4 SPF **Y3** 

3/9/94 4138' - 4144' Communication between 4104' - (6) 4 SPF

4656' - 4662' 3/7/94

4116' & 4138' - 4144' (6') 4 SPF R2

3/2/94 5444' - 5463' (19') 4 SPF **B**1

**ACID JOB / BREAKDOWN JOB** 

3-3-94: 5444' - 5463'

500 gailons 15% HCL. Bailed

off. ATP 2300 psi, max 4590 psi.

ATR 7 bpm, max-7 bpm, ISIP

1200 psi, rate 13 bpm @ 5000 psi

3-7-94: 4656' - 4662'

500 gals 15% HCL. Good ball action.

ATP-3300 psi, max 5000 psi.

ATR 3.2 bpm, max 3.9 bpm

ISIP 1600 psi, Rate 20 bpm @ 5290 psi

3-9-94: 4104' - 4116'

500 gals 15% HCL. Balled Off.

ATP 2600 psi, max 4950 psi.

ATR 4 bpm, max 4 bpm, ISIP 430 psi

Pump for rate 9.1 bpm @ 2150 psi

3-9-94: 4138' - 4144'

500 gals 15% HCL, No Ball Off.

ATP 1500 psi, max 2600 psi.

ATR 3 bpm, max 8.9 bpm, ISIP 850 psi

Pump for rate 8 bpm @ 2600 psi



11/3/95 vk

WELL DATA SHEET CONTINUED PAGE TWO

#### **FRAC JOB**

3-3-93: 5444' - 5463'

24,500# 20/40 mesh sand & 25,300# 16/30 mesh sand in 5441 gals 2% KCL wtr. Ave pressure 1700 psi, max 2150 psi. Avg rate 26 BPM max 28.1 BPM. ISIP 1650 5 min 1480#, 10 min 1350# 15 min 1240#, run trace isotope.

3-7-94: 4656' - 4662'

18,100# 16/30 mesh sand in 5700 gals 2% KCL wtr. Avg Press 2700 psi, max 3550 psi. Ave Rate 20.2 BPM max 20.5 BPM. ISIP 2150 psi, 5 min 1580 psi, 10 min 1400 psi, 15 min 1340 psi.

3-9-94: 4104' - 4144'

& 4138' - 4144'

52,200# 16/30 mesh sand in 19,830 gals 2% KCL wtr. Avg Press 2500 psi, max 2950 psi. Avg Rate 24.7 BPM, max 25.1 BPM. ISIP 1750 psi, 5 min 1400 psi 10 min-1350, 15 min-1320



ev.GR - 5318.6' GL ev.KB - 5328.6' KB (10' KB)

#### WELLBORE DIAGRAM

DATE: 11/3/95 vk

	i	1 1 1 1 1		ACID JOB /BREAKD	OWN	
CSG SIZE: 8-5/8" GRADE: J-55 WEIGHT: 24#				3-3-94: 5444' - 5463'		
LENGTH: 254.03' (6 jts) DEPTH LANDED: 262' KB HOLE SIZE: 12-1/4" CEMENT DATA: Western - 150 sxs Class "G" + (2% CCI + 1/4 Celeflake)per sx.				3-7-94: 4656' - 4662'	ATP-3300 psi, max 5000 psi. ATR 3.2 bpm, max 3.9 bpm ISIP 1800 psi, Rale 20 bpm 62 529	
DUCTION CASING	262' KB			3-9-94: 4104' - 4116	ATP 2600 psi, max 4950 psi.	
CSG SIZE: 5-1/2"  GRADE: K-55  WEIGHT: 15.5#  LENGTH: 5672.25' (129 jts)  DEPTH LANDED: 5681.25				3-9-94: 4138' - 4144	ATR 4 bpm, max 4 bpm, ISIP 430 p Pump for rate 9.1 bpm @ 2150 psi 500 gals 15% HCL. No Ball Off. ATP 1500 psi, max 2600 psi. ATR 3 bpm, max 6.9 bpm, ISIP 850 Pump for rate 8 bpm @ 2800 psi	
HOLE SIZE: 7-7/8" CEMENT DATA: 132 sxs Thrifty-life and		]		FRAC JOB		
tail w/257 axa 50-50 POZ. CEMENT TOP AT: 2390' KB				3-3-93: 5444' - 5463	24,500# 20/40 mesh sand & 25,300# 16/30 mesh sand In 5441 gals 2% KCL wtr.	
ING			C @ 2390' KB		Ave pressure 1700 psi, max 2150 psi. Avg rate 28 BPM max 28.1 BPM, ISIP 1650	
SIZE/GRADE/NT.: 2-7/8", EUE J-55, 6.5# NO. OF JOINTS: 128 jts @ 4049.21' TUBING ANCHOR: 2-1/2" x 5-1/2" (Trico) NO. OF JOINTS: 45 jts @ 1410.45' SEATING NIPPLE: 2-7/8" x 1.10' PERFORATED SUB: 2-7/8" x 3'				3-7-94: 4656' - 4662'	5 min 1480#, 10 min 1350# 15 min 1240#,run trace isotope.	
MUD ANCHOR: 1 Jt @ 30.52' STRING LENGTH: 5495' SN LANDED AT: 5473.11' KB KER RODS				3-9-94: 4104' - 4144 & 4138' - 4144	max 20.5 BPM. ISIP 2150 psi, 5 min 1580 psi, 10 min 1400 psi, 15 min 1340 psi. 52,200# 16/30 mesh sand	
		1111			2950 psi. Avg Rate 24.7	
POLISHED ROD: 1-1/4" X 22' SUCKER RODS: 1 - 3/4" X 4' PONY 218 - 3/4" X 25' D-61 Rods					BPM, max 25.1 BPM. ISIP 1750 psi, 5 min 1400 psi 10 min-1350, 15 min-1320	
STRING LENGTH: 5471.5'				PERFORATION REC	NORD.	
PUMP NUMBER: 1041 (Trico) PUMP SIZE: 2.5"x1.5"x16" RWAC w/PA plunger	<u> </u>	410	<b>4</b> ' - 16'	3/9/94 4104' - 411 3/9/94 4138' - 414	6' (12') 4 SPF Y3	1
STROKE LENGTH: 87" PUMP SPEED, SPM: 4.5	ţi.ń	413	8' - 44'		een 4104' - 4116' & 4138' - 4144'	2 3 4
PUMPING UNIT: LUFKIN LM-228D-213-86T PRIME MOVER: AJAX CMA 6-1/2" x 10"	i	465	8' - 62'	3/2/94 5444' - 546	3' (19') 4 SPF B1	5
LOGS: IPLT, ALT, MSC						
Well was cored on 2-26-94.						
	ް	544	4' - 63'			
			LANDED @ 547 ( @ 5505' KB	73' KB		
		PBT	D @ 5633.74' H	(B		



Elev.GR - 5318.6' GL Elev.KB - 5328.6' KB (10' KB)

**Proposed Injection Wellbore Diagram** 

DATE: 3/22/96 JZ

#### **SURFACE CASING**

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 254.03' (6 jts)
DEPTH LANDED: 262' KB
HOLE SIZE: 12-1/4"

CEMENT DATA: Western - 150 sxs Class "G" +

(2% CCl + 1/4 Celeflake)per sx.

262' KB

#### PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: K-55

WEIGHT: 15.5#

LENGTH: 5672.25' (129 jts)

DEPTH LANDED: 5682.25' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 132 sxs Thrifty-lite and

tail w/257 sxs 50-50 POZ.

CEMENT TOP AT: 2390' KB

#### TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 4034'
SEATING NIPPLE: 2-7/8" X 1.1'
ARROW SET 1 PACKER: 5-1/2" X 4'
PACKER SET AT: 4044' KB

Uinta Formation Surface to 1450 ft.

TOC @ 2390' KB

#### PERFORATION RECORD

 3/9/94
 4104' - 4116'
 (12')
 4 SPF
 Y3

 3/9/94
 4138' - 4144'
 (6')
 4 SPF
 Y3

 Communication between 4104' - 4116'
 4 138' - 4144'

 3/7/94
 4656' - 4662'
 (6')
 4 SPF
 R2

 3/2/94
 5444' - 5463'
 (19')
 4 SPF
 B1

Green River Formation 1450 to 5400 ft.

ARROW SET-1 PACKER SET @ 4044' KB

4104' - 16'

4138' - 44'

15

響

4656' - 62'

5444' - 63'

Douglas Creek Member 4550 to 5400 ft. Wasatch Fm. Transition 5400 to 5950 ft.

PBTD @ 5633,74' KB TD @ 5700' KB

Wasatch Formation 5950 ft.



Elev.GR - 5318.6' GL Elev.KB - 5328.6' KB (10' KB)

#### Proposed Plugging & Abandonment Diagram

DATE: 3/22/96 JZ


#### **SURFACE CASING**

CSG SIZE: 8-5/8" GRADE: J-55 WEIGHT: 24# LENGTH: 254.03' (6 jts) DEPTH LANDED: 262' KB HOLE SIZE: 12-1/4"

CEMENT DATA: Western - 150 sxs Class "G" +

(2% CCI + 1/4 Celeflake)per sx.

262' KB



Plug No.2 Surface to 362 ft. Perforate csg at 100 ft below the surface csg shoe & circulate 100 sx of Class-G Cement

Permanent P&A marker w/ identifying well information.

#### **PRODUCTION CASING**

CSG SIZE: 5-1/2" GRADE: K-55 WEIGHT: 15.5# LENGTH: 5672.25' (129 jts)

DEPTH LANDED: 5682.25' KB HOLE SIZE: 7-7/8"

CEMENT DATA: 132 sxs Thrifty-lite and

tail w/257 sxs 50-50 POZ.

CEMENT TOP AT: 2390' KB

Uinta Formation Surface to 1450 ft.

TOC @ 2390' KB

#### PLUGGING PROCEDURE

Enter the well w/tbg and wash to TD. If the well is not dead, circulate mud with sufficient weight to kill the well. Pump a balanced cement plug using 260 sacks across the Douglas Creek Member of the Green River Formation from TD to at least 300 ft above the upper most perfs. The production csg will be perforated for two feet using 4 SPF at a point 100 ft below the surface csg shoe. Circulation will be established to surface and cement will be circulated to fill the production csg & the annulus from the perforations to surface using 100 sx of class-G cement. The top of the second cement plug will be at the surface & the bottom will be 100 ft below the surface csg shoe. A P&A marker will be set to identify the location.

#### PERFORATION RECORD

3/9/94	4104' - 4116'	(12')	4 SPF	<b>Y3</b>
3/9/94	4138' - 4144'	( 6')	4 SPF	Y3
Commu	nication between 4104	'-4116' &	4138' - 4	144'
3/7/94	4656' - 4662'	( 6')	4 SPF	R2
3/2/94	5444' - 5463'	(19')	4 SPF	B1

Green River Formation 1450 to 5400 ft.

4104' - 16'

Plug No.1 TD to 3804 ft. 260 sx of Class-G Cement

4138' - 44'

4656' - 62'

100

5444' - 63'

Douglas Creek Member 4550 to 5400 ft. Wasatch Fm. Transition 5400 to 5950 ft.

PBTD @ 5633.74' KB TD @ 5700' KB

Wasatch Formation 5950 ft.